
THE VILLAGE OF TINLEY PARK

Cook County, Illinois

Will County, Illinois

**RESOLUTION
NO. 2018-R-046**

**A RESOLUTION APPROVING A CONTRACT BETWEEN THE VILLAGE OF TINLEY PARK
AND IROQUOIS PAVING CORPORATION FOR THE TINLEY PARK CONVENTION CENTER
PARKING LOT IMPROVEMENTS**

**JACOB C. VANDENBERG, PRESIDENT
KRISTIN A. THIRION, VILLAGE CLERK**

**MICHAEL J. PANNITTO
BRIAN H. YOUNKER
CYNTHIA A. BERG
WILLIAM P. BRADY
MICHAEL W. GLOTZ
JOHN A. CURRAN
Board of Trustees**

RESOLUTION NO. 2018-R-046

A RESOLUTION APPROVING A CONTRACT BETWEEN THE VILLAGE OF TINLEY PARK AND IROQUOIS PAVING CORPORATION FOR THE TINLEY PARK CONVENTION CENTER PARKING LOT IMPROVEMENTS

WHEREAS, the Village of Tinley Park, Cook and Will Counties, Illinois, is a Home Rule Unit pursuant to the Illinois Constitution of 1970; and

WHEREAS, the Corporate Authorities of the Village of Tinley Park, Cook and Will Counties, Illinois, have considered entering into an Agreement with Iroquois Paving Corporation., a true and correct copy of such Agreement being attached hereto and made a part hereof as **EXHIBIT 1**; and

WHEREAS, the Corporate Authorities of the Village of Tinley Park, Cook and Will Counties, Illinois, have determined that it is in the best interests of said Village of Tinley Park that said Agreement be entered into by the Village of Tinley Park;

NOW, THEREFORE, Be It Resolved by the President and Board of Trustees of the Village of Tinley Park, Cook and Will Counties, Illinois, as follows:

Section 1: The Preambles hereto are hereby made a part of, and operative provisions of, this Resolution as fully as if completely repeated at length herein.

Section 2: That this President and Board of Trustees of the Village of Tinley Park hereby find that it is in the best interests of the Village of Tinley Park and its residents that the aforesaid "Agreement" be entered into and executed by said Village of Tinley Park, with said Agreement to be substantially in the form attached hereto and made a part hereof as **EXHIBIT 1**.

Section 3: That the President and Clerk of the Village of Tinley Park, Cook and Will Counties, Illinois are hereby authorized to execute for and on behalf of said Village of Tinley Park the aforesaid Agreement.

Section 4: That this Resolution shall take effect from and after its adoption and approval.


ADOPTED this 17th day of July, 2018, by the Corporate Authorities of the Village of Tinley Park on a roll call vote as follows:

AYES: Younker, Pannitto, Berg, Brady, Glotz, Curran

NAYS: None

ABSENT: None

APPROVED this 17th day of July, 2018, by the President of the Village of Tinley Park.


Village President

ATTEST:

Deputy Village Clerk

STATE OF ILLINOIS)
COUNTY OF COOK) SS
COUNTY OF WILL)

CERTIFICATE

I, KRISTIN A. THIRION, Village Clerk of the Village of Tinley Park, Counties of Cook and Will and State of Illinois, DO HEREBY CERTIFY that the foregoing is a true and correct copy of Resolution No. 2018-R-046, “A RESOLUTION APPROVING A CONTRACT BETWEEN THE VILLAGE OF TINLEY PARK AND IROQUOIS PAVING CORPORATION FOR THE TINLEY PARK CONVENTION CENTER PARKING LOT IMPROVEMENTS,” which was adopted by the President and Board of Trustees of the Village of Tinley Park on July 17, 2018.

IN WITNESS WHEREOF, I have hereunto set my hand and affixed the corporate seal of the Village of Tinley Park this _____ day of _____ 2018.

KRISTIN A. THIRION, VILLAGE CLERK

EXHIBIT 1

IROQUOIS PAVING CORPORATION AGREEMENT



VILLAGE OF TINLEY PARK
Tinley Park Convention Center Parking Lot Improvements
REL Project 18-R0455 . 01

VILLAGE OF TINLEY PARK
COOK & WILL COUNTIES, ILLINOIS
NOTICE TO CONTRACTORS

The Village of Tinley Park will receive sealed proposals for the following improvements at the Clerk's office, 16250 South Oak Park Avenue, Tinley Park, Illinois 60477, until 9:30 AM on Thursday July 5, 2018.

TINLEY PARK CONVENTION CENTER PARKING LOT IMPROVEMENTS

Proposals will be publicly read aloud on Thursday July 5, 2018 after 9:31 AM. No bid shall be withdrawn after the opening of the proposals without the consent of the President and Board of Trustees for a period of ninety days after the scheduled time of closing bids.

All proposals shall be sealed in an envelope, addressed to the Village of Tinley Park, attention Clerk's office. The name and address of the bidder and the name of the project shall also appear on the outside of the envelope. Proposals must be submitted on the forms provided by the Engineer.

The Bid Documents, including specifications, are on file at the office of the Engineer, Robinson Engineering, Ltd., 17000 South Park Avenue, South Holland Illinois 60473, (phone 708-331-6700), and may be obtained from the Engineer's office upon payment of Fifty Dollars (\$50.00) for each paper copy and/or Ten Dollars (\$10.00) per CD format. The bid documents will be issued until 4:30 PM on the last business day preceding the bid. No refund will be made for documents received from the Engineer.

A certified check/bank draft drawn on a solvent bank or a bid bond, payable without condition to the Village of Tinley Park in an amount not less than ten percent (10%) of the bid shall be submitted with each proposal, as a guarantee that, if the proposal is accepted, a contract will be entered into and the performance of the contract is properly secured.

A performance bond in a sum equal to one hundred percent (100%) of the amount of the bid, with sureties to be approved by the President and Board of Trustees for the faithful performance of the contract must be furnished by the successful bidder. All bids or proposals shall contain an offer to furnish bond upon acceptance of such bid or proposal.

The right is reserved to reject any or all proposals, to waive technicalities, to postpone the bid opening, or to advertise for new proposals, if in the judgment of the President and Board of Trustees their best interests will be promoted thereby.

The contractor will be required to pay not less than the prevailing wage rates on this project as established by the United States Department of Labor. He shall also comply with all applicable Federal, State and local regulations.

The Village of Tinley Park Local Vendor Purchasing Policy provides local vendors with preferential treatment when competing for contracts with the Village. A local vendor is defined as a business that has an actual business location within the Village of Tinley Park and is licensed by the Village. As such, when considering contracts, the Village of Tinley Park reserves the right to forego the lowest and responsible bid in favor of a local vendor under the following circumstances:

<u>Contract Value</u>	<u>Range (up to a maximum of)</u>
\$0-\$250,000	5%
\$250,000-\$500,000	4%
\$500,000-\$750,000	3%
\$750,000-\$1,000,000	2%
\$1,000,000-\$2,000,000	1%

Responsible bidders are determined pursuant to the criteria set forth pursuant to the criteria set forth in the Village's Responsible Bidder Ordinance No. 2009-O-002.

Bidder qualifications and experience will also be included in the basis for determining the lowest responsible bidder. Prequalifications will be required to be submitted to the engineer by all potential bidders. If in the opinion of the engineer and the President and Board of Trustees, an applicant would not be able to serve the best interest of the Village, a proposal will not be issued to the applicant.

President and Board of Trustees
Village of Tinley Park
Cook & Will Counties, Illinois

PROPOSAL
and
CONTRACT

PROPOSAL

TO THE OWNER, Village of Tinley Park

1. Proposal of Iroquois Paving Corporation
(name and address of bidder)
1889 E US Hwy 24, PO Box 466, Watseka IL 60970
curtis.luecke@iroqpavcorp.com
(email address of bidder)

for the improvement described in the NOTICE TO CONTRACTORS.

2. In submitting this proposal, the undersigned declares that the only persons or parties interested in the proposal as principals are those named herein; and that proposal is made without collusion with any other person, firm or corporation.
3. The undersigned further declares that he has carefully examined the proposal, plans, specifications, form of contract and contract bond, and special provisions (if any), and that he has inspected in detail the site of the proposed work, and that he has familiarized himself with all of the local conditions affecting the contract and the detailed requirements of construction, and understands that in making this proposal he waives all right to plead any misunderstanding regarding the same.
4. The undersigned further understands and agrees that if this proposal is accepted, he is to furnish and provide all necessary machinery, tools, apparatus and other means of construction, and to do all of the work, and to furnish all of the materials specified in the contract, except such materials as are to be furnished by the Owner, in the manner and at the time therein prescribed, and in accordance with the requirements therein set forth, and is fully responsible for the construction means, methods, techniques, sequences and safety procedures and programs incident thereto.
5. The undersigned declares that he understands that the quantities mentioned are approximate only and that they are subject to increase or decrease; that he will take in full payment therefore the amount and the summation of the actual quantities, as finally determined, multiplied by the unit prices shown in the schedule of prices contained herein.
6. The undersigned further agrees that the unit prices submitted herewith are for the purpose of obtaining a gross sum, and for use in computing the value of extras and deductions; if there is a discrepancy between the gross sum bid and that resulting from the summation of the quantities multiplied by their respective unit prices, the latter shall apply.
7. The undersigned further agrees that if the Owner decides to extend or shorten the improvement, or otherwise alter it by extras or deductions, including the elimination of any one or more of the items, as provided in the specifications, he will perform the work as altered, increased or decreased at the contract unit prices.

8. The undersigned further agrees that the Owner may at any time during the progress of work covered by this contract order other work or materials incidental thereto and that all such work and materials as do not appear in the proposal or contract as a specific item accompanied by a unit price, and which are not included under the bid price for other items in this contract, shall be performed as extra work, and that he will accept as full compensation therefore the actual cost plus fifteen per cent (15%), the actual cost to be determined as provided in the specifications.
9. The undersigned further agrees to execute a contract for this work and present the same to the Owner within fifteen (15) days after the date of notice of the award of the contract to him.
10. The undersigned further agrees that he and his surety will execute and present within fifteen (15) days after the date of notice of the award of contract, a contract bond satisfactory to and in the form prescribed by the Owner, in the penal sum of the full amount of the contract, guaranteeing the faithful performance of the work in accordance with the terms of the contract.
11. The undersigned further agrees to begin work not later than ten (10) days after the execution and approval of the contract and contract bond, unless otherwise provided, and to prosecute the work in such manner and with sufficient materials, equipment, labor and safety precautions as will insure its completion within the time limit specified herein, it being understood and agreed that the completion within the time limit is an essential part of the contract. The undersigned agrees to complete the work within _____ calendar days after the date of the execution of the contract by both parties, or by _____ if this is a completion day contract, unless additional time shall be granted by the Engineer in accordance with the provisions of the specifications. In case of failure to complete the work within the time names herein or within such extra time as may have been allowed by extensions, the undersigned agrees that the Owner shall withhold from such sums as may be due him under the terms of this contract, the costs set forth in the specifications, which cost shall be considered and treated not as a penalty, but as damages due the Owner from the undersigned by reason of inconvenience to the public, added cost of engineering and construction observation, maintenance of detours, and other items which have caused an expenditure of public funds resulting from the failure of the undersigned to complete the work within the time specified in the contract.
12. Accompanying this proposal is a bank draft, bank cashier's check, certified check or bid bond, complying with the requirements of the specifications, made payable to: _____

*per
Special
provisions*

The amount of the bond, check or draft is _____
_____ bid bond (\$ _____ bid bond _____).

If the proposal and the undersigned shall fail to execute a contract and contract bond as required herein, it is hereby agreed that the amount of the check or draft substituted in lieu thereof, shall become the property of the Owner, and shall be considered as payment of damages due to delay and other causes suffered by the Owner because of the failure to execute said contract and contract bond; otherwise said check or draft substituted in lieu thereof shall be returned to the undersigned.

ATTACH BANK DRAFT, BID BOND, BANK CASHIER'S
CHECK OR CERTIFIED CHECK HERE

In the event that one check, bond, or draft is intended to cover two or more proposals, the amount must be equal to the sum of the proposal guarantees of the individual sections covered.

13. The undersigned submits herewith his schedule of prices covering the work to be performed under this contract; he understands that he must show in the schedule the unit prices for which he proposes to perform each item of work; that the extensions must be made by him; and that if not so done, his proposal may be rejected as irregular.
14. The undersigned firm certifies that it is not barred from bidding on this contract as a result of a conviction for the violation of State laws prohibiting bid-rigging or bid-rotating.



AIA Document A310tm - 2010

Bid Bond

Contractor:

(Name, Legal Status and Address)
Iroquois Paving Corporation
P O Box 466
Watseka IL 60970

Surety:

(Name, Legal Status and Principal Place of Business)
Travelers Casualty and Surety Company of America
One Tower Square
Hartford CT 06183-6014

Owner:

(Name, Legal Status and Address)
Village of Tinley Park
16250 South Oak Park Avenue
Tinley Park, IL 60477

Bond Amount: Ten percent of bid

Project:

(Name, location or address, and Project number, if any)
Tinley Park Convention Center Parking Lot Improvements

The Contractor and Surety are bound to the Owner in the amount set forth above, for the payment of which the Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, as provided herein. The conditions of this Bond are such that if the Owner accepts the bid of the Contractor within the time specified in the bid documents, or within such time period as may be agreed to by the Owner and Contractor, and the Contractor either (1) enters into a contract with the Owner in accordance with the terms of such bid, and give such bond or bonds as may be Specified in the bidding or Contract Documents, with a surety admitted in the jurisdiction of the Project and otherwise acceptable to the Owner, for the faithful performance of such Contract and for the prompt payment of labor and material furnished in the prosecution thereof; or (2) pays to the Owner the difference, not to exceed the amount of this Bond, between the amount specified in said bid and such larger amount for which the Owner may in good faith contract with another party to perform the work covered by said bid, then this obligation shall be null and void, otherwise to remain in full force and effect. The Surety hereby waived any notice of an agreement between the Owner and Contractor to extend the time in which the Owner may accept the bid. Waiver of notice by the Surety shall not apply to any extension exceeding sixty (60) days in the aggregate beyond the time for acceptance of bids specified in the bid documents, and the Owner and Contractor shall obtain the Surety's consent for an extension beyond sixty (60) days.

If this Bond is issued in connection with a subcontractor's bid to a Contractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

When this Bond has been furnished to comply with a statutory or other legal requirement in the location of the Project, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.


ADDITIONS AND DELETIONS:

The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An *Additions and Deletions Report* that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.


The document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

Signed and sealed this 5th day of July, 2018




(Witness)




(Witness)

Iroquois Paving Corporation
(Contractor as Principal) (Seal)



(Title) President

Travelers Casualty and Surety Company of America
(Surety) (Seal)



(Title) Tim R Patton Attorney-in-Fact

State of Illinois

} ss:

County of Macon

On 5th day of July, 2018 before me, a Notary Public in and for said County and State, residing therein, duly commissioned and sworn,
personally appeared **Tim R Patton**

known to me to be Attorney-in-Fact of Travelers Casualty and Surety Company of America
the corporation described in and that executed the within and foregoing instrument, and known to me to be the person who executed the said
instrument in behalf of the said corporation, and he duly acknowledged to me that such corporation executed the same.

IN WITNESS WHEREOF, I have hereunto set my hand and affixed my official seal, the day and year stated in this certificate above.

Glenda Hoffman
(Notary Public)



CONTRACTOR'S STATEMENT

1. Do you have sufficient knowledge of Drawings and Specifications of the work covered by this Contract to warrant submitting a Proposal for this work?
Yes

2. (a) Have you done work of this nature? Yes
(b) To what extent? (Dollar value) \$10,000,000+
(c) For whom? State of Illinois

3. Do you have sufficient equipment to perform this work? Yes
If so, list major items: Asphalt plant, paver, roller, milling machine, excavators, semi trucks, pick up trucks

4. Give Bank reference: Prospect Bank,
Address: 177 W Wood St, Paris, IL 61944

5. List names and addresses of major suppliers:
BP Products North America Inc., 12713 Collections Center Drive Chicago, IL 60693
County Materials Corporation P.O. Box 100 Marathon, WI 54448--0100
VCNA Prairie LLC - 5185 Paysphere Circle Chicago, IL 60674

6. Have you ever had, or do you now have, funds withheld for non-completion of work to the satisfaction of any municipality? No
(a) If so where? N/A
(b) For what reason? N/A

7. Have you ever been disqualified by a Governmental Agency for failure to satisfactorily complete a public improvement? No

CONTRACTOR'S STATEMENT (cont.)

- 8. Have you ever been cited for failing to withhold or report payroll deductions for Federal Income Tax? No

- 9. Have you ever been cited by the Federal Government for any violation of the Copeland Act (Anti-kick-back Law)? No


- 10. If awarded contract, work will begin in _____ calendar days.
within 30 days of contract execution

CERTIFICATE OF ELIGIBILITY TO BID

I, Joseph A. Cowan (contractor), pursuant to section 33E-11 of the Illinois Criminal Code of 1961 as amended, hereby certifies that neither (he, she, it) nor any of (his, her, its) partners, officers, or owners of (his, her, its) business has been convicted in the past five (5) years of the offense of bid-rigging under section 33E-3 of the Illinois Criminal Code of 1961 as amended and that neither (he, she, it) nor any of (his, her, its) business has ever been convicted of the offense of bid-rotating under section 33E-4 of the Illinois Criminal Code of 1961 as amended.

IROQUOIS PAVING CORPORATION

Date: 7/5/18

By:  _____
(Name of Contractor)

President
(Title)



SCHEDULE OF PRICES

Local Agency Village of Tinley Park
Location Convention Center Parking Lot Improvements
Description OPTION 2- 4" grind southeast parking lot, 2" grind main lot and resurface southeast and main lot

The undersigned submits herewith his schedule of prices covering the work to be performed under this contract; he understands that he must show in the schedule the unit prices for which he proposes to perform each item of work; that the extensions must be made by him, and if not so done, his proposal may be rejected as irregular.

Schedule for Single Bid

(For complete information covering these items, see plans and specifications.)

Bidder's Proposal for making Entire Improvements					383,948.90
Item No.	Items	Unit	Quantity	Unit Price	Total
1	TOPSOIL FURNISH AND PLACE, 4" (SPECIAL)	SQ YD	75	15.00	1125.00
2	PREPARATION OF BASE	SQ YD	2,500	0.01	25.00
3	AGGREGATE BASE REPAIR	TON	840	20.00	16800.00
4	BITUMINOUS MATERIALS (PRIME COAT)	POUND	20,430	0.01	204.30
5	BITUMINOUS MATERIALS (TACK COAT)	POUND	9,590	0.01	95.90
6	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,150	64.50	74,175.00
7	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2,770	68.00	188,360.00
8	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	16,770	1.75	29,347.50
9	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	9,080	2.45	22,246.00
10	COMBINATION CURB AND GUTTER REMOVAL	FOOT	200	14.00	2,800.00
11	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	200	42.00	8400.00
12	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,100	2.45	2695.00
13	PAINT PAVEMENT MARKING - LINE 4"	FOOT	28,000	0.50	14000.00
14	PAINT PAVEMENT MARKING - LINE 6"	FOOT	800	0.80	640.00
15	PAINT PAVEMENT MARKING - LINE 24"	FOOT	100	2.85	285.00
16	REMOVE EXISTING PARKING BLOCKS	EACH	20	0.01	0.20
17	CONCRETE PARKING BLOCKS	EACH	20	150.00	3000.00
18	SODDING, SPECIAL	SQ YD	75	15.00	1125.00
19	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	25	425.00	10625.00
20	DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED	EACH	5	1000.00	5000.00
21	RUBBER ADJUSTING RINGS	EACH	50	35.00	1750.00
22	STEEL ADJUSTING RINGS	EACH	10	125.00	1250.00

SIGNATURES

(If an individual)

Signature of Bidder

Business Address

(If a co-partnership)

Firm Name (SEAL)


Signed by (SEAL)

Business Address

Insert
Names and
Addresses of
All Members
of the Firm
.....
.....
.....
.....

(If a corporation)

Corporate Name Iroquois Paving Corporation

Signed By 


President

Business Address 1889 E. US Hwy. 24, P.O. Box 466

(Corporate Seal)

Insert
Names of
Officers
President Joseph A. Cowan

Secretary	<u>John D. Lynch</u>
Treasurer	<u>John D. Lynch</u>

Attest. 

Secretary

Phone Number 815-432-5211

BIDDER'S CERTIFICATE

The undersigned, having executed the attached bid for the construction of:

Village of Tinley Park Convention Center Parking Lot Improvements
Name of Project

for the Village/City/Town of Tinley Park, County of Cook,

State of Illinois hereby certifies that he has read all of the Contract

Documents, including the Notice to Bidders, Instructions to Bidders, Proposal Forms,

General conditions of the contract, Detail Specifications, Forms of contract, Form of

Performance Bond and Form of Maintenance Bond, and that he has examined the plans

and that his proposal for the work is based on the conditions and requirements therein;

and should the contract be awarded to him, he agrees to execute the work in strict

accordance therewith, including compliance with the Insurance Requirements of the

General Conditions.

Name of Bidder

IROQUOIS PAVING CORPORATION

By: 

Company Name

Date: 7/5/18

CONTRACT

1. THIS AGREEMENT, made and concluded this 17th day of July, 2018, between the Village of Tinley Park, acting by and through its Mayor & Board of Trustees known as the party of the first part, and Iroquois paving Corporation, his/their executors, administrators, successors or assigns, known as the party of the second part.

2. WITNESSETH: That for and in consideration of the payment and agreements mentioned in the Proposal hereto attached, to be made and performed by the party of the first part, and according to the terms expressed in the Bond referring to these presents, the party of the second part agrees with said party of the first part at his/their own proper cost and expense to do all the work, furnish all materials and all labor necessary to complete the work in accordance with the plans and specifications hereinafter described, and in full compliance with all of the plans of this agreement and the requirements of the Engineer under it.

3. And it is also understood and agreed that the Notice to Contractors, proposals, contract bond, General Requirements and Covenants (Division I), Technical Specifications (Division II), Special Provisions (Division III) and Standard drawings (Division IV), in addition to any specific plans and specifications upon which the contractor's proposal is based, are all incorporated by reference into this contract and are therefore made a part hereof.

4. IN WITNESS WHEREOF, the said parties have executed these presents on the date above mentioned.

FOR THE VILLAGE OF TINLEY PARK, IL
(Party of the First Part)

By: [Signature]

Title: Jacob C. Vandenberg, Mayor

Attest: [Signature]

Title: Kristin A. Thirion, Clerk

MUNICIPAL SEAL

Executed by Municipality

FOR THE CONTRACTOR
(Party of the Second Part)

Iroquois Paving Corporation

By: [Signature]

Title: President

Attest: [Signature]

Title: Vice-President

CORPORATE SEAL

Executed by Contractor

CONTRACT BOND

KNOWN ALL MEN BY THESE PRESENTS, that we, Iroquois Paving Corporation
 _____, a corporation organized under the laws of the State of
Delaware, and licensed to do business in the State of Illinois, as principal, and
Travelers Casualty and Surety Company of America, a corporation organized and existing under the laws of the State
 of Connecticut, with authority to do business in the State of Illinois, as Surety, are held
 and firmly bound unto the Village of Tinley Park, State of Illinois, in the penal sum of
Three Hundred and Eight Three Thousand Nine Hundred Forty Eight & 90/100 ---
Dollars (\$383,948.90 ---), lawful money of the United States, well and truly to be paid
 unto said Village of Tinley Park, for the payment of which we bind ourselves, our successors
 and assigns, jointly, severally, and firmly by these presents.

THE CONDITION OF THE FOREGOING OBLIGATION IS SUCH that whereas, the said Principal has
 entered into a written contract with an Owner which is the Village of Tinley Park and acts through its
Mayor & Board of Trustees or the construction of the work designated
REL#18-R0455- Tinley Park Convention Center Parking Lot Improvements, which
 contract hereby is referred to and made a part hereof, as if written herein in length, and whereby the said Principal
 has promised and agreed to perform said work in accordance with the terms of said Contract, and has promised
 to pay all sums of money due for any labor, materials, apparatus, fixtures or machinery furnished to such Principal
 for the purpose of performing such work and has further agreed to pay all direct and indirect damages to any
 person, firm, company, or corporation suffered or sustained on account of the performance of such work, for any
 reason whatsoever, during the time thereof and until such work is completed and accepted; and has further agreed
 that this bond shall inure to the benefit of any person, firm, company or corporation, to whom any money may
 be due from the Principal, subcontractor or otherwise, for any such labor, materials, apparatus, fixtures or
 machinery so furnished, and that suit may be maintained on such bond by any such person, firm, company or
 corporation, for the recovery of any such money.


NOW, THEREFORE, if the said Principal shall well and truly perform said work in accordance with the
 terms of said contract, and shall pay all sums of money due or to become due for any labor, materials, apparatus,
 fixtures or machinery furnished to him for the purpose of constructing such work, and shall commence and
 complete the work within the time prescribed in said contract, and shall pay and discharge all damages, direct and
 indirect, that may be suffered or sustained on account of

Executed by Contractor


such work, for any reason whatsoever, during the time of the performance thereof and until the said work shall have been accepted, and shall hold the aforesaid Owner and its or his agents harmless on account of any such damages, and shall in all respects fully and faithfully comply with all the provisions, conditions and requirements of said contract, then this obligation to be void, otherwise to remain in full force and effect.

IN WITNESS WHEREOF, we have duly executed the foregoing obligation this 24th day of July A.D. 20 18

Contractor's corporate name: Iroquois Paving Corporation


By: 
President

CORPORATE SEAL


Attest: 
Attestor's Title: VP

Executed by Contractor

Surety's corporate name: Travelers Casualty and Surety Company of America

By: 
Attorney-in-fact Blake E Allison


CORPORATE SEAL

By: 
Attorney-in-fact

Executed by Surety for Contractor

APPROVED THIS 17th DAY OF July A.D. 20 18


VILLAGE OF TINLEY PARK, IL

By: 
Title: Jacob C. Vandenberg, Mayor

Executed by Municipality

ATTEST FOR VILLAGE OF TINLEY PARK, IL

MUNICIPAL SEAL

By: 
Title: Kristin A. Thirion, Clerk

STATE OF Illinois)
) SS
COUNTY OF Macon)

I, Stacy R Standley (Notary), a Notary Public in and for said County in the State aforesaid, do hereby certify that Joseph A Cowan (President) and John D Lynch (Secretary), to me personally known to be president and secretary, respectively, of Iroquois Paving Corporation (Contractor), a corporation, and also known to me to be the persons whose names are subscribed to the foregoing instrument, appeared before me this day in person and acknowledged that as such president and secretary respectively they signed, sealed and delivered the said instrument as the free and voluntary act of said Corporation, for the uses and purposes therein set forth, and that they were duly authorized to execute the same by the Board of Directors of said Corporation.

GIVEN UNDER MY HAND AND NOTARIAL SEAL THIS 24th DAY OF July A.D. 2018

SEAL

Stacy R Standley
Notary Public




STATE OF Illinois)
) SS
COUNTY OF Macon)

I, Stacy R Standley (Notary), a Notary Public in and for said County in the State aforesaid, do hereby certify that Blake E Allison (Attorney-in-Fact) who is personally known to me to be the same person who signed the above and foregoing instrument as the Attorney in Fact for Travelers Casualty and Surety Company of America (Surety) appeared before me this day in person and acknowledged that he signed the name of Blake E Allison (Principal) thereto, as his Principal, and his own name as Attorney in Fact, as the free and voluntary act of his said Principal for the uses and purposes therein set forth, and that he executed the said instrument under authority given him by said Principal.

GIVEN UNDER MY HAND AND NOTARIAL SEAL THIS 24th DAY OF July A.D. 2018

SEAL

Stacy R Standley
Notary Public





**Travelers Casualty and Surety Company of America
Travelers Casualty and Surety Company
St. Paul Fire and Marine Insurance Company**

POWER OF ATTORNEY

KNOW ALL MEN BY THESE PRESENTS: That Travelers Casualty and Surety Company of America, Travelers Casualty and Surety Company, and St. Paul Fire and Marine Insurance Company are corporations duly organized under the laws of the State of Connecticut (herein collectively called the "Companies"), and that the Companies do hereby make, constitute and appoint **Blake E. Allison, of Forsyth, Illinois**, their true and lawful Attorney-in-Fact to sign, execute, seal and acknowledge any and all bonds, recognizances, conditional undertakings and other writings obligatory in the nature thereof on behalf of the Companies in their business of guaranteeing the fidelity of persons, guaranteeing the performance of contracts and executing or guaranteeing bonds and undertakings required or permitted in any actions or proceedings allowed by law.

IN WITNESS WHEREOF, the Companies have caused this instrument to be signed, and their corporate seals to be hereto affixed, this 3rd day of February, 2017.



State of Connecticut

City of Hartford ss.

By:
Robert L. Raney, Señor Vice President

On this the 3rd day of February, 2017, before me personally appeared **Robert L. Raney**, who acknowledged himself to be the Senior Vice President of Travelers Casualty and Surety Company of America, Travelers Casualty and Surety Company, and St. Paul Fire and Marine Insurance Company, and that he, as such, being authorized so to do, executed the foregoing instrument for the purposes therein contained by signing on behalf of the corporations by himself as a duly authorized officer.

In Witness Whereof, I hereunto set my hand and official seal.

My Commission expires the 30th day of June, 2021



Marie C. Tetreault, Notary Public

This Power of Attorney is granted under and by the authority of the following resolutions adopted by the Boards of Directors of Travelers Casualty and Surety Company of America, Travelers Casualty and Surety Company, and St. Paul Fire and Marine Insurance Company, which resolutions are now in full force and effect, reading as follows:

RESOLVED, that the Chairman, the President, any Vice Chairman, any Executive Vice President, any Senior Vice President, any Vice President, any Second Vice President, the Treasurer, any Assistant Treasurer, the Corporate Secretary or any Assistant Secretary may appoint Attorneys-in-Fact and Agents to act for and on behalf of the Company and may give such appointee such authority as his or her certificate of authority may prescribe to sign with the Company's name and seal with the Company's seal bonds, recognizances, contracts of indemnity, and other writings obligatory in the nature of a bond, recognizance, or conditional undertaking, and any of said officers or the Board of Directors at any time may remove any such appointee and revoke the power given him or her; and it is

FURTHER RESOLVED, that the Chairman, the President, any Vice Chairman, any Executive Vice President, any Senior Vice President or any Vice President may delegate all or any part of the foregoing authority to one or more officers or employees of this Company, provided that each such delegation is in writing and a copy thereof is filed in the office of the Secretary; and it is

FURTHER RESOLVED, that any bond, recognizance, contract of indemnity, or writing obligatory in the nature of a bond, recognizance, or conditional undertaking shall be valid and binding upon the Company when (a) signed by the President, any Vice Chairman, any Executive Vice President, any Senior Vice President or any Vice President, any Second Vice President, the Treasurer, any Assistant Treasurer, the Corporate Secretary or any Assistant Secretary and duly attested and sealed with the Company's seal by a Secretary or Assistant Secretary; or (b) duly executed (under seal, if required) by one or more Attorneys-in-Fact and Agents pursuant to the power prescribed in his or her certificate or their certificates of authority or by one or more Company officers pursuant to a written delegation of authority; and it is

FURTHER RESOLVED, that the signature of each of the following officers: President, any Executive Vice President, any Senior Vice President, any Vice President, any Assistant Vice President, any Secretary, any Assistant Secretary, and the seal of the Company may be affixed by facsimile to any Power of Attorney or to any certificate relating thereto appointing Resident Vice Presidents, Resident Assistant Secretaries or Attorneys-in-Fact for purposes only of executing and attesting bonds and undertakings and other writings obligatory in the nature thereof, and any such Power of Attorney or certificate bearing such facsimile signature or facsimile seal shall be valid and binding upon the Company and any such power so executed and certified by such facsimile signature and facsimile seal shall be valid and binding on the Company in the future with respect to any bond or understanding to which it is attached.

I, **Kevin E. Hughes**, the undersigned, Assistant Secretary of Travelers Casualty and Surety Company of America, Travelers Casualty and Surety Company, and St. Paul Fire and Marine Insurance Company, do hereby certify that the above and foregoing is a true and correct copy of the Power of Attorney executed by said Companies, which remains in full force and effect.

Dated this 24th day of July, 2018



Kevin E. Hughes, Assistant Secretary

**To verify the authenticity of this Power of Attorney, please call us at 1-800-421-3880.
Please refer to the above-named Attorney-in-Fact and the details of the bond to which the power is attached.**



CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY) 07/24/2018

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must have ADDITIONAL INSURED provisions or be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement.

PRODUCER: J.L. Hubbard Insurance and Bonds, 1090 South Route 51, Forsyth, IL 62535. CONTACT NAME: Holli Schorey, PHONE: (217) 877-3344, FAX: (217) 877-0795, E-MAIL ADDRESS: hschorey@jlhubbard.com. INSURER(S) AFFORDING COVERAGE: INSURER A: West Bend Mutual Insurance Company 15350, INSURER B: Great American Insurance Group 16691.

COVERAGES CERTIFICATE NUMBER: REVISION NUMBER:

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES.

Table with columns: INSR LTR, TYPE OF INSURANCE, ADDL INSD, SUBR WVD, POLICY NUMBER, POLICY EFF (MM/DD/YYYY), POLICY EXP (MM/DD/YYYY), LIMITS. Rows include Commercial General Liability, Automobile Liability, Umbrella Liab, Workers Compensation and Employers' Liability, Pollution Liability, and Rented Equipment.

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required) RE: REL#18-R0455 Convention Center Parking Lot Improvements Village of Tinley Park and Robinson Engineering Inc are named as additional insured on a primary non-contributory basis...

CERTIFICATE HOLDER: Village of Tinley Park, 16250 S Oak Park Ave, Tinley Park, IL 60477. CANCELLATION: SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS. AUTHORIZED REPRESENTATIVE: [Signature]

THIS ENDORSEMENT CHANGES THE POLICY. PLEASE READ IT CAREFULLY.

ADDITIONAL INSURED – CONTRACTOR'S BLANKET

This endorsement modifies insurance provided under the following:

COMMERCIAL GENERAL LIABILITY COVERAGE PART

A. WHO IS AN INSURED (Section II) is amended to include as an additional insured any person or organization whom you are required to add as an additional insured on this policy under a written contract or written agreement.

The written contract or written agreement must be:

1. Currently in effect or becoming effective during the term of this policy; and
2. Signed by all parties to the written contract or written agreement prior to the "bodily injury," "property damage," "personal injury and advertising injury."

B. The insurance provided to the additional insured is limited as follows:

1. That person or organization is only an additional insured with respect to liability for "bodily injury," "property damage" or "personal and advertising injury" caused in whole or in part, by:
 - a. Your premises; or
 - b. Your negligent acts or omissions in connection with "Your work" for that additional insured.

However:

- a. The insurance afforded to such additional insured only applies to the extent permitted by law; and
 - b. If coverage provided to the additional insured is required by a contract or agreement, the insurance afforded to such additional insured will not be broader than that which you are required by the written contract or written agreement to provide such additional insured.
2. The Limits of Insurance applicable to the additional insured are those specified in the written contract or written agreement or in the Declarations for this policy, whichever is less. These Limits of Insurance are inclusive and not in addition to the Limits of Insurance shown in the Declarations.
 3. Except when required by written contract or written agreement, the coverage provided to the additional insured by this endorsement does not apply to:

a. "Bodily injury" or "property damage" occurring after:

- (1) All work on the project (other than service, maintenance or repairs) to be performed by or on behalf of the additional insured at the site of the covered operations has been completed; or
- (2) That portion of "your work" out of which the injury or damage arises has been put to its intended use by any person or organization other than another contractor or subcontractor engaged in performing operations for a principal as part of the same project.

b. "Bodily injury" or "property damage" arising out of acts or omissions of the additional insured other than in connection with the general supervision of "your work."

4. The insurance provided to the additional insured does not apply to "bodily injury," "property damage," "personal injury and advertising injury" arising out of an architect's, engineer's, or surveyor's rendering of or failure to render any professional services including;

- a. The preparing, approving, or failing to prepare or approve maps, shop drawings, opinions, reports, surveys, field orders, change orders or drawings and specifications; and
- b. Supervisory, or inspection activities performed as part of any related architectural or engineering activities.

This exclusion applies even if the claims against any insured allege negligence or other wrongdoing in the supervision, hiring, employment, training or monitoring of others by that insured, if the "occurrence" which caused the "bodily injury" or "property damage", or the offense which caused the "personal and advertising injury", involved the rendering of, or the failure to render, any professional architectural, engineering or surveying services.

C. As respects the coverage provided under this endorsement, Paragraph 4.b. **SECTION IV – COMMERCIAL GENERAL LIABILITY CONDITIONS** is amended with the addition of the following:

4. Other insurance

b. Excess insurance

This insurance is excess over:

Any other valid and collectible insurance procured by or on behalf of the additional insured whether primary, excess, contingent or on any other basis unless a written contract specifically requires that this insurance be either primary or primary and noncontributing. Where required by written contract, we will consider any other insurance procured by the additional insured for injury or damage covered by this endorsement to be excess and noncontributing with this insurance.

If no written contract specifically requires primary or noncontributory coverage, then this insurance is excess and as a condition of coverage, the additional insured shall be obligated to tender the defense and indemnity of every claim or suit to all other insurers that may provide coverage to the additional insured, whether on a contingent, excess or primary basis.

When this insurance is excess, we will have no duty under Coverage **A.** and Coverage **B.** to defend the insured against any "suit" if any other insurer has a duty to defend the insured against that "suit". If no other insurer defends, we will undertake to do so, but we will be entitled to the insured's rights against all those other insurers.

THIS ENDORSEMENT CHANGES THE POLICY. PLEASE READ IT CAREFULLY.

DESIGNATED INSURED


This endorsement modifies insurance provided under the following:

BUSINESS AUTO COVERAGE FORM
GARAGE COVERAGE FORM
MOTOR CARRIER COVERAGE FORM
TRUCKERS COVERAGE FORM

With respect to coverage provided by this endorsement, the provisions of the Coverage Form apply unless modified by this endorsement.

This endorsement identifies person(s) or organization(s) who are "insureds" under the Who Is An Insured Provision of the Coverage Form. This endorsement does not alter coverage provided in the Coverage Form.

This endorsement changes the policy effective on the inception date of the policy unless another date is indicated below.

Endorsement Effective: 12-31-2017	Countersigned By:  (Authorized Representative)
Named Insured: Iroquois Paving Corp	

SCHEDULE

Name of Person(s) or Organization(s): Any party for whom the insured is required to provide designated insured status.
--

(If no entry appears above, information required to complete this endorsement will be shown in the Declarations as applicable to the endorsement.)

Each person or organization shown in the Schedule is an "insured" for Liability Coverage, but only to the extent that person or organization qualifies as an "insured" under the Who Is An Insured Provision contained in **Section II** of the Coverage Form.

If a written contract between you and the designated insured specifically requires that this insurance be primary, then the insurance afforded by this endorsement is primary insurance and we will not seek contribution from any other insurance available to the designated insured named in this schedule unless the other insurance is provided by a contractor other than the named insured. Then we will pay only our share. Our share is the proportion that the Limit of Insurance of our Coverage Form bears to the total of the limits of all the Coverage Forms and policies covering on the same basis.

If no contract between you and the designated insured requires that this insurance be primary, then the coverage granted to the designated insured under this endorsement shall follow the provisions of the Coverage Form.

ENDORSEMENT # 7

This endorsement, effective 12:01 a.m., 12/31/2017, forms a part of Policy No. CSE 2111372 06 issued to IROQUOIS PAVING CORPORATION By GREAT AMERICAN E & S INSURANCE COMPANY

THIS ENDORSEMENT CHANGES THE POLICY. PLEASE READ IT CAREFULLY.

PRIMARY COVERAGE FOR THE INSURED'S CLIENT

This endorsement modifies insurance provided under the following:

CONTRACTING SERVICES ENVIRONMENTAL LIABILITY INSURANCE POLICY

The INSURED and the Company agree to the following Policy change(s):

Section II. DEFINITIONS, Item N. INSURED is deleted in its entirety and replaced with the following:

N. INSURED means:

1. the FIRST NAMED INSURED, any ADDITIONAL NAMED INSURED, and any present or former director, officer, partner, member, employee, leased or temporary worker thereof, while acting within the scope of his/her duties as such; and
2. any organization or entity in which the FIRST NAMED INSURED has an ownership interest of fifty percent (50%) or more, or otherwise has management control over, as of the inception date of this Policy; and
3. any joint ventures in which the INSURED is named as a co-venturer, but solely with regard to the INSURED's liability arising out of its CONTRACTING SERVICES provided under such joint venture; and
4. solely with regard to Coverage A under this Policy:

When required by written contract, INSURED also includes the client for whom the INSURED performs CONTRACTING SERVICES provided that such contract was signed by the INSURED and such client prior to the date the POLLUTION CONDITION first commenced. However, the client is included as an INSURED under this Policy solely to the extent that the client is found liable based upon CONTRACTING SERVICES negligently performed by an INSURED other than the client. Coverage for such client under this Policy shall not exceed the lesser of the following amounts:

- i. the Limit of Liability required under such written contract; or
- ii. the applicable Coverage A Limit of Liability of this Policy.

Notwithstanding Section IX. CONDITIONS, Item L. OTHER INSURANCE, and only when required by such written contract, the coverage afforded under this Policy for any entity who is an INSURED solely by reason of subparagraph 4. shall apply as primary as to any other valid and collectible insurance available to such INSURED.

All other terms and conditions remain the same.

DIVISION I

GENERAL REQUIREMENTS AND COVENANTS

<u>SECTION 1. DEFINITION OF TERMS</u>		1
1-1	DESCRIPTION	1
1-2	ABBREVIATIONS	1
1-3	ADDENDA	2
1-4	AWARD	2
1-5	BASE COURSE	2
1-6	BITUMINOUS PAVEMENT	2
1-7	BIDDER	2
1-8	CONTRACT	2
1-9	CONTRACTOR	3
1-10	CONTRACT BOND	3
1-11	CORPORATION	3
1-12	CULVERT	3
1-13	ENGINEER	4
1-14	FORCE MAIN	4
1-15	ENGINEERING OBSERVER	4
1-16	LABORATORY	4
1-17	MANHOLE	4
1-18	NOTICE TO BIDDERS	4
1-19	OWNER	4
1-20	PAVEMENT STRUCTURE	4
1-21	PLANS	5
1-22	PLUMBING	5
1-23	PROPOSAL (BID)	5
1-24	PROPOSAL GUARANTY	5
1-25	RAILROAD	5
1-26	RIGHT-OF-WAY AND EASEMENTS	5
1-27	SEWER, COMBINED	5
1-28	SEWER, SANITARY	5
1-29	SEWER, SERVICE	6
1-30	SEWER, STORM	6
1-31	SPECIAL PROVISIONS	6

<u>SECTION 3. AWARD AND EXECUTION OF CONTRACT</u>	13
3-1 CONSIDERATION OF PROPOSALS	13
3-2 AWARD OF CONTRACT	13
3-3 RETURN OF PROPOSAL GUARANTY	13
3-4 REQUIREMENT OF CONTRACT BOND	13
3-5 EXECUTION OF THE CONTRACT	14
3-6 FAILURE TO EXECUTE CONTRACT	14
<u>SECTION 4. SCOPE OF WORK</u>	15
4-1 INTENT OF THE PLANS AND SPECIFICATIONS	15
4-2 SPECIAL WORK	15
4-3 CHANGES	15
4-4 PERIODIC AND FINAL CLEANUP	16
4-5 LUMP SUM CONTRACTS	17
4-6 LOCAL ORDINANCES AND REGULATIONS	17
4-7 PREFERENCE TO VETERANS	17
<u>SECTION 5. CONTROL OF THE WORK</u>	18
5-1 PLANS AND WORKING DRAWINGS	18
5-2 CONFORMITY WITH PLANS AND SPECIFICATIONS	18
5-3 COORDINATION OF COMPONENT PARTS OF THE CONTRACT	18
5-4 COOPERATION BY CONTRACTOR	19
5-5 UTILITIES	19
5-6 COOPERATION BETWEEN CONTRACTORS	19
5-7 CONSTRUCTION STAKES	20
5-8 AUTHORITY AND DUTIES OF OBSERVERS	20
5-9 ENGINEER'S FIELD OFFICE AND/OR LABORATORY	20
5-10 CONSTRUCTION OBSERVATION	21
5-11 REMOVAL OF DEFECTIVE AND UNAUTHORIZED WORK	22
5-12 FINAL ACCEPTANCE	22
5-13 PUBLIC CONSTRUCTION BID ACT, 30 ILCS 557/1	23

7-21	USE OF WATER	39
7-22	COST OF SERVICES	39
7-23	WORK IN BAD WEATHER	39
7-24	SUNDAY WORK	39
7-25	WATCHMEN	40
7-26	CONSTRUCTION DEBRIS	40
7-27	SAMPLE INSURANCE CERTIFICATE	41
<u>SECTION 8. PROSECUTION AND PROGRESS</u>		42
8-1	SUBLETTING OR ASSIGNMENT OF CONTRACT	42
8-2	PROGRESS SCHEDULE	42
8-3	PRE-CONSTRUCTION CONFERENCE	42
8-4	PROSECUTION OF THE WORK	42
8-5	COMPLETION DATE	42
8-6	LIMITATIONS OF OPERATIONS	43
8-7	SUSPENSION OF WORK	43
8-8	DETERMINATION AND EXTENSION OF CONTRACT TIME FOR COMPLETION	43
8-9	FAILURE TO COMPLETE THE WORK ON TIME	44
8-10	DEFAULT ON CONTRACT	44
8-11	TERMINATION OF THE CONTRACTOR'S RESPONSIBILITY	45
<u>SECTION 9. MEASUREMENT AND PAYMENT</u>		46
9-1	MEASUREMENT OF QUANTITIES	46
9-2	SCOPE OF PAYMENT	46
9-3	INCREASED OR DECREASED QUANTITIES	46
9-4	PAYMENT FOR EXTRA WORK	47
9-5	PAYMENT FOR SUBCONTRACTING, EXTRA WORK	48
9-6	PARTIAL PAYMENTS	48
9-7	ACCEPTANCE AND FINAL PAYMENT	49
9-8	OWNER'S RIGHT TO WITHHOLD CERTAIN AMOUNTS	49
9-9	RELEASE OF CLAIMS AND LIENS	50

SECTION 1. DEFINITION OF TERMS

1-1 DESCRIPTION

When a standard specification number is used in the Specifications it shall be taken to mean the latest revision of that Standard Specification at the time of the Bid.

Whenever in the specifications and Contract the following terms, or pronouns in place of them, are used, the intent and meaning shall be interpreted as follows:

1-2 ABBREVIATIONS

The following organizations are referred to in this specification by abbreviations of the titles. Additional information noted but not detailed can be obtained from these organizations by writing to them.

ASTM	American Society for Testing and Materials 1916 Race Street Philadelphia, Pennsylvania 19103
ASSHTO	The American Association of State Highway and Transportation Officials 917 National Press Building Washington, D.C. 20004
AWWA	American Water Works Association 6666 West Quincy Avenue Denver, Colorado 80235
NSF	National Sanitation Test Laboratory Foundation Box 1478 Ann Arbor, Michigan
ANSI	American National Standards Institute 1430 Broadway New York, New York 10018
IDOT	Illinois Department of Transportation 2300 South Dirksen Parkway Springfield, Illinois 62764
FHWA	Federal Highway Administration DOT Building, 400 Seventh St., S.W. Washington, D.C. 20590
OSHA	Occupational Safety and Health Act
MWRDGC	The Metropolitan Water Reclamation District of Greater Chicago 100 East Erie Street Chicago, Illinois 60611

REL Robinson Engineering, Ltd

ISO Insurance Services Office

1-3 ADDENDA

Written or graphic instruments issued prior to the execution of the Agreement, which modify or interpret the Contract Documents, Drawings, and Specifications by additions, deletions, clarifications or corrections.

1-4 AWARD

The decision of the Owner to accept the proposal of the lowest responsive, responsible bidder for the work, subject to the execution of and approval of a satisfactory Contract therefore, and bond to secure the performance thereof, and to such other conditions as may be specified or otherwise required by law.

1-5 BASE COURSE

The layer or layers of specified or selected material of designed thickness placed on a sub-base or a subgrade to support the surface course.

1-6 BITUMINOUS PAVEMENT

A pavement structure which maintains intimate contact and distributes loads to the subgrade and depends upon aggregate interlock particle friction and cohesion for stability, and a pavement structure which includes a bituminous concrete surface course over a bituminous concrete base course or a portland cement concrete base course.

1-7 BIDDER

Any individual, firm, partnership or corporation submitting a proposal for the Work contemplated, acting directly or through a duly authorized representative.

1-8 CONTRACT

The written agreement between the Owner and the Contractor setting forth the obligations of the parties thereunder, including, but not limited to, the performance of the Work (the furnishing of labor and materials, and the basis of payment).

The Contract includes such of the following document parts as may be utilized. These document parts so utilized will be as fully part of the Contract as if therein set out verbatim, or, if not attached, as if attached thereto. The controlling order of priority for these documents on the project is as follows (e.g., A is controlling over B-N, etc.):

- A. Supplemental Agreements (Change Order)
- B. Addenda
- C. Special Conditions of Contract
- D. General Conditions of Contract
- E. Special Provisions to the Specifications
- F. Detailed Specifications
- G. Complete Project Plans or Drawings
- H. General Specifications
- I. Contract
- J. Contractor's Contract Bond
- K. Contractor's Proposal
- L. Notice to Proceed
- M. Notice of Award
- N. Notice to Bidders

1-9 CONTRACTOR

The Bidder awarded the Contract for the Work.

1-10 CONTRACT BOND

The approved form of security furnished by the Contractor and his surety as a guaranty that he will execute the Work in accordance with the terms of the Contract.

1-11 CORPORATION

With respect to the execution and performance of the Contract, a corporate body authorized or licensed to do business in the State of Illinois for projects in Illinois and in the State of Indiana for projects in Indiana.

1-12 CULVERT

A drainage structure extending across and beneath a traveled way and having a tubular or box-type cross-section open on both ends.

1-13 ENGINEER

ROBINSON ENGINEERING, LTD. or an engineer of a municipality, including such assistants as are authorized to represent them, who represents the Owner during the construction phase activities of the Work.

1-14 FORCE MAIN

A pipe constructed or used to carry sewage under pressure.

1-15 ENGINEERING OBSERVER

The authorized representative of the Owner or of the Engineer assigned to observe the progress of the Work to determine only if the Work is proceeding in accordance with the technical plans and specifications.

1-16 LABORATORY

An established testing laboratory approved by the Engineer.

1-17 MANHOLE

A vertical enclosed structure providing access to a pipe line or other structure.

1-18 NOTICE TO BIDDERS

The official notice, included in the proposal form, inviting bids for the proposed improvement, including a brief description of the Work.

1-19 OWNER

The Village, City, Town, Sanitary District, or other governmental body, corporation, partnership or individual initiating the project, acting through its legally constituted officials, officers or employees. The Department as referenced in the State Specifications.

1-20 PAVEMENT STRUCTURE

The combination of sub-base, base course and surface course placed on a sub-grade to support the traffic load and distribute it to the roadbed.

1-21 PLANS

All official drawings or reproductions of drawings pertaining to the Work provided for in the contract.

1-22 PLUMBING

Plumbing shall be as defined in the latest adopted Illinois State Plumbing Code, copies of which are available from the Illinois Department of Public Health, Division of Engineering and Sanitation, 535 West Jefferson Street, Springfield, Illinois 62706.

1-23 PROPOSAL (BID)

The written offer of the Bidder to perform the proposed Work.

1-24 PROPOSAL GUARANTY

The security designated in the proposal to be furnished by the Bidder as a guaranty that said Bidder will enter into a Contract with the Owner for the acceptable performance of the Work and will furnish the required Contract Bond, if the Work is awarded to him.

1-25 RAILROAD

The Railroad or Railway Company whose property is involved in the Work.

1-26 RIGHT-OF-WAY AND EASEMENTS

The areas owned, or acquired by permanent easement; also, the areas acquired by temporary easement during the time the easement is in effect.

1-27 SEWER, COMBINED

Any sewer constructed or used for the purpose of carrying both storm water and waterborne wastes to a treatment facility.

1-28 SEWER, SANITARY

Any sewer constructed or used for the purpose of carrying waterborne wastes to a treatment facility.

1-29 SEWER, SERVICE

A branch sanitary sewer line constructed from the main sanitary sewer line to a point described in the Special Provisions or Plans or to a point established by the Engineer.

1-30 SEWER, STORM

A sewer constructed or used for carrying storm water or sub-surface water to a storm water outlet.

1-31 SPECIAL PROVISIONS

Specific directions, provisions, requirements and revisions of the Specifications peculiar to the Work under consideration which are not satisfactorily provided for in the Specifications. The Special Provisions set forth the final contractual intent as to the matter involved. The Special Provisions included in the Contract shall not operate to annul those portions of the Specifications with which they are not in conflict.

1-32 SPECIFICATIONS

The body of directions, provisions and requirements contained herein, or in any supplement to this document referred to in the Special Provisions, together with written agreements and all documents of any description made or to be made pertaining to the method or manner of performing the Work, the quantities or the quality of materials to be furnished under the contract.

1-33 STATE SPECIFICATIONS

IDOT, Standard Specifications for Road and Bridge Construction, latest edition at the time of Bid. This book outlines the general requirements and covenants to all improvements, as well as provisions relating to materials, equipment and construction requirements for individual items of work.

1-34 SUBCONTRACTOR

The individual, firm, partnership or corporation to whom the Contractor, with the written consent of the Engineer, sublets, assigns, or otherwise disposes of any part of the Work covered by the contract.

1-35 SUB-BASE

The layer or layers of specified or selected material of designed thickness placed on a sub-grade to support a base course.

1-36 SUB-GRADE

The top of surface of a roadbed upon which the pavement structure and shoulders are constructed.

1-37 SUPPLEMENTAL AGREEMENT

The written agreement executed by the Owner and the Contractor, with the assent of the Contractor's surety, covering modifications or alterations of the terms of the original Contract.

1-38 SUPPLIER

Any person or organization who supplies materials or equipment for the Work including that fabricated to a special design.

1-39 SURETY

The corporate body, individual or individuals which engage to be responsible for the Bidder's acts in the execution of the Contract in the event of its being awarded to him; or, which are bound with and for the Contractor to insure his acceptable performance of the Contract, his payment of all obligations pertaining to the Work, and his fulfillment of such other conditions as may be specified or otherwise required by law.

1-40 SURFACE COURSE

One or more layers of a pavement structure designed to accommodate the traffic load, the top layer of which resists skidding, traffic abrasion, and the disintegrating effects of climate. The top layer is sometimes called "wearing course".

1-41 WATER MAIN

A pipe constructed or used to carry potable water under pressure.

1-42 WATER SERVICE LINE

That line connected to the water main, which delivers potable water to the user's facilities.

1-43 THE WORK

The improvement advertised for bids, described in the Proposal form, indicated on the Plans and covered in the Specifications, Special Provisions, Contract, authorized alterations, extensions and deductions, and supplementary agreements, or any part or parts thereof.

SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS

2-1 CONTENTS OF THE PROPOSAL FORM

Bidders will be furnished with forms stating the location and description of the Work contemplated, the approximate quantities of Work to be performed, the amount of the Proposal Guarantee, requirements pertaining to labor, and the date, time and place of filing and opening Proposals. All documents bound with or attached to the proposal shall be considered a part thereof, and shall not be detached or altered.

2-2 INTERPRETATION OF ESTIMATE OF QUANTITIES

An estimate of quantities of Work to be done and materials to be furnished under the Specifications is given in the Proposal. It is given as a basis for comparison of Proposals and the award of the Contract. The Owner and Engineer do not expressly or by implication agree that the actual quantities involved will correspond therewith; nor shall the Bidder plead misunderstanding or deception because of such estimate of quantities pertaining to the Work.

Payment will be based on the actual quantities of Work performed in accordance with Contract, at the Contract unit prices specified. No allowance will be made for any change in anticipated profits due to an increase or decrease in the original estimate of quantities. The Owner reserves the right to omit any item entirely, or to increase or decrease any or all items as provided in Section 4-3.

2-3 EXAMINATION OF PLANS, SPECIFICATIONS, SPECIAL PROVISIONS, AND SITE OF WORK

The bidder shall, before submitting his bid, carefully examine the Proposal, Plans, Specifications, Special Provisions, and form of Contract and bond. He shall inspect in detail the site of the proposed Work and familiarize himself with all the local conditions affecting the Contract and the detailed requirements of construction. If his Bid is accepted, he will be responsible for all errors in his Proposal resulting from his failure or neglect to comply with these instructions. The Owner or Engineer will, in no case, be responsible for any change in anticipated profits resulting from such failure or neglect.

When the Plans or Special Provisions include information pertaining to sub-surface exploration, borings, test pits, and other preliminary investigations, such information is included only for the convenience of the Bidder. The Owner or Engineer assumes no responsibility whatever in respect to the sufficiency of the information, and there is no guaranty, either expressed or implied, that the conditions indicated are representative of those existing throughout the Work, or that unanticipated developments may not occur.

When the Plans or Special Provisions include information pertaining to the location of underground utility facilities, such information is only included for the convenience of the Bidder. The Owner or Engineer assumes no responsibility whatever in respect to the sufficiency or accuracy of the information, or lack of information, shown on the Plans relative to the location of underground utility

facilities. It shall be the Contractor's responsibility to obtain from the respective utility companies detailed information relative to the location of their facilities and the work schedules of the utility companies for removing or adjusting them.

2-4 ENGINEER'S ESTIMATE

The Engineer's "Estimate of Cost" as prepared for the Owner for the work to be completed under this contract may or may not be available to the Bidders at the discretion of the Owner or the Engineer. If the "Estimate of Cost" is available, it shall be given to all prospective bidders upon request.

2-5 PREPARATION OF THE PROPOSAL

The Bidder shall submit his Proposal on the form furnished by the Owner. The Proposal shall be executed properly, and Bids shall be made for all items indicated in the proposal form, except that when alternate bids are asked, a Bid on more than one alternate for each item is not required, unless the Special Provisions provide otherwise. The Bidder shall indicate, in figures, a unit price or lump sum for each of the separate items called for in the Proposal; he shall show the products of respective quantities and unit prices in the column provided for that purpose, and the gross sum shown in the place indicated in the Proposal shall be the summation of said products. All writing shall be with ink or typewriter, except the signature of the bidder, which shall be written with ink.

If the Proposal is made by an individual, his name and post office address shall be shown. If made by a firm, joint venture, or partnership, the name and post office address of each member of the firm, joint venture, or partnership shall be shown. If made by a corporation, the Proposal shall show the names, titles, and business addresses of the president, secretary, and treasurer, certified to by the secretary.

2-6 MULTIPLE BIDS

If multiple Bids are to be received, bidding shall be in accordance with the instructions in the Special Provisions.

2-7 REJECTION OF PROPOSALS

Proposals that contain omissions, erasures, alterations, additions not called for, conditional or alternate bids unless called for, irregularities of any kind, or proposals otherwise regular which are not accompanied by the proper proposal guaranty shall be rejected as informal or insufficient. However, the Owners reserve the right to reject any or all Proposals and to waive such technical error as may be deemed best for the interest of the Owner.

2-8 PROPOSAL GUARANTY

Each proposal shall be accompanied by a bid bond, bank draft, bank cashier's check, or properly certified check for not less than ten per cent (10%) of the amount Bid unless otherwise specified in the Special Provisions.

If a multiple Bid is submitted, the bid bond, bank draft, bank cashier's check, or certified checks, which accompany the individual Proposals making up the combination, will be considered as also covering the multiple Bid.

See Paragraph 3-3 regarding return of Proposal Guaranty.

The bid bond, bank draft, cashier's checks, or certified checks accompanying Proposals shall be made payable to the Owner.

2-9 DELIVERY OF PROPOSALS

Proposals shall be delivered prior to the time and at the place indicated in the notice to bidders. Each Proposal shall be placed in an envelope sealed and plainly marked to indicate its contents. Only sealed Proposals will be accepted.

Proposals will not be opened unless received at the place of letting and prior to the time stated in the Notice to Bidders.

2-10 WITHDRAWAL OF PROPOSALS

Permission will be given a Bidder to withdraw a Proposal if he makes his request in writing before the time for opening Proposals. If a Proposal is withdrawn, the Bidder will not be permitted to submit another Proposal for the same Work at the same letting.

2-11 WITHDRAWAL OF PROPOSAL GUARANTY

See Paragraphs 3-2 and 3-3 on award of Contract and return of Proposal Guaranty.

2-12 PUBLIC OPENING OF PROPOSALS

Unless otherwise specified, Proposals will be opened and read publicly at the time and place specified in the Notice to Bidders. Bidders, their authorized agents, and other interested parties are invited to be present.

2-13 DISQUALIFICATION OF BIDDERS

Any one or more of the following causes may be considered as sufficient for the disqualification of a Bidder and rejection of his Proposal.

- A. More than one Proposal for the same Work from an individual, firm, partnership, or corporation under the same or different names.
- B. Evidence of collusion among bidders.
- C. Unbalanced Proposals in which the prices for some items are substantially out of proportion to the prices for other items.
- D. Failure to submit a unit price for each item of Work listed in the Proposal.
- E. If the Proposal form is other than that furnished by the Engineer or if the form is altered or any part thereof is detached.
- F. If there are omissions, erasures, alterations, unauthorized additions, conditional or alternate bids, or irregularities of any kind which may tend to make the Proposal incomplete, indefinite or ambiguous as to its meaning.
- G. If the bidder adds any provisions reserving the right to accept or reject an award, or to enter into a contract pursuant to an award.
- H. If the Proposal is not accompanied by the proper proposal guaranty.
- I. If the Proposal is prepared with other than ink or typewriter.
- J. Lack of competency as revealed by financial statement or experience questionnaire.
- K. Unsatisfactory performance record as shown by past work judged from the standpoint of workmanship and progress.
- L. Uncompleted work, which, in the judgment of the Owner, might hinder or prevent the prompt completion of additional work.
- M. False information provided on a Bidder's "Contractor's Statement."
- N. Failure to comply with any prequalification regulations of the Owner.
- O. Default under previous contracts.

2-14 COMPETENCY OF BIDDERS

The Bidder, if a corporation, shall show the name of the State in which the corporation is chartered. Each Bidder shall furnish the Owner within two (2) weeks after request, with satisfactory evidence of his competency to perform the Work contemplated. When requested, he shall submit to the Owner a

financial statement prepared by a Certified Public Accountant showing his financial condition at the end of his past fiscal year. The accountant who prepares the statement shall certify that he holds a valid and unrevoked certificate as a Certified Public Accountant, issued in accordance with the laws of the State in which he is licensed. The Bidder, if requested, shall also answer and submit questionnaires relating to his experience and available equipment for performing construction work similar to that for which he is offering a proposal, and shall do so within the same two weeks from the time of request.

Before an award is made, the Bidder may, at the option of the Owner be required to furnish a statement showing the value of all uncompleted work for which he has entered into contracts.

2-15 MATERIAL SUBSTITUTIONS

If restrictions of any governmental authority prohibit the use of certain items that are required by the Plans and Specifications, substitution for such items will be determined by the Owner.

Each Bidder shall base his bid on the furnishing of all items exactly as shown on the Plans and as described in the Specifications. The successful Bidder will not be authorized to make any substitutions on his own volition, but in each and every case must obtain a properly authorized change order from the Owner on his Contract before installing any work in variance with the Contract requirements.

2-16 CONTRACTOR'S UNDERSTANDING

It is understood and agreed that the Contractor has, by careful examination, satisfied himself as to the nature and location of the work, the conformation of the ground, the character, quality and quantity of the materials to be encountered, the character of equipment and facilities needed preliminary to and during the prosecution of the Work, the general and local conditions, and all other matters which can in any way affect the Work under this Contract. No verbal agreement or conversation with any officer, agent, or employee of the Owner and Engineer, either before or after the execution of this Contract, shall affect or modify any of the terms or obligations herein contained.

2-17 STATUS OF RIGHT-OF-WAY, EASEMENT AND CONSTRUCTION EASEMENT ACQUISITION

Each bidder is instructed to fully acquaint himself with the status of the right-of-way, easement and construction easement acquisition at the time of submission of his proposal and the possibility of the acquisition of the parcels remaining to be acquired, if any, in time so as not to interfere with the progress of his work under this contract, and the owner shall not be liable to any damage that may occur to him for any and all delay through delay of the owner in securing the necessary right-of-way, easement and construction easement.

The owner agrees that it will make every effort to acquire any right-of-way, easement and construction easement with all speed and diligence possible.

SECTION 3. AWARD AND EXECUTION OF CONTRACT

3-1 CONSIDERATION OF PROPOSALS

The proposals received will be compared on the basis of the summation of the products of the items of Work listed and the unit prices offered. In case of discrepancy between the gross sum shown in the Proposal prices, the unit prices shall govern, and any errors found in said products shall be corrected. In awarding Contracts, the Owner will, in addition to considering the amounts stated in the Proposals, take into consideration the responsibility of the various Bidders as determined from a study of the data required under the previous article and from other investigations, which the Owner may elect to make.

3-2 AWARD OF CONTRACT

Except in cases where the Owner exercises the right reserved to reject any or all Proposals, the Contract will be awarded by the Owner, as soon as practicable after the opening of Proposals.

Unless otherwise specified, if a Contract is not awarded within forty- five (45) days after the opening of Proposals, a Bidder may file a written request with the Owner for the withdrawal of his bid or award date may be extended by mutual consent of the Owner and Bidder. The Owner will have a maximum of ten (10) days after the receipt of such request to award the Contract or release the Bidder from further obligation by return of the Bidder's Proposal Guaranty.

3-3 RETURN OF PROPOSAL GUARANTY

The Proposal Guaranties of all except the two lowest Bidders will be returned promptly after the Proposals have been checked. Proposal Guaranties of the two lowest Bidders will be returned as soon as the Contract and Bond of the successful bidder have been properly executed and approved.

If Contracts cannot be awarded promptly, the Owner shall permit the two (2) lowest Bidders to substitute for the bank cashier's checks, or certified checks which they may have submitted with their Proposals as Proposal Guaranties, a bid bond executed by a corporate surety company satisfactory to the Owner, but such substitutions shall not be made until a period of three (3) days has elapsed after the date of opening Proposals.

3-4 REQUIREMENT OF CONTRACT BOND

The successful Bidder, at the time of the execution of the Contract, shall deposit with the Owner a surety bond for the full amount of the Contract. The form of bond shall be that furnished by the Owner, and the surety shall be acceptable to the Owner.

3-5 EXECUTION OF THE CONTRACT

The contract shall be executed by the successful Bidder. The bond, when required, shall be executed by the principal and the sureties, and executed Contract and Contract Bond shall be presented to the Owner within fifteen (15) days after the date of notice of the award of the Contract.

Each Contract must be executed in three (3) original counterparts, and there shall be executed original counterparts of the Contract Bond in equal number to the executed original counterparts of the Contract. One (1) copy each of such executed documents will be retained by the Owner and the Engineer, the third will be delivered to the Contractor.

3-6 FAILURE TO EXECUTE CONTRACT

Failure on the part of the successful Bidder to execute a Contract and an acceptable Contract Bond and acceptable insurance certificates as provided herein, within fifteen (15) days from the date of receipt of Contract documents from the Owner will be considered as just cause for the annulment of the award and the forfeiture of the proposal guaranty to the Owner, not as a penalty but in payment of liquidated damages sustained as a result of such failure.

SECTION 4. SCOPE OF WORK

4-1 INTENT OF THE PLANS AND SPECIFICATIONS

The intent of the contract is to prescribe a complete outline of work which the Contractor undertakes to do in full compliance with the contract, plans and specifications. The Contractor shall furnish all required materials, equipment, tools, labor, and incidentals, unless otherwise provided in the contract, and shall include the cost of these items in the unit prices bid for the several units of work. Contractor shall be solely responsible for all safety procedures and safety violations. The quantities appearing in the bid schedule of prices are estimates prepared for the establishment of pay item prices and the comparison of bids. Payment to the Contractor will be made for the actual measured quantities performed and accepted or material furnished and accepted according to the contract, and the scheduled quantities may be increased, decreased, or omitted as herein provided.

Under no circumstances shall the Contractor exceed any established pay item quantity without notification to the Engineer and receipt of written authorization as provided herein.

The latest edition of the State Specifications and Standard Specifications for Water and Sewer Construction in Illinois shall be the basis and govern this contract unless otherwise provided by special provision or exception.

4-2 SPECIAL WORK

Should any construction or requirement not covered by the Specifications be anticipated on any proposed Work, Special Provisions for the same will be prepared and included in the Proposal form, which Special Provisions shall be considered as a part of the Specifications the same as though contained fully herein.

4-3 CHANGES

The Owner reserves the right to make, in writing, at any time during work, changes in quantities, alterations in work, and the performance of extra work to satisfactorily complete the project. Such changes in quantities, alterations, and extra work shall not invalidate the contract nor release the surety, and the Contractor agrees to perform the work as altered.

If the alterations or changes in quantities significantly change the character of the work under the contract, whether or not changed by any such different quantities or alterations, an adjustment, excluding loss of anticipated profits, will be made to the contract. The basis for the adjustment shall be agreed upon prior to the performance of the work. If a basis cannot be agreed upon, then an adjustment will be made either for or against the Contractor in such amount as the Owner may determine to be fair and equitable.

If alterations or changes in quantities do not significantly change the character of the work to be performed under contract, the altered work will be paid for as provided elsewhere in the contract.

The term "significant change" shall be construed to apply only when the character of the work as altered differs materially in kind or nature from that involved or included in the original proposed construction or when a major item, defined as an item whose total original contract costs exceeds ten percent of the total original contract amount, is increased in excess of 125 percent or decreased below 75 percent of the original contract quantity.

All alterations, cancellations, extensions, and deductions shall be authorized in writing by the Owner before work is started. Such authorizations shall set up the items of work involved and the method of payment for each item.

The Contractor shall accept payment for alterations which result in an increase or decrease in the quantities of work to be performed according to the following:

- A. All increases in work of the type which appear in the contract as pay items accompanied by unit prices will, except as provided under paragraph (C) herein, be paid for at the contract unit prices. Decreases in quantities included in the contract will be deducted from the contract at the unit bid prices. No allowance will be made for delays or anticipated profits.
- B. Major items of work for which the quantities are increased by not more than 125 percent or reduced to not less than 75 percent of the original contract quantities will be paid for as specified in paragraph (a) above. Any adjustments for increased quantities for major items of work increased more than 125 percent shall only apply to that portion in excess of 125 percent of original contract quantities. Any adjustments made for major items of work which are decreased to less than 75 percent of the original contract quantities shall apply to the actual amount of work performed.
- C. Extra work which is not included in the contract as pay items at unit prices and is not included in other items of the contract will be paid for according to Section 9-4.

4-4 PERIODIC AND FINAL CLEANUP

From time to time or as may be ordered by the Owner and immediately after completion of the Work, the Contractor shall at his own expense clean up and remove all refuse and unused materials of any kind resulting from the Work. Upon failure to do so within five (5) working days after receipt of written request from the Owner, the Work may be done by the Owner and the cost thereof be charged to the Contractor and be deducted from his Contract price. Upon completion of the Work, the Contractor shall remove all his equipment and put the area of the Work in a neat and clean condition and do all other cleaning required to complete the Work in a workmanlike manner, ready for use and satisfactory to the Owner.

All Cleanup shall be performed as specified in the various sections of these Specifications or in the Special Provisions.

4-5 LUMP SUM CONTRACTS

On lump sum Contract, when specified in Special Provisions, or Contracts containing lump sum items, the lump sum contract price shall include the furnishing and installation of all Work described in the Specifications and/or shown on the Plans.

4-6 LOCAL ORDINANCES AND REGULATIONS

The Contractor shall keep himself fully informed of all existing laws, ordinances, and regulations of the municipality affecting the work and/or material of this Contract. If any inconsistency is discovered between the Plans, Specifications and those covered by local municipal laws, ordinances, or regulations, it shall be reported to the Owner and Engineer.

4-7 PREFERENCE TO VETERANS

Attention is called to assure compliance with Illinois Revised State Chapter 126 Section 23. Preference to veterans upon public works: "In the employment and appointment to fill positions in the construction, addition to, or alteration of all public works undertaken or contracted for by the state, or by any political subdivision thereof, preference shall be given to persons who were engaged in the military or naval service of the United States in time of war".

SECTION 5. CONTROL OF THE WORK

5-1 PLANS AND WORKING DRAWINGS

The Contractor shall submit to the Engineer such shop, working, or layout drawings pertaining to the construction of the Work, as may be required. These drawings shall be reviewed by Engineer for general conformance with the design concept only. This review by the Engineer does not relieve the Contractor and/or fabricator/vendor of responsibility for conformance with the Contract documents (see 1-8) and applicable codes, all of which have priority over these shop, working and layout drawings. Corrections or comments made on the shop drawings by the Engineer during this review process do not relieve the Contractor from compliance with the requirements of the Contract documents (1-8) and applicable codes.

When the Contract includes Work adjacent to a railroad and false work, cofferdams, or sheeting is required, the Contractor shall submit to the Engineer for his approval and the Railroad Engineer's approval, plans for the false work, cofferdams, or sheeting by a Registered Structural Engineer. It shall be the responsibility of the Contractor to contact the railroad to determine how to meet their requirements. The cost of meeting those requirements shall be borne by the Contractor. The plans shall be submitted sufficiently in advance of the time the Contractor intends to start work to permit checking. No such work shall be started prior to receipt by the Contractor of approval of the Plans for the false work, cofferdams, or sheeting.

The cost of furnishing such Drawings shall be incidental to the contract and no additional compensation will be allowed the Contractor for any delays resulting therefrom.

5-2 CONFORMITY WITH PLANS AND SPECIFICATIONS

It is the intent of the Specifications that all Work performed and all materials furnished shall be in conformity with the lines, grades, cross section, dimensions and material requirements shown on the Plans or indicated in the Specifications.

In the event the Engineer finds the materials or the finished product in which the materials are used or the Work performed are not in conformity with the Engineering Plans and technical Specifications including tolerances and have resulted in an inferior or unsatisfactory product, the Work or material shall be removed and replaced or otherwise corrected by and at the expense of the Contractor.

5-3 COORDINATION OF COMPONENT PARTS OF THE CONTRACT

The Specifications, the accompanying Plans, the Proposal, the Special Provisions, and all other contract documents are intended to describe a complete Work and are essential parts of the Contract. A requirement occurring in any of them is binding. In case of discrepancy, figured dimensions shall govern over scaled dimensions, Plans shall govern over Specifications, Special Provisions shall govern over both Specifications and Plans, and quantities shown on the plans shall govern over those shown in the

Proposal. Neither the Owner, Engineer, nor the Contractor shall take advantage of any apparent error or omission in the Plans or Specifications, and the Owner shall be permitted to make such minor changes or alterations as may be deemed necessary for the fulfillment of the intent of the Plans and Specifications. Any corrections or alterations so made shall be subject to the provisions of Section 4-3.

5-4 COOPERATION BY CONTRACTOR

The Contractor will be furnished necessary copies of the Plans and Special Provisions, and he shall have one copy of each available on the work at all times during its prosecution. He shall give the work his constant attention to facilitate the progress thereof, and shall cooperate with the Owner and Engineer in every way possible. He shall have on the Work site at all times a competent, English-speaking representative authorized to receive orders and act for him and shall not replace him without prior written notification to the Owner.

5-5 UTILITIES

Not all of the gas, power, telephone or cable television lines, whether above or below ground, have been shown on the drawings. The location of existing underground utilities, such as water mains, sewers gas mains, etc., as shown on the drawings, have been determined from the best available information and are given for the convenience of the Contractor. The Contractor must assume responsibility for location and protection of all utilities, whether shown or not, and must realize that the actual locations of the utilities shown on the drawings may be different from the location indicated.

It is the responsibility of the Contractor to phone the Joint Utility Locating Information for Excavators (J.U.L.I.E.) at least 48 hours before excavation starts (except Saturday, Sunday and Holidays) phone toll free 1-800-892-0123. The Contractor shall also be responsible for having the "Dig Number" assigned as a result of the phone request available at the construction site and at his office.

It is understood and agreed that the Contractor has considered in his Proposal all of the permanent and temporary utility appurtenances shown or otherwise indicated on the Plans in their present positions and that no additional compensation will be allowed for any delays, inconvenience, or damage sustained by him due to any interference from the said utility appurtenances of the operation of moving them either by the utilities company or by the Contractor; or on account of any special construction methods required in prosecuting his work due to the existence of said appurtenances.

5-6 COOPERATION BETWEEN CONTRACTORS

If separate contracts are let for Work comprising an entire improvement, each Contractor shall conduct his Work so as not to interfere with or hinder the progress or completion of the Work being performed by other Contractors.

The Contractor shall as far as possible arrange his Work, and place and dispose of the materials being used so as not to interfere with the operations of the other contractors within the limits of the same improvement. He shall join his work with that of the others in an acceptable manner and shall perform it in proper sequence to that of the others. In case of dispute, the latest approved progress schedule shall govern.

5-7 CONSTRUCTION STAKES

Construction stakes and/or paint will be furnished and set by the Engineer to mark the general location, alignment, elevation and grade of the Work. The Contractor shall exercise proper care in the preservation of stakes set for his use or the use of the Engineer. The Contractor shall pay for the cost of replacing stakes damaged by his operation or those stolen by others.

5-8 AUTHORITY AND DUTIES OF OBSERVERS

Observers employed by the Owner or by the Engineer shall be authorized to observe the progress of the Work to determine if the Work is proceeding in accordance with the technical Plans and Specifications, and to perform such other duties as may be designated by the Engineer. However, the Engineer shall not be responsible for the construction means, methods, techniques, sequences or safety procedures and precautions in connection with the work by the contractors.

5-9 ENGINEER'S FIELD OFFICE AND/OR LABORATORY

When required by the Special Provisions, the Contractor shall furnish a field office and laboratory. The field office and/or laboratory shall be a weatherproof building for the exclusive use of the Engineer. It shall be independent of any building used by the Contractor. All keys to the building shall be turned over to the Engineer. The Engineer shall designate the location of the building and it shall remain on the site until released by the Engineer.

The building shall conform to the following requirements:

- Floor space, not less than 120 square feet
- Height of ceiling, not less than..... 8 feet
- Windows, not less than 3
- Door, with lock approved by the Engineer 1
- Instrument locker, 2 feet x 3 feet x 4 feet, with adjustable shelves
- Hinged wall table 3 feet x 6 feet

The Contractor shall provide lights, heat, and when electric power is available, summer air conditioning for the building. The conditions shall be acceptable to the Engineer.

When shown on the plans or specified in the Special Provisions, the Contractor shall furnish two (2) buildings conforming to the above requirements, one to be used as a field laboratory, and each to be located where designated by the Engineer.

With the approval of the Engineer, a mobile building or buildings of approximately the same dimensions and having similar facilities may be substituted for the above described building or buildings.

The cost of furnishing the building or buildings, light, heat, and air conditioning shall be paid for at the contract lump sum price for "FIELD OFFICE AND/OR LABORATORY". The office and/or laboratory shall remain the property of the Contractor when the Work is completed.

5-10 CONSTRUCTION OBSERVATION

All materials and each part or detail of the Work may be subject at all times to observation by the Engineer and the Owner, or their authorized representatives, and the Contractor will be held strictly to the true intent of the Contract documents in regard to quality of materials, workmanship and the diligent execution of the Contract. Observations may be made at the site or at the source of material supply whether mill, plant or shop. The Engineer, or his representatives, shall be allowed access to all parts of the Work and shall be furnished with such information and assistance by the Contractor as is required to make his observations and construction review. The duty of the Engineer to conduct observations and construction review of the Contractor's performance shall not include review of the adequacy of the Contractor's safety measures in, on, or near the construction site.

Engineer shall not at any time supervise, direct, or have control over any contractors' work, nor shall Engineer have authority over or responsibility for the means, methods, techniques, sequences, or procedures of construction selected or used by any contractor, nor for safety precautions and programs in connection with the contractors' work, nor for any failure of any Contractor to comply with laws and regulations applicable to contractors' work. Engineer neither guarantees the performance of any contractor nor assumes responsibility for any contractor's failure to furnish and perform its work. Engineer shall have no authority to stop the work of any contractor on the Project. The Engineer's efforts will be directed toward providing assurance for the Owner that the completed project will conform to the Plans and Specifications as prepared by the Engineer, to safeguard the Owner against variances and deviations from the Plans and Specifications, and to assist in a correct interpretation of the Plans and Specifications.

The Engineer shall not have control of the construction and does not have a right, duty or responsibility to stop work for any reason including any contractor's failure to follow proper safety precautions or any acts or omissions. The Engineer shall not be responsible for the acts, errors or omissions of any contractor or any of their agents or employees or any other person performing any of the Work under the Contract.

The Contractor shall, upon written notice from the Owner, remove or uncover such portions of the finished Work as he may direct, before the final acceptance of the same. After examination, the Contractor shall restore said portion of the Work to the standard required by the Contract documents. If the Work thus exposed or examined proves acceptable, the expenses of uncovering or removing and the replacing of the parts removed shall be paid for as Extra work, unless otherwise provided in the Contract documents, but if the Work so exposed or examined is unacceptable, the expense of uncovering or removing and the replacing of the same in accordance with the Contract documents shall be borne by the Contractor.

The Contractor shall supervise and direct the Work. He will be solely responsible for the means, methods, techniques, sequences and procedures of construction.

Any reference to "supervision" by the Engineer in the Illinois Department of Transportation, Standard Specifications for Road and Bridge Construction or any other referenced documents shall be changed to "observation."

When the State and/or Federal Government is to pay a portion of the cost of the Work covered by the Contract, the Work shall be subject to the observation of the representatives of those Governments, but such observation shall in no sense make those Governments a part of the Contract.

5-11 REMOVAL OF DEFECTIVE AND UNAUTHORIZED WORK

Work done without lines and grades being given, or beyond the lines shown on the Plans or as given, except as herein provided, or any extra work done without authority will be considered as unauthorized and at the expense of the Contractor, and will not be measured or paid for. Work so done may be ordered by the Owner to be removed or replaced at the Contractor's expense.

All work, which has been rejected, shall be remedied or removed and replaced so as to comply with the Plans and Specifications by the Contractor at his own expense. Upon failure on the part of the Contractor to comply promptly with any order of the Owner made under the provisions of this article, the Owner shall, after giving written notice to the Contractor, have the authority to cause defective work to be remedied, or removed and replaced, or to cause unauthorized work to be removed, and to deduct the cost thereof from the contract price due or become due to the Contractor.

5-12 FINAL ACCEPTANCE

The Engineer shall make final acceptance of all Work included in the Contract, as soon as practicable after notification by the Contractor that the Work is completed. If the Work is not acceptable to the Engineer, he shall inform the Contractor in writing as to the particular defects to be remedied before final acceptance can be made.

The Contractor shall be relieved of normal maintenance responsibilities for any sections of the work, which are completed and accepted by the Owner prior to project completion. For the remainder of the Work, the guarantee period shall be as stated in Section 7-16.

When the Contract includes work for which the County, State and/or Federal Government is to pay a portion of the cost thereof, such work shall also be subject to the inspection and approval of the representatives of those governments.

5-13 PUBLIC CONSTRUCTION BID ACT, 30 ILCS 557/1

It is agreed that the Public Construction Bid Act, 30 ILCS 557/1, shall not be applicable to this contract pursuant to the home rule powers of the community.

SECTION 6. CONTROL OF MATERIAL

6-1 QUALITY OF MATERIALS

It is the intent of the Specifications that first-class materials shall be used throughout the Work, and that they shall be incorporated as to produce completed construction, which is workmanlike and acceptable in every detail. The cost of collecting and furnishing of samples of all test material shall be borne by the Contractor. The cost of all testing shall be borne by the Owner. Only materials, which conform to the requirements of these Specifications, shall be incorporated in the Work.

6-2 DEFECTIVE MATERIALS

All materials not conforming to the requirements of the Specifications shall be considered as defective and shall be removed from the Work; if in place, they shall be removed by the Contractor at his expense and replaced with acceptable materials. No defective materials, the defects of which have been subsequently corrected, shall be used until approval has been given. Upon failure of the Contractor to comply forthwith with any written order of the Owner pursuant to the provisions of this article, the Owner shall have authority to remove and replace defective materials and to deduct the cost of removal and replacement from any monies due to become due the Contractor.

6-3 TESTING MATERIALS

All materials should be tested and approved by the Engineer before incorporation in the Work. The Contractor shall give sufficient advance notice of placing orders to permit tests to be completed before the materials are incorporated in the Work and the Contractor shall afford such facilities as the Engineer may require for collecting and forwarding samples and making observations.

6-4 SAND, GRAVEL AND CRUSHED STONE

The source of sand, gravel and crushed stone construction shall be approved by the Engineer prior to usage. The approval shall be based upon testing of samples furnished by the Contractor and tested by the Engineer for conformance with Specifications. Approval shall be contingent upon the Contractor using materials on the job, which conform with the samples satisfactorily tested.

6-5 CONCRETE

Samples of concrete used in construction shall be taken by the Contractor and made into test cylinders in conformance with ASTM C31. The Owner shall provide the services of an independent testing laboratory to collect and test the cylinders in conformance with ASTM C39, and furnish a copy of test results to the Engineer. Any concrete, which tests indicate failed to conform to the Specifications, shall be removed and replaced at Contractor's expense. At the option of the Owner, the concrete may be accepted and agreed upon adjustment in payment.

6-6 MISCELLANEOUS MATERIALS

Fittings, valves, castings, hydrants, house service pipes, masonry blocks, bricks, manhole sections or other miscellaneous manufactured materials used in water and sewer construction shall be furnished with the implied guarantee that such materials conform with the requirements of the Specifications. The Engineer reserves the right to require a certified statement from the manufacturer of such materials that the specific materials have been inspected and tested and conform with the Specifications.

6-7 JOB SITE OBSERVATION

Regardless of any tests of materials made at the source, the Contractor shall carefully inspect all materials before installation and reject any materials, which have been damaged or have visible flaws. The Engineer also reserves the right to make such observation, but failure to detect irregularities does not relieve the Contractor of responsibility to remove and replace materials, which are found to be defective after installation.

6-8 STORED MATERIALS

If it is necessary to store materials, they shall be protected in such a manner as to insure the preservation of their quality and fitness for the Work. All stored materials shall be inspected at the time of use in the Work, even though they may have been inspected and approved before being placed in storage. The Contractor may use the right-of-way for storage of materials. If stockpiling is done outside the right-of-way, the additional space required shall be provided by the Contractor at his expense.

6-9 "OR EQUAL" CLAUSE

Whenever, in any of the Contract Documents, an article, material or equipment is defined by describing a proprietary product, or by using the name of a manufacturer, or vendor, the term "or equal", if not inserted shall be implied except where the Proposal provides for alternate bids. The specific article, materials, or equipment mentioned shall be understood as indication of the type function, minimum standard or design, efficiency and quality desired and shall not be construed in such a manner as to exclude manufacturer's products of comparable quality, design and efficiency. The Contractor shall comply with the requirements of the Contract Documents relative to an Owner's approval of materials and equipment before they are incorporated in the project.

SECTION 7. LEGAL REGULATIONS AND RESPONSIBILITY TO PUBLIC

7-1 LAWS TO BE OBSERVED

The Contractor shall at all times observe and comply with all Federal laws, State laws, County laws, local laws, ordinances, and regulations which in any manner affect the conduct of the Work, and all such orders or decrees as exist at the time Bids are advertised, of legislative bodies or tribunals having legal jurisdiction or authority over the work and no plea of misunderstanding or ignorance thereof will be considered. The Engineer shall not be responsible for determining whether the Contractor is in compliance with these laws, ordinances and regulations.

The Contractor shall indemnify and save harmless the Owner, the Engineer, and all of their officers, agents, employees and servants against any claim or liability, including legal fees, arising from or based on the violation of such law, ordinance, regulation, order or decree, whether by themselves or their employees.

7-1.01 INDEMNIFICATION

To the fullest extent permitted by law, the Contractor shall defend, indemnify and hold harmless Owner and REL and their respective officers, agents and employees, from and against all claims, damages, losses, costs, expenses, judgments and liabilities, including but not limited to attorney's fees, costs and expenses, arising out of or in connection with Contractor's performance of or failure to perform this Agreement, provided that any such claim, damage, loss, costs, expenses, judgments or liabilities are attributable to bodily injury, sickness, disease or death, or to injury or destruction of tangible personal property, including the loss of use resulting therefrom, that is caused in whole or in part by any act or omission of the Contractor, any subcontractor, anyone directly or indirectly employed by them or anyone for whose acts any of them may be liable, regardless of whether or not it is caused in part by any party indemnified hereunder.

Contractor shall defend, indemnify and hold harmless Owner, REL, and their respective officers, agents and employees from and against all claims, damages, losses, costs and expenses arising out of, relating to, or incurred in connection with the use by Contractor, its officers, agents, subcontractors and employees of any equipment, materials, tools, construction equipment, machinery, and/or motor vehicles owned or leased by Owner. The indemnification provided by this Section shall apply regardless of whether Owner consents to the use of equipment by Contractor.

In the event such indemnity as described above is prohibited by law, then said indemnity shall only be to the extent caused by the negligent acts or omissions of the Contractor, subcontractors, anyone directly or indirectly employed by any of them, or anyone for whose acts any of them may be liable, or to the extent allowed by applicable law.

The indemnification obligation under this paragraph shall not be limited in any way by any limitations on the amount or type of damages, compensation or benefits payable by or for the benefit of Contractor or any indemnities under any Worker's Compensation Act, Occupational Disease Act, Disability Benefits Act, or any other employee benefits act. The Contractor further agrees to waive any and all liability limitations based upon the Worker's Compensation Act court interpretations or otherwise.

Contractor agrees that a similar waiver of liability limitation will be incorporated in its agreements with subcontractors or anyone directly or indirectly employed by them. Contractor agrees that in the event it fails to incorporate such a waiver of liability limitation in its agreements with said subcontractors and others, then it will be responsible for any additional liability arising out of said failure. The defense and indemnification obligations set forth in this provision shall survive the termination or expiration of this Agreement.

Contractor further agrees that all future contracts in furtherance of this contract between Contractor and any of its subcontractors will designate Owner and REL as intended third party beneficiaries of that contract. Contractor hereby agrees to specifically label Owner and REL as an "intended third party beneficiaries" in all contracts entered in furtherance of this contract.

7-2 INSURANCE REQUIREMENTS

7-2.01 GENERAL

The Contractor and any Subcontractors shall obtain and thereafter keep in force for the term of the contract the insurance coverage specified in 7-2.02 MINIMUM INSURANCE REQUIREMENTS.

The Contractor shall not commence work under the Contract until all the insurance required by this section or any Special Provisions has been obtained. The insurance companies must be authorized to do business in the State of Illinois for Work in Illinois and the State of Indiana for Work in Indiana.

The insurance companies providing coverage shall be rated in the Best's Key Rating Guide with a rating not lower than A- and shall have a financial size category of not less than VII.

The Contractor shall be solely responsible for enforcing compliance with these insurance requirements by all Subcontractors of any tier.

A. PRIMARY INSURANCE

All insurance required of the Contractor shall be specifically endorsed so that it is Primary Insurance as to all additional insureds with respect to all claims arising out of operations by or on their behalf. If additional insureds have other applicable insurance coverage, those coverages shall be deemed to be on an excess or contingent basis.

B. NO WAIVER OF INSURANCE REQUIREMENT BY OWNER

Under no circumstances shall the Owner be deemed to have waived any of the insurance requirements of this Contract by any act or omission, including, but not limited to:

1. Allowing work by Contractor or any Subcontractor of any tier to start before receipt of certificates of insurance, endorsements, and other required insurance documents; or
2. Failure to examine, or to demand correction of any deficiency of, any certificate of insurance received.

The Contractor agrees that the obligation to provide insurance is solely the Contractor's responsibility and cannot be waived by any act or omission of the Owner.

C. INSURANCE DOES NOT LIMIT LIABILITY

The purchase of insurance by the Contractor under this Contract shall not be deemed to limit the liability of the Contractor in any way for damages suffered by Owner (e.g., in excess of policy limits, because of deductibles, or not covered by the policies purchased).

D. NOTIFICATION OF PERSONAL INJURY/PROPERTY DAMAGE

The Contractor shall notify the Owner, in writing, of any possible or potential claim for personal injury or property damage arising out of the work of this Contract promptly whenever the occurrence giving rise to such a potential claim becomes known to the Contractor.

7-2.02 MINIMUM INSURANCE REQUIREMENTS

The insurance coverage required of the Contractor and any Subcontractors shall be written for not less than the following, or greater if required by law:

- A. **Workers' Compensation and Occupational Disease Insurance** in accordance with applicable state and federal laws, and Employer's Liability Insurance with a bodily injury per accident limit of liability of at least \$ 500,000, bodily injury by disease limit each employee of \$500,000 and bodily injury by disease policy limit of \$500,000 or such greater sum as may be reasonably required by Owner.

B. Commercial General Liability Insurance provided by ISO form CG 0001 with a combined Bodily Injury and Property Damage limit of at least \$1,000,000 per occurrence, \$2,000,000 products and completed operations aggregate and \$2,000,000 general aggregate, or such greater sum as may be reasonably required by Owner.

1. Completed Operations and Products liability insurance shall be maintained for a period of 2-years after completion and acceptance of the Project by Owner, or such longer period as may be reasonably required by the Owner.
2. The above policy shall include an endorsement identifying Owner, Robinson Engineering, Ltd, and any other parties as may be reasonably required by Owner or REL as Additional Insured. ISO endorsements CG 2010 and CG 2037 any edition, or equivalent forms, must be used to provide this coverage. Copies of the endorsements must be included with the certificate of insurance as required in paragraph L.
3. Claims-Made coverage triggers are not acceptable to Owner.
4. ISO form CG2503, Designated Construction Project(s) General Aggregate Limit or an equivalent form must be endorsed to the policy and identified on the certificate of insurance. An Owners and Contractors Protective Liability policy can be utilized in lieu of aggregate limits per project, (see 7-2.020 for OCP requirements)
5. The policy shall not contain a sunset provision, commutation clause or any other provision which would prohibit the reporting of a claim and the subsequent defense and indemnity that would normally be provided by the policy.
6. The policy shall not contain any provision, definition or endorsement which would serve to eliminate third party action over claims.
7. Residential Work exclusions or limitations, in any form, are not acceptable to Contractor.

C. Comprehensive Automobile Liability Insurance covering use of all owned, non-owned and hired vehicles with Bodily Injury and Property Damage limit of at least \$1,000,000 Combined Single Limit, or such greater sum as may be reasonably required by the Owner. This policy shall include coverage for Owner, REL, and any other parties as may be reasonably required by Owner, for liability arising out of the actions of Contractor, whether by endorsement or otherwise.

D. Excess or Umbrella Liability Insurance limits of no less than \$5,000,000 per occurrence for Employer's Liability, Commercial General Liability and Comprehensive Automobile Liability, in excess of the minimum policy limits stated below:

Employer's Liability	\$500,000 / \$500,000 / \$500,000
Commercial General Liability	\$1,000,000 per occurrence
Commercial General Liability	\$2,000,000 general aggregate
Commercial General Liability	\$2,000,000 completed operations aggregate
Comprehensive Auto Liability	\$1,000,000 combined single limit

Excess/Umbrella coverage shall be provided as no less than Follow Form and shall name Owner, REL, and any other parties as may be reasonably required by Owner, as Additional Insured on a Primary and Non-Contributory basis.

E. Pollution Liability in the amount of \$1,000,000 per occurrence and in the aggregate or such sum as may be reasonably required by the Owner. This requirement covers the Contractor's use of, transportation, removal and/or disposal of hazardous materials and/or pollutants. Additionally, this requirement must apply to any disposal site receiving hazardous materials and/or pollutants. Pollution means the actual or alleged discharge, dispersal, release, seepage, migration, growth, or escape of smoke, soot, fumes, acids, alkalis, toxic chemicals, mold, mildew, spores, fungi, microbes, bacterial matter, legionella pneumophila, asbestos, lead, silica, liquids or gases, waste materials, contaminants, or other irritants, into or upon land, the atmosphere, any structure on land, the atmosphere contained within that structure, or any watercourse or body of water, including groundwater. Radioactive matter shall also be considered a pollutant, except as otherwise covered or protected by insurance or protections provided pursuant to 42 U.S.C. § 2014(w), as amended, or Section 170 of the Atomic Energy Act of 1954, as amended.

F. Professional Liability in the amount of \$2,000,000 per occurrence and in the aggregate or such sum as may be reasonably required by the Owner. This requirement covers the Contractor's duties that involve professional architectural, engineering, design or consultation work. Any applicable deductibles and/or retention's must be noted on the Certificate of Insurance. Policy exclusions are not allowed for pollution, including mold, fungi or bacteria including the vapor produced or arising therefrom. Please see the project Special Provisions for the project specific needs of this policy.

- G. *Property and Equipment*** Contractor shall purchase and maintain at its own discretion and expense, Builder's Risk/Installation Floater Insurance in an amount equal to the insurable value of the Contractor's property, whether off site or in transit, to cover any equipment, tools or tangible personal property. Contractor assumes all liability and risks, and agrees to waive all claims against Owner and REL for damage to or loss of equipment, machinery, tools, supplies and other tangible personal property owned or supplied by Contractor and utilized or intended to be utilized during the course of Contractor's Work. Any insurance carried by Contractor covering such damage or loss shall be endorsed with a waiver of subrogation in favor of Owner and REL. Any and all subcontractors agree to assume the same liabilities and risks as Contractor.
- H. *Each of Contractor's*** General Liability, Auto Liability, Pollution Liability, Professional Liability and Excess/Umbrella Liability policies must be endorsed as Primary and Non-Contributory as to any insurance maintained by the Additional Insured(s) and shown on the certificate of insurance.
- I. *An endorsement*** in favor of the Additional Insured(s) waiving the Contractor's and its insurer's rights of subrogation shall be issued with respect to the Commercial General Liability, Comprehensive Auto Liability, Pollution Liability, Professional Liability and Workers' Compensation and Employers Liability policies. Evidence of this endorsement must be noted on the certificate of insurance.
- J. *Self-funded*** or other non-risk transfer insurance mechanisms or deductibles/self-insured retentions greater than \$25,000 per occurrence are not acceptable to Owner on any insurance coverage required in this agreement. If the Contractor has such a program, full disclosure must be made to Owner and REL prior to any consideration being given.
- K. *Any subcontractor*** employed by Contractor shall have equivalent coverage.
- L. *A Certificate of Insurance***, including copies of the Additional Insured endorsements, shall be sent to REL prior to the commencement of any Work (please see the sample attached at the end of Section 7). All Certificates of Insurance and Endorsements verifying the existence of the above required insurance shall be in form and content satisfactory and acceptable to Owner and REL and shall be submitted to REL in a timely manner so as to confirm Contractor's full compliance with these insurance requirements stated herein, throughout the entire term of this Agreement.

Certificates must be sent to: RELCertificates@thehortongroup.com

M. Contractor shall provide written notice via email to RELcertificates@thehortongroup.com of any cancellation notice received by Contractor from any insurer providing insurance as required in this Agreement within two (2) business days of Contractor's receipt of such notice.

N. Permitting Contractor to commence Work prior to RELs receipt of the required certificate shall not be a waiver of the Contractor's obligation to provide all of the above insurance. Acceptance by Owner or REL of insurance submitted by Contractor shall not relieve or decrease in any manner the liability of the Contractor for its performance under this Agreement.

In the event Contractor fails to obtain or maintain any of the foregoing required coverage, the Owner may purchase such coverage and charge the expense thereof to the Contractor, or may terminate this Agreement.

These Insurance provisions are intended to be a separate and distinct obligation on the part of Contractor. Therefore, these provisions shall be enforceable and Contractor shall be bound thereby regardless of whether or not the Indemnity provisions of this Agreement are determined at any time to be enforceable in the jurisdiction in which the Work covered by this Agreement is performed. The obligation of the Contractor to provide the insurance herein specified shall not limit in any way the liability or obligations assumed by the Contractor elsewhere in this Agreement.

In the event Contractor or its insurance carrier(s) defaults on any obligations under this Insurance provision, Contractor agrees that it will be liable for all reasonable expenses and attorneys' fees incurred by Owner in the enforcement of the terms of this provision.

O. Owner's And Contractor's Protective Liability Insurance

If the Contractor is unable or unwilling to provide the required General Liability Additional Insured forms, an Owner's and Contractor's Protective Policy can be purchased as an acceptable alternate; Required limits of insurance;

1. Bodily Injury and Property Damage Combined

\$5,000,000 Each Occurrence

\$10,000,000 Annual Aggregate

2. The Contractor will furnish and maintain during the entire period of construction an Owner's and Contractor's Protective Liability policy written in the name of the Owner and REL with not less than the limits indicated. The named insureds shall be:

- a. Owner
 - b. Robinson Engineering, Ltd.
3. Proof of insurance for the coverages required to be purchased by the Contractor, including the Owner's and Contractor's Protective Policy shall be submitted to REL for transmittal to the Owner for his approval prior to the start of construction. Proof of the Owner's Protective Policy shall consist of providing an entire copy of that policy to REL. With respect to all other coverages required to be purchased by the Contractor, proof of insurance shall consist of a Certificate of Insurance issued by the Contractor's insurance agency.
 4. It is further understood that any insurance maintained or carried by Owner and Robinson Engineering, Ltd. shall be in excess of any coverage provided by any Contractor or Subcontractor.

P. *Railroad Protective Insurance* will be required by Special Provisions if needed.

Q. *Builder's Risk Insurance* is not provided by the Owner. The Contractor is responsible for any loss that would be insured by such coverage. On Contracts for construction of buildings, bridges, or other structures, all Builder's Risk coverage may be required by Special Provisions. Such coverage shall name the Owner, Contractor, subcontractors, and suppliers, as their interests may appear as named insureds.

7-3 PERMITS AND LICENSES

The Contractor, prior to commencing work, shall at his own expense procure all permits, licenses, and bonds necessary for the prosecution of the work, required by Municipal, County, State and Federal regulations, unless specifically provided otherwise in the Special Conditions of the Contract.

The Contractor shall also give all notice, pay all fees, and comply with all Federal, State, County and Municipal laws, ordinances, rules and regulations and building and construction codes bearing on the conduct of the Work.

7-4 PATENTS AND ROYALTIES

If any design, device, material or process covered by letters patent or copyright is used by the Contractor, he shall provide for such use by legal agreement with the owner of the patent or a duly authorized licensee of such owner, and shall save harmless the Owner and the Engineer from any and all loss or expense on account thereof, including its use by the Owner.

7-5 STATE AND FEDERAL PARTICIPATION

When the County, State, and/or the Federal Government pays all or any portion of the cost of the Work, the Work shall be subject to the inspection of the appropriate agency.

7-6 SANITARY PROVISIONS

The Contractor shall comply with all rules and regulations of the Federal, State, County, and local health departments, and shall take precautions to avoid creating unsanitary conditions. The Engineer shall not be responsible for determining whether the Contractor is in compliance with these rules and regulations.

7-7 PUBLIC CONVENIENCE AND SAFETY

The Contractor shall notify the Owner at least five (5) days in advance of the starting of Work, which might in any way inconvenience or endanger traffic, so that arrangements may be made, if necessary, for closing the road and providing suitable detours. The Contractor shall at all times conduct the Work as to insure the least obstruction to vehicular and pedestrian traffic. The convenience of the general public and of residents along the roadway shall be provided for in an adequate and satisfactory manner. (See also 7-9, 7-14 and 8-6.)

If a temporary road is required for the convenience of the general public and/or residents along the roadway, temporary road requirements will not be paid for separately, but will be incidental to the Contract and no extra compensation will be allowed.

7-8 BARRICADES AND WARNING SIGNS

When any section of road is closed to traffic, the Contractor shall provide, erect, and maintain barricades, red flags, signs and lights at each end of the closed section and at all intersecting roads in accordance with the Illinois Manual of Uniform Traffic Control Devices.

If during the progress of the work, it is necessary to provide access to private property along the road, the Contractor shall provide, erect, and maintain within the closed portion of the road, such barricades, signs, flags and lights as may be necessary to protect the Work and to safeguard local traffic.

When traffic is to be permitted to use the road during construction, the Contractor shall protect the work and provide for safe and convenient public travel by providing, erecting, and maintaining such barricades, red flags, and lights as are necessary.

The Contractor's responsibility for the work, as provided in Section 7-15, shall apply, even though barricades, signs, red flags, and lights are installed as required above.

The cost of furnishing and maintaining barricades, warning signs, red flags, and lights as required herein shall be incidental to the Contract and no extra compensation will be allowed. The Engineer shall not be responsible for determining whether the Contractor is in compliance with these rules and regulations.

7-9 DEBRIS ON TRAVELED SURFACE OR STRUCTURES

Where the Contractor's equipment is operated on any portion of the traveled surface or structures used by traffic on or adjacent to the section under construction, the Contractor shall clean the traveled surface of all dirt and debris at the end of each day's operation.

The cost of this work shall be included in the unit prices bid and no additional compensation will be allowed. The Engineer shall not be responsible for determining whether the Contractor is in compliance with these rules and regulations.

7-10 EQUIPMENT ON TRAVELED SURFACE AND STRUCTURES

The traveled surface and structures on or adjacent to the work shall be protected, from damage by lugs or cleats on treads or wheels of equipment.

All equipment used in the prosecution of the work shall comply with the legal loading limits established by the statutes of the State of Illinois or local regulations when moved over or operated on any traveled surface or structure unless permission in writing has been issued by the Owner. Before using any equipment, which may exceed the legal loading, the Contractor shall secure a permit, allowing ample time for making an analysis of stresses to determine whether or not the proposed loading would be within safe limits. The Owner will not be responsible for any delay in construction operations or for any costs incurred by the Contractor as a result of compliance with the above requirements. The Engineer shall not be responsible for determining whether the Contractor is in compliance with these rules and regulations.

7-11 USE OF EXPLOSIVES

When the use of explosives is necessary for the prosecution of the Work, the Contractor shall be governed by the rules and regulations of the Department of Mines and Minerals of the State of Illinois and any local regulations, which govern the use of explosives. The Engineer shall not be responsible for determining whether the Contractor is in compliance with these rules and regulations.

7-12 USE OF FIRE HYDRANTS

If the Contractor desires to use water from hydrants, he shall make application to the proper authorities, and shall conform to the municipal ordinances, rules or regulations concerning their use. Water from

hydrants or other sources shall be at the Contractor's expense unless otherwise provided in the Special Provisions.

Fire hydrants shall be accessible at all times to the Fire Department. No material or other obstructions shall be placed closer to a fire hydrant than permitted by municipal ordinances, rules or regulations, or within ten feet (10') of a fire hydrant, in the absence of such ordinances, rules or regulations.

7-13 PROTECTION AND RESTORATION OF PROPERTY

If corporate or private property interferes with the Work, the Contractor shall notify, in writing, the owners of such property, advising them of the nature or disposition of such property. The Contractor shall furnish the Owner with copies of such notifications and with copies of any agreements between him and the property owners concerning such protection or disposition.

The Contractor shall take all necessary precautions for the protection of corporate or private property, such as walls and foundations of buildings, vaults, underground structures of public utilities, underground drainage facilities, overhead structures of public utilities, trees, shrubbery, crops and fences contiguous to the Work, of which the Contract does not provide for removal. The Contractor shall protect and carefully preserve all official survey monuments, property marks, section markers, and Geological Survey monuments, or other similar monuments, until the Owner or an authorized surveyor or agent has witnessed or otherwise referenced their location or relocation. The Contractor shall take reasonable precautions to avoid disturbing any archeological and other historic remains encountered during construction. The Contractor shall notify the Owner of the presence of an such survey or property monuments or archeological and other historic remains as soon as they are discovered.

The Contractor shall be responsible for the damage or destruction of property of any character resulting from error, neglect, misconduct or omission in his manner or method of execution or non-execution of the Work, or caused by defective Work or the use of unsatisfactory materials, and such responsibility shall not be released until the Work shall have been completed and accepted and the requirements of the Specifications complied with.

Whenever public or private property is so damaged or destroyed, the Contractor shall at his own expense, restore such property to a condition equal to that existing before such damage or injury was done by repairing, rebuilding, or replacing it as may be directed, or he shall otherwise make good such damage or destruction in an acceptable manner. If he fails to do so, the Owner may, after the expiration of a period of forty-eight (48) hours after giving him notice in writing, proceed to repair, rebuild, or otherwise restore such property as may be deemed necessary, and the cost thereof shall be deducted from any compensation due, or which may become due the Contractor under his contract.

The Contractor shall remove all mailboxes within the limits of construction, which interfere with construction operations and shall erect them at temporary locations. As soon as construction

operations permit, he shall set the mailboxes at their permanent locations. The Contractor shall replace at his own expense any mailbox or post which has been damaged by his operations.

The cost of all materials required and all labor necessary to comply with the above provisions will not be paid for separately, but shall be considered as incidental to the Contract, unless otherwise specified in the Special Provisions.

7-14 PROTECTION AND RESTORATION OF TRAFFIC SIGNS

Any traffic sign within the limits of construction, which interferes with construction operations, may be removed by the Contractor when authorized by the traffic sign owner. Any traffic sign, which has been removed, shall be re-erected immediately by the Contractor at the temporary location designated by the traffic sign owner, and as soon as construction operations permit, the sign shall be set at its permanent location. The cost of all materials required and all labor necessary to comply with this provision will not be paid for separately, but shall be considered as incidental to the contract.

The Contractor shall replace at his own expense any traffic sign or post which has been damaged due to his operations.

Any traffic sign designated as critical by the traffic sign owner shall not be disturbed and no additional compensation will be allowed the Contractor for any delays, inconvenience, or damage sustained by him due to any special construction methods required in prosecuting his work due to the existence of such traffic signs.

7-15 CONTRACTOR'S RESPONSIBILITY FOR WORK

The Work shall be under the control and care of the Contractor until final acceptance or use or occupancy by the Owner. The Contractor shall assume all responsibility for injury or damage to the Work by action of the elements or from any other cause whatsoever, and shall rebuild, repair, restore, and make good, at his expense, all injuries or damages to the Work, except that when the Work is opened to usage by written order of the Owner, the provisions of this article shall not apply to damage caused by such use and not due to the Contractor's fault or negligence.

When materials are furnished to the Contractor by the Owner for inclusion in the work, the Contractor's responsibility for handling and installation of all such materials shall be the same as for materials furnished by him.

In case of suspension of Work by the Contractor, the Contractor shall be responsible for the Work and shall take such precautions as may be necessary to prevent damage to the Work, provide for normal drainage and shall erect any necessary temporary structures, signs, or other facilities at his expense.

7-16 GUARANTEE PERIOD

The Contractor shall warrant all Work performed for a period of one (1) year from the date of final acceptance in writing by the Engineer. In case of acceptance of a part of the work for use or occupancy prior to final acceptance of the entire Work, the guarantee for the part so accepted shall be for a period of one year from the date of such partial acceptance, in writing, by the Engineer.

In placing orders for equipment, the Contractor shall purchase same only under a written guarantee from the respective manufacturers that the equipment supplied will function satisfactorily as an integral part of the completed Work in accordance with the Plans and Specifications, and that the manufacturer will repair or otherwise make good any defects in workmanship or materials which may develop within a period of one (1) year from the date of final acceptance. Furthermore, the Contractor shall require that the manufacturer agree in writing at the time the order for equipment is placed that he will be responsible for the proper functioning of the equipment in cooperation with the Contractor, and that whenever necessary during the installation period or tuning up period following construction period, the manufacturer will supply without additional cost to the Owner, such superintendence and mechanical labor and any adjustments and additional parts and labor needed to make the equipment function satisfactorily, even if same was not shown on the approved shop drawings.

7-17 PERSONAL LIABILITY OF OWNER'S AGENTS

In carrying out the provisions of this contract, or in exercising any power or authority granted to the Owner, there shall be no personal liability upon any officer or authorized agent of the Owner provided the Owner is a governmental body, it being understood that all such persons act as agents and representatives of the Owner.

7-18 NO WAIVER OF LEGAL RIGHTS

The Owner and the Engineer shall not be precluded by any measurement, estimate, or certificate made either before or after the completion and acceptance of the Work and payment therefor, from showing the true amount and character of the Work performed and materials furnished by the Contractor, or from showing that any such measurement, estimate, or certificate is untrue or incorrectly made, or that the Work or materials do not conform in fact to the Contract. The Owner shall not be precluded, notwithstanding any such measurement, estimate, or certificate and payment in accordance therewith, from recovering from the Contractor and his sureties such damages as if it may sustain by reason of his failure to comply with the terms of the Contract. Neither the acceptance by the Owner, nor any representative of the Owner, nor any payment for or acceptance of the whole or any part of the work, nor any extension of time, nor any possession taken by the Owner, shall operate as a waiver of any portion of the Contract, or of any power herein reserved, or any right to damages herein provided. A waiver of any breach of the Contract shall not be held to be a waiver of any other or subsequent breach.

7-19 SAFETY

Contractor shall comply with State and Federal Safety regulations as outlined in latest revision of Federal Construction Safety Standards (Series 1926) and with applicable provisions and regulation of Occupation Safety and Health Administration (OSHA) Standards of the Williams-Steiger Occupational Health and Safety Act of 1970 (rev.). The Engineer shall not be responsible for determining the Contractor's compliance with these regulations.

The Contractor is solely responsible for the safety procedures, programs and methods of its employees, subcontractors of every tier, and agents. Contractor shall hold the Owner and the Engineer harmless for any and all damages resulting from violations thereof.

7-20 USE OF PRIVATE LAND

The Contractor shall not use any vacant lot or private land as a plant site, depository for materials, or as a spoil site without the written authorization of the owner of the land (or his agent), a copy of which authorization shall be filed with the Owner.

7-21 USE OF WATER

Contractors desiring to use water furnished by the Owner will be required to make application for extension to the proper authorities and conform to the rules and regulations provided in such cases by the municipal ordinances and pay the usual water rates.

7-22 COST OF SERVICES

The Contractor will be required to pay the established water rates for water obtained from the Owner. Large quantities of water for flushing trenches, filling mains, testing or other operations shall be drawn only at night or at times specifically authorized by the Owner.

The cost of all power, lighting and heating required during construction shall be paid by the Contractor and its costs merged in the contract price.

7-23 WORK IN BAD WEATHER

No construction work shall be done during stormy, freezing or inclement weather, except such as can be done satisfactorily, and to secure first-class construction throughout, and then only subject to permission of the Owner.

7-24 SUNDAY WORK

No work shall be performed under these specifications at night or on Sunday and legal holidays without the approval of the Owner. If it is found necessary to continue the work at night or on Sunday or on a legal holiday, the Contractor will be charged for the Engineering and observation at such times at the rate of Seven Hundred Fifty Dollars (\$750.00) per day of eight (8) working hours for each person doing such work on the job, and the amount will be deducted from money due to the Contractor at the time of settlement.

7-25 WATCHMEN

Watchmen are to be provided by the Contractor at the site of the project to prevent loss, damage to property, or accidents.

7-26 CONSTRUCTION DEBRIS

The Contractor shall not conduct any generation, transportation, or recycling of construction or demolition debris, clean or general or uncontaminated soil generated during construction, remodeling, repair, and demolition of utilities, structures, and roads that is not commingled with any waste, without the maintenance of documentation identifying the hauler, generator, place of origin of the debris or soil, the weight or volume of the debris or soil, and the location, owner, and operator of the facility where the debris or soil was transferred, disposed, recycled or treated. This documentation must be maintained by the Contractor for 3 years.

7-27 SAMPLE INSURANCE CERTIFICATE

EMAIL ALL CERTIFICATES TO RELCERTIFICATES@THEHORTONGROUP.COM



CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

PRODUCER YOUR INSURANCE AGENT	CONTACT NAME:	
	PHONE (A/C, RES, EXT):	FAX (A/C, No):
INSURED YOUR NAME AND ADDRESS	E-MAIL ADDRESS:	
	INSURER(S) AFFORDING COVERAGE	
	INSURER A - CARRIERS MUST BE RATED	
	INSURER B - A, VII OR BETTER	
	INSURER C:	
	INSURER D:	
INSURER E:		
INSURER F:		

COVERAGES CERTIFICATE NUMBER: REVISION NUMBER:

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADD. SUBR (ISR, WGT)	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
	GENERAL LIABILITY <input checked="" type="checkbox"/> COMMERCIAL GENERAL LIABILITY CLAIMS-MADE <input checked="" type="checkbox"/> OCCUR	Y Y	POLICY NUMBER	EFF DATE	EXP DATE	EACH OCCURRENCE \$ 1,000,000 DAMAGE TO RENTED PREMISES (Ea. occ/yr) \$ ANY LIMIT MED EXP (Any one person) \$ ANY LIMIT PERSONAL & ADV INJURY \$ 1,000,000 GENERAL AGGREGATE \$ 2,000,000 PRODUCTS - COMPROP AGG \$ 2,000,000
	AUTOMOBILE LIABILITY <input checked="" type="checkbox"/> ANY AUTO ALL OWNED AUTOS <input checked="" type="checkbox"/> HIRED AUTOS	Y Y	POLICY NUMBER	EFF DATE	EXP DATE	COMBINED SINGLE LIMIT (Ea. accident) \$ 1,000,000 BODILY INJURY (Per person) \$ BODILY INJURY (Per accident) \$ PROPERTY DAMAGE (Per accident) \$
	UMBRELLA LIAB EXCESS LIAB	Y Y	POLICY NUMBER	EFF DATE	EFF DATE	EACH OCCURRENCE \$ 5,000,000 AGGREGATE \$ 5,000,000
	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICEMEMBER EXCLUDED? (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below.	Y/N N N/A Y	POLICY NUMBER	EFF DATE	EFF DATE	<input checked="" type="checkbox"/> WC STATUTORY LIMITS OTHER E.L. EACH ACCIDENT \$ 500,000 E.L. DISEASE - EA EMPLOYEE \$ 500,000 E.L. DISEASE - POLICY LIMIT \$ 500,000
	POLLUTION PROFESSIONAL		POLICY NUMBER	EFF DATE	EFF DATE	\$1,000,000/1,000,000 AGG \$1,000,000/2,000,000 AGG

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (Attach ACORD 101, Additional Remarks Schedule, if more space is required)
REL JOB NUMBER AND PROJECT NAME AND ADDRESS:
Additional insured with respect to General Liability, Auto Liability and Umbrella/Excess Liability on a primary and noncontributory basis when required by written contract (Owner and Robinson Engineering Ltd.) Owner is Certificate Holder. Waiver of Subrogation in favor of listed additional insureds with respect to General Liability, Auto Liability, Umbrella/Excess Liability and Workers' Compensation policies. Additional insured with respect to General Liability coverage per ISO forms CG2010 and CG2037 or equivalent forms. Umbrella/Excess is on a follow form basis and is primary and non-contributory.

CERTIFICATE HOLDER	CANCELLATION
OWNER	SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.
	AUTHORIZED REPRESENTATIVE

© 1988-2010 ACORD CORPORATION. All rights reserved.

ACORD 25 (2010/05)

The ACORD name and logo are registered marks of ACORD

SECTION 8. PROSECUTION AND PROGRESS

8-1 SUBLETTING OR ASSIGNMENT OF CONTRACT

The Contractor shall not sublet, sell, transfer, assign, or otherwise dispose of the Contract or Contracts or any portion thereof, or of his right, title, or interest therein, without written consent of the Owner. In case such consent is given, the Contractor will be permitted to sublet a portion thereof, but shall perform with his own organization, Work amounting to not less than 50 per cent of the total Contract, except that any items designated in the Contract as "specialty items" may be performed by subcontract and may be deducted from the total Contract price before computing the amount of work required to be performed by the Contractor with his own organization. No subcontracts, or transfer of Contract, shall in any case release the Contractor of his liability under the Contract. All transactions of the Owner shall be with the Contractor; subcontractors shall be recognized only in the capacity of employees or workmen and shall be subject to the same requirements as to character and competence.

8-2 PROGRESS SCHEDULE

Promptly after the award of the contract, if requested, the Contractor shall submit to the Owner a satisfactory progress schedule, which shall show the proposed sequence of work, and how the Contractor proposes to complete the various items of work within the number of days set up on the contract. The progress schedule shall be reviewed and revised periodically as working conditions warrant. The Contractor shall confer with the Owner in regard to the prosecution of the Work in accordance with this schedule. This schedule shall be used as a basis for establishing major construction operations, and for checking progress of the Work.

8-3 PRE-CONSTRUCTION CONFERENCE

Unless the need for a preconstruction conference is waived by the Engineer, the Contractor shall make himself and his representatives available to meet with the Engineer and other representatives of the Owner, prior to the start of construction to discuss scheduling, handling of materials, payments, etc.

8-4 PROSECUTION OF THE WORK

The Contractor shall begin the Work to be performed under the contract not later than ten (10) days after the execution and acceptance of the Contract, unless otherwise provided, but not prior to the execution of the Contract.

8-5 COMPLETION DATE

The Contractor shall complete all Work on or before the stipulated completion date, or on or before a later date determined as specified herein; otherwise, the Owner may proceed to collect liquidated damages described hereinafter.

When a delay occurs due to unforeseen causes beyond the control and without the fault or negligence of the Contractor, including, but not restricted to, acts of the public enemy, governmental acts, fires, floods, epidemics, strikes, extraordinary delays in delivery of materials caused by strikes, lockouts, wrecks, freight embargoes, governmental acts, or acts of God, the time of completion shall be extended in whatever amount is determined by the Owner.

An "Act of God" means an earthquake, flood, cloudburst, cyclone, or other cataclysmic phenomena of nature beyond the power of the Contractor to foresee or make preparation in defense against. A rain, windstorm or other natural phenomenon of normal intensity, based on U.S. Weather Bureau reports, for the particular locality and for the particular season of the year in which the work is being prosecuted, shall not be construed as an "Act of God", and no extension of time will be granted for the delays resulting therefrom.

8-6 LIMITATIONS OF OPERATIONS

The Contractor shall conduct his work so as to create a minimum amount of inconvenience to vehicular and pedestrian traffic. At any time when, in the judgment of the Owner, the Contractor has obstructed or closed the road or is carrying on operations on a greater portion of a street than is necessary for the proper prosecution of the Work, the Owner may require the Contractor to finish the section on which Work is in progress before the Work is started on any additional section. (See also Section 7-7).

8-7 SUSPENSION OF WORK

The Owner shall have authority to suspend the Work wholly or in part, for such period of time as he may deem necessary, due to conditions unfavorable for the satisfactory prosecution of the Work, or to conditions which in his opinion warrant such action; or for such time as is necessary by reason of failure on the part of the Contractor to carry out orders given, or to perform any or all provisions of the Contract. No additional compensation will be paid the Contractor because of any costs caused by such suspension, except when the suspension is ordered for reasons not resulting from any act or omission on the part of the Contractor. If it becomes necessary to stop Work for an indefinite period of time, the Contractor shall store all material in such manner that they will not obstruct or impede the traveling public unnecessarily or become damaged in any way, take every precaution to prevent damage or deterioration of the Work performed, provided suitable drainage of the roadway, and erect temporary structures where necessary. The Contractor shall not suspend Work without written authority from the Owner. (See also Section 7-15).

8-8 DETERMINATION AND EXTENSION OF CONTRACT TIME FOR COMPLETION

When the time for completion of the Work contemplated is specified in the Contract, it is understood that the completion of the Work within the time specified is an essential part of the Contract. If the Contractor finds it impossible to complete the Work within the time specified in the Contract, he may, at

any time prior to the last thirty (30) days of the Contract time specified, make written request to the Owner for an extension of Contract time. He shall set forth in full in his request the reasons, which he believes justify the granting of his request. If the Owner finds that the Work is delayed because of conditions beyond the control of the Contractor, or that the quantities of work done, or to be done, are in excess, he shall promptly grant an extension of time for completion, which appears reasonable and proper. The extended time for completion shall then be considered as in effect the same as if it were the original Contract time for completion.

8-9 FAILURE TO COMPLETE THE WORK ON TIME

Should the Contractor fail to complete the Work within the Contract time the Contractor shall be liable to the Owner in the amount shown in the following schedule of deductions, as liquidated damages, and not as a penalty, for each day of overrun in the Contract time or such extended time as may have been allowed.

SCHEDULE OF DEDUCTIONS FOR EACH DAY OF OVERRUN IN CONTRACT TIME

Original Contract Amount		Daily Charge	
From more than	To and Including	Calendar Day	Work Day
\$ 0	100,000	\$ 475	\$ 675
100,000	500,000	750	1,050
500,000	1,000,000	1,025	1,425
1,000,000	3,000,000	1,275	1,725
3,000,000	6,000,000	1,425	2,000
6,000,000	12,000,000	2,300	3,450
12,000,000	And over	5,800	8,125

8-10 DEFAULT ON CONTRACT

If the Contractor fails to begin the Work under Contract within the time specified, or fails to perform the Work with sufficient workmen and equipment or with sufficient materials to insure the completion of said Work within the Contract time, or shall perform the Work unsuitable, or shall neglect or refuse to remove materials or perform anew such Work as shall be rejected as defective and unsuitable, or shall discontinue the prosecution of the Work, or if the Contractor shall become insolvent or be declared bankrupt, or shall commit any act of bankruptcy or insolvency, or shall make an assignment for the benefit of creditors, the Owner shall give notice in writing to the Contractor and his surety of such delinquency, said notice to specify the corrective measures required.

If the Contractor, within a period of ten (10) days after said notice, shall not proceed in accordance therewith, the Owner shall have full power and authority to forfeit the rights of the Contractor and at its

option to call upon the surety to complete the Work in accordance with the terms of the contract, or it may take over the Work, including any or all materials and equipment on the ground as may be suitable and acceptable, and may complete the Work with his own forces, or may enter into a new agreement for the completion of said Contract according to the terms and provisions thereof, or use such other methods as, in its opinion, shall be required for the completion of said Contract in an acceptable manner.

All costs and charges incurred by the Owner, together with the cost of completing the work under Contract, shall be deducted from the Contract amount. In case the expense so incurred by the Owner shall be less than the sum which would have been payable under the Contract if it had been completed by the Contractor, the Contractor shall be entitled to receive the difference subject to any claims for liens thereon in case such expense shall exceed the sum which would have been payable under the Contract, the Contractor and the surety shall be liable and shall pay to the Owner the amount of such excess.

8-11 TERMINATION OF THE CONTRACTOR'S RESPONSIBILITY

Whenever the Work called for by the Contract shall have been completely performed on the part of the Contractor and all parts of the Work have been approved and deemed to be in compliance with the Technical Plans and Specifications by the Engineer, according to the Contract, and the final estimate paid, the Contractor's obligations shall be considered fulfilled, except as set forth in his Bond, in Section 7-18 and his one-year guarantee, in Section 7-16.

SECTION 9. MEASUREMENT AND PAYMENT

9-1 MEASUREMENT OF QUANTITIES

All Work completed under the Contract will be measured by the Engineer according to United States Standard Measures. The method of measurement shall be described in the Specifications or the Special Provisions.

9-2 SCOPE OF PAYMENT

The Contractor shall receive and accept the compensation as herein provided, in full payment for furnishing all materials, labor, tools and equipment; for performing all Work contemplated and embraced under the Contract; for all loss or damage arising out of the nature of the Work or from action of the elements; for any unforeseen difficulties or obstructions which may arise or be encountered during the prosecution of the Work until its final acceptance by the Owner; for all risks of every description connected with the prosecution of the Work; also, for all such expenses incurred by or in consequence of suspension or discontinuance of such prosecution of the work as herein specified, or for any infringement of patents, trademarks, or copyrights, and for completing the Work in an acceptable manner according to the Contract Documents.

Contractor will be paid in cash and/or negotiable warrants at intervals, and in accord with the terms of the Contract. Except for subdivision contracts, the Owner will retain ten percent (10%) of each periodic payment until final completion and acceptance by the Owner of all Work included in the Contract.

The payment of any current estimate prior to final acceptance of the Work by the Owner shall in no way constitute an acknowledgment of the acceptance of the Work, nor in any way prejudice or affect the obligation of the Contractor, at his expense, to repair, correct, renew, or replace any defects or imperfections in the construction or in the strength or quality of the materials used in or about the construction of the Work under Contract and its appurtenances, nor any damage due or attributable to such defects, which defects, imperfections, or damage shall have been discovered on or before the final inspection and acceptance of the Work. Defects, imperfections, or damage, shall be determined by the Engineer observing the work for compliance with the Plans and Specifications, and the Contractor shall be liable to the Owner for failure to correct the same as provided herein.

9-3 INCREASED OR DECREASED QUANTITIES

Whenever the quantity of any item of Work as given in the Proposal shall be increased or decreased, payment shall be made on the basis of the actual quantity completed at the unit price for such item named in the Proposal, except as otherwise provided in Sections 4-3 or in the detailed specifications for each class of Work.

9-4 PAYMENT FOR EXTRA WORK

Extra Work which results from any of the changes as specified in Section 4-3 shall not be started, except in case of an emergency, until receipt of a written authorization or Work order from the Owner, which authorization shall state the items of work to be performed and the method of payment for each item. Work performed without such order will not be paid for.

Extra work will be paid for:

- A. Either at a lump sum price or at unit prices agreed upon by the Contractor and the Owner. (In case a Supplemental Agreement is signed between the Contractor and the Owner, the agreed prices pertaining thereto shall prevail).

- B. If acceptable to the Engineer, on the following force account basis:
 - 1. Labor. The Contractor will be paid the actual amount of wages for all labor and foreman in direct charge of the specific Work for each hour that said labor and foreman are actually engaged in such Work, to which cost shall be added twenty percent (20%) of the sum thereof.

 - 2. Bond, Insurance, Tax, Welfare Fund and other Payments. The Contractor will receive the actual cost of Contractor's bond, public liability and property damage insurance, workmen's compensation insurance, social security tax, welfare fund and other payments, if any, in accordance with agreements applicable to the Contract, required for force account work, to which no percentage shall be added. The Contractor shall furnish satisfactory evidence of the rate or rates paid for such bond, insurance tax, welfare fund and other payments.

 - 3. Materials. The Contractor will receive the actual cost for all materials which are an integral part of the finished Work, including freight charges as shown by the original receipted bills, to which shall be added fifteen percent (15%) of the sum thereof.

The Contractor will be reimbursed for any materials used in the construction of the Work, such as sheeting, false work, form lumber, curing materials, etc., which are not an integral part of the finished Work. The amount of reimbursement shall be agreed upon in writing before such Work is begun, and no percent shall be added. The salvage value of such materials shall be taken into consideration in the reimbursement agreed upon.

4. **Equipment.** Machinery and equipment, which the Contractor has on the job for use on contract items, shall be used on extra Work as deemed necessary or desirable. The Contractor will be paid for all machinery and equipment used on extra work in accordance with the latest revision of "SCHEDULE OF AVERAGE ANNUAL EQUIPMENT OWNERSHIP EXPENSE WITH OPERATING COST" as issued by the Department of Transportation, State of Illinois, for the period that said machinery and equipment are in use on such Work, to which no percent shall be added. In the event that equipment is used which is not included in aforesaid publication, the latest edition of the "Compilation of Nationally Averaged Rental Rates for Construction Equipment" compiled by Equipment Distributors, 615 West 22nd Street, Oak Brook, Illinois 60521, shall be used to determine equipment rental rates and no percent shall be added to the rates indicated in such publication.

9-5 PAYMENT FOR SUBCONTRACTING, EXTRA WORK

Where an authorized subcontractor performs some or all of the Work qualifying as an Extra Work item and compensation is to be based on the terms of paragraph 9-4 (2), the cost of labor, bonds, material and equipment shall be the cost to the subcontractor on these items and an additional allowance to the prime Contractor of five percent (5%) of all costs as determined in paragraph 9-4 (2) shall be made in such instances.

9-6 PARTIAL PAYMENTS

Once each month, the Contractor will make an approximate estimate, in writing, of the materials in place complete, the amount of Work performed, and the value thereof, at the contract unit prices. From the amount so determined of completed work there shall be deducted ten percent (10%) to be retained until after the completion of the entire Work to the satisfaction of the Owner, and the balance certified to the Owner for payment.

In addition, an estimate may, at the discretion of the Owner and upon presentation of receipted bills and freight bills, be made for payment of the value of acceptable non-perishable materials delivered at the Work site or in acceptable storage places and not used at the time of such estimate. The care and storage of such material shall be the Contractor's responsibility. In the absence of receipted bills, an estimate may, at the request of the Contractor and at the discretion of the Owner, be made for payment of the value of materials in acceptable storage places and not used at the time of the estimate, but in such an event payment shall be made of such amounts by a check requiring the endorsement of both the Contractor and materials supplier. Endorsement of such a check by the material supplier shall be construed a waiver of lien for the cost of materials covered by the check. Such materials, when so paid for by the Owner, shall become the property of the Owner, and in the event of default on the part of the Contractor, the Owner may use or cause to be used such materials in the construction of the Work

provided for in the Contract. The amount thus paid by the Owner shall be deducted from estimates due the Contractor as the material is used in the Work.

9-7 ACCEPTANCE AND FINAL PAYMENT

Whenever the Work provided for by the Contract shall have been completely performed on the part of the Contractor, and all parts of the Work have been deemed to be in substantial compliance with the Plans and Specifications by the Engineer and accepted by the Owner, a final estimate showing the value of the Work will be prepared by the Engineer as soon as the necessary measurements and computations can be made, all prior estimates upon which payments have been made being approximate only and subject to correction in the final payment. The amount of this estimate, less any sums that have been deducted or retained under the provisions of the Contract, will be paid to the Contractor as soon as practicable after the final acceptance, provided the Contractor has furnished to the Owner satisfactory evidence that all sums of money due for any labor, materials, apparatus, fixtures, or machinery furnished for the purpose of such Work have been paid or that the person or persons to whom the same may be due have consented to such final payment.

Neither the final payment on this contract by the Owner nor any provisions in the contract documents shall relieve the Contractor of the responsibility for negligence in the furnishing and installation of faulty materials or for faulty workmanship which shows up within the extent and period provided by law or within the guarantee period of one (1) year from final acceptance of the work performed under this Contract, whichever is greater, nor of the responsibility of remedying such faulty workmanship and materials.

The acceptance by the Contractor of the final payment shall constitute a release and waiver of all claims by the Contractor except those previously made and still unsettled.

9-8 OWNER'S RIGHT TO WITHHOLD CERTAIN AMOUNTS

The Owner may withhold, in addition to retained percentages, from payment to the Contractor, such an amount or amounts as may be necessary to cover:

- A. Payments that may be earned or due for just claims for labor and materials furnished in and about the Work.
- B. For defective Work not remedied.
- C. For failure of the Contractor to make proper payments to his subcontractors.
- D. For reasonable doubt that the contract can be completed for the balance then unpaid.

The Owner will disburse and shall have the right to act as agent for the Contractor in disbursing such funds as have been withheld pursuant to this paragraph to the party or parties who are entitled to payment therefrom. The Owner will render to the Contractor a proper accounting of all such funds disbursed in behalf of the Contractor.

The Owner also reserves the right, even after full completion and acceptance of the Work, to refuse payment of the final ten percent (10%) due the Contractor, until it is satisfied that all subcontractors, material suppliers, and employees of the Contractor have been paid in full.

9-9 RELEASE OF CLAIMS AND LIENS

Neither the final payment nor any part of the retained percentage shall become due until the Contractor shall deliver to the Owner a complete release of all claims or liens arising out of this contract, or receipts in full in lieu thereof and, if required in either case, an affidavit that so far as he has knowledge or information the release and receipts include all the labor and materials for which a lien or claim could be filed; but the Contractor may, if a subcontractor refuses to furnish a release or receipt in full, furnish a bond satisfactory to the Owner to indemnify the Owner against any claim or lien (in cases where such payment is not already guaranteed by surety bond). If any claim or lien remains unsatisfied after all payments are made, the Contractor shall refund to the Owner all monies that the latter may be compelled to pay in discharging such a lien, including all costs and a reasonable attorney's fee.

DIVISION II

Technical Specifications

EXCAVATION AND CLEANUP

<u>SECTION 1. EXCAVATION AND BACKFILL FOR UNDERGROUND CONDUITS</u>	1
1-1 DESCRIPTION	1
1-2 CONSTRUCTION DETAILS	1
<u>SECTION 2. RESTORATION OF SURFACES</u>	13
2-1 GENERAL	13
2-2 CONSTRUCTION DETAILS	13
<u>SECTION 3. FINISHING AND CLEAN UP FOR UNDERGROUND CONDUITS</u>	16
3-1 CLEAN UP	16

SECTION 1. EXCAVATION AND BACKFILL FOR UNDERGROUND CONDUITS

1-1 DESCRIPTION

For the purpose of this section, underground conduits shall be considered sewer pipe, water main or any other pipe conduit indicated on the Plans. Wherever the term "pipe" or "pipe line" is used, it shall mean underground conduit.

Excavation and backfill shall include all excavation, backfilling, compacting, disposal of surplus material, restoration of all disturbed surface, and all other work incidental to the construction of trenches, including any additional excavation which may be required for manholes or other structures forming a part of the pipe line.

1-2 CONSTRUCTION DETAILS

1-2.01 SURFACE REMOVAL AND TOPSOIL PRESERVATION

Along the proposed pipe lines as indicated on the Plans, the Contractor shall remove the surface materials only to such widths as will permit a trench to be excavated which will afford sufficient room for proper efficiency and proper construction. Where sidewalks, driveways, pavements and curb and gutter are encountered, care shall be taken to protect such against fracture or disturbance beyond reasonable working limits. In areas specified on the Plans, topsoil suitable for final grading and landscaping shall be piled separately in locations approved by the Owner and preserved so that it may be restored after the remainder of the backfill is replaced.

1-2.02 WIDTH OF EXCAVATION

- A. The bottom width of the trench at and below the top of the pipe and inside the sheeting and bracing, if used, shall be in accordance with Section 550.04 of the Standard Specifications, unless otherwise noted.

Note: The strength or class of pipe shall be as indicated on the Plans.

- B. Trench sheeting and bracing or a trench shield shall be used as required by the rules and regulations of O.S.H.A. The Engineer shall not be responsible for determining whether the contractor is in compliance with this provision. The bottom of the trench excavation shall conform to the details shown on the Plan.
- C. If these trench widths are exceeded without the written permission of the Engineer, the pipe shall be installed with a concrete cradle or with concrete encasement or a stronger pipe than originally specified shall be used as approved by the Engineer.

1-2.03 EXCAVATION BELOW GRADE

In cases where the excavation is carried beyond or below the lines and grades given by the Engineer, the Contractor shall, at his own expense, refill all such excavated space with suitable granular material.

1-2.04 ROCK EXCAVATION

A. GENERAL

Wherever "rock" is used as the name of an excavated material, it shall mean boulders or pieces of rock, concrete, or masonry measuring one-half (1/2) cubic yard or more, hard shale or solid ledge rock and masonry which requires for its removal the continuous use of pneumatic tools or drilling and blasting.

Before payment is allowed for "Rock Excavation", the Contractor shall be required to demonstrate the material cannot be removed "by hand pick" or by power operated excavator or shovel. No payment will be made for Rock Excavation unless air tools or explosives were used by the Contractor. No payment will be made for "Rock Excavation" unless the Engineer approves such payment in writing in advance upon being satisfied that the material meets the above criteria.

B. MEASUREMENT FOR PAYMENT

Where "Rock Excavation" is to be measured for payment, quantities will be determined by the Engineer. Rock required to be removed shall be computed by the cubic yard. Width for pay purposes shall be the measured width of rock removed, but shall not exceed the width specified in Section 550.04 of the Standard Specifications, plus any sheeting and bracing if required. Depth for pay purposes shall be the difference in elevation between the top and bottom of the rock as determined by the Engineer. Where rock is encountered in the bottom of the trench, the maximum depth for payment purposes will be six inches (6") below the bottom of the pipe. Where the proposal does not contain a pay item for "Rock Excavation", the additional cost of rock removal as defined by the specifications shall be paid on extra work basis. (Division I, Section 9-4).

C. PAYMENT

Payment shall be made at the Contract unit price per cubic yard of "Rock Excavation". These prices shall be full compensation for furnishing all materials; for all preparation, excavation and disposal of rock; and for all labor, equipment, tools and incidentals necessary to complete the item.

1-2.05 SUBSURFACE EXPLORATION

All information available to the Owner, if any, on subsurface exploration will be made available for examination by prospective Bidders. However, it is understood and agreed that the Owner shall in no way be held responsible for interpretation of this information, its accuracy or its thoroughness. Prospective Bidders shall make such subsurface explorations as they believe necessary to verify and supplement information received from the Owner.

1-2.06 EXPLORATORY EXCAVATION

A. GENERAL

Whenever, in the opinion of the Engineer, it is necessary to explore an excavate in advance of the Work to determine the best line and grade for the construction of the proposed pipe line, the Contractor shall make explorations and excavations for such purposes.

B. PAYMENT

The cost of such excavation will be paid at the contract unit price per foot for "Exploration Trench", or if no Bid Item is included, on an extra work basis.

1-2.07 BRACED AND SHEETED TRENCHES

A. GENERAL

Open-cut trenches shall be sheeted and braced or otherwise protected as required by any governing Federal or State laws and municipal ordinances, and as may be necessary to protect life, property, or the Work. In any event, the minimum protection shall conform to the recommendations in the Occupational Safety and Health Act Standards for Construction (OSHA). A sand box or trench shield may be used in lieu of sheeting as permitted by OSHA. When close-sheeting is used, it shall be so driven as to prevent adjacent soil from entering the trench either below or through such sheeting. Tight sheeting shall be used in that portion of the excavation in or along state and county highways below the intersection of a 1 to 1 slope line from the nearest face of the excavation to the edge of the pavement.

Where sheeting and bracing are used, the trench width shall be increased accordingly. The sheeting will be driven to the full depth of work, or to a depth where the soil has the stability necessary to meet the OSHA standards, whichever is lower. The shallower depth of required sheeting may be established by soil boring and analysis, to be performed at the Contractor's sole cost. The owner shall have the right of consent in the selection of the soils engineer for the sampling and analysis. This provision shall not relieve the contractor, in any degree, from his responsibilities under the contract.

Sheeting and bracing, which are required to be left in place shall be cut off at the specified elevation. Trench bracing, except that specified to be left in place, may be removed when the backfilling reaches the said bracing's level. All sheeting except that required to be left in place may be removed as the excavation is refilled, in such a manner as to avoid bank cave-in(s) or disturbance to the adjacent area(s) or structure(s). The voids left by the withdrawal of the sheeting shall be carefully filled by jetting, vibrating, ramming or other satisfactory means.

B. PAYMENT

Payment for sheeting and bracing, and all other Work incidental to sheeting and bracing, shall not be made separately but shall be included in the Contract price for the pipe size, except when ordered left in place.

Payment for timber sheeting left in place when shown on the plans or directed by the Engineer shall be made at the Contract unit price per 1,000 board feet of "Timber Sheeting Left in Place."

Payment for steel sheet piling when specified shall be made at the Contract unit price per square foot for "Steel Sheet Piling."

Payment for steel sheet piling left in place when shown on the plans or directed by the Engineer shall be made at the Contract unit price per square foot for "Steel Sheet Piling Left in Place."

1-2.08 TRENCHES WITH SLOPING SIDES, LIMITED

The Contractor may, at his option, where working conditions and right-of-way permit, excavate pipe line trenches with sloping sides, but with the following limitations:

- A. In general, only braced and vertical trenches will be permitted in traveled streets, alleys or narrow easements.
- B. Where trenches with sloping sides are permitted, the slopes shall not extend below the top of the pipe, and trench excavations below this point shall be made with vertical sides with widths not exceeding those specified hereinbefore for the various sizes of pipe.

1-2.09 SHORT TUNNELS

In some instances, trees, fire hydrants, sidewalks and other obstructions may be encountered, the proximity of which may be a hindrance to open-cut excavation. In such cases, the Contractor shall excavate by means of short tunnels in order to protect such obstructions against damage. Where such obstructions are shown on the Plans, short tunnel work shall be considered incidental to the construction of the pipe line and shall not be grounds for extra payment or payment for tunnel work. Where such obstructions are not shown on the Plans, payment will be at the Contract unit price or as extra work in accordance with Division I, Section 9-4.

1-2.10 PILING EXCAVATION MATERIAL

All excavated material shall be stockpiled to avoid obstructing streets, sidewalks and driveways. Excavated material suitable for backfilling shall be stockpiled separately on the site. No material shall be placed closer than 2'0" to the edge of an excavation. Fire hydrants under pressure, valve pit covers, valve boxes, curb top boxes, or other utility controls shall be left unobstructed and accessible until the Work is completed. Gutters shall be kept clear or other satisfactory provisions made for street drainage. Natural watercourses shall not be obstructed or polluted. Surplus material and excavated material unsuitable for backfilling shall be transported and disposed of off the site in disposal areas obtained by the Contractor.

1-2.11 REMOVAL OF WATER

The Contractor shall at all times during construction provide and maintain ample means and devices with which to promptly remove and properly dispose of all water entering the excavations or other parts of the Work until all Work to be performed therein has been completed. No sanitary sewer shall be used for disposal of trench water, unless specifically approved by the Engineer and then only if the trench water does not ultimately arrive at existing pumping or sewage treatment facilities. No water containing settle able solids shall be discharged into storm sewers.

1-2.12 BLASTING

Blasting for excavation will be permitted only after securing the approval of the Owner and only when proper precautions are taken for the protections of persons and property. The hours of blasting will be reviewed by the Owner. Any damage caused by blasting shall be repaired by the Contractor at his expense. The Contractor's methods of procedure in blasting shall conform to Federal and State laws and municipal ordinances and O.S.H.A. rules and regulations. The Engineer shall not be responsible for determining whether the contractor is in compliance with these rules and regulations.

1-2.13 SAFETY

A. BARRICADES, GUARDS AND SAFETY PROVISIONS

To protect persons from injury and to avoid property damage, adequate barricades, construction signs, lights and guards as required shall be placed and maintained by the Contractor at his expense during the progress of the construction Work and until it is safe for traffic to use the roads and streets. All material piles, equipment and pipe which may serve as obstructions to traffic shall be enclosed by fences or barricades and shall be protected by proper lights when the visibility is poor. The rules and regulations of O.S.H.A. and appropriate authorities respecting safety provisions shall be observed. The Engineer shall not be responsible for determining whether the contractor is in compliance with these rules and regulations.

B. STRUCTURE PROTECTION

Temporary support, adequate protection and maintenance of all underground and surface structures, drains, sewers and other obstructions encountered in the progress of the Work shall be furnished to the Contractor at his expense. Any structures which may have been disturbed shall be restored upon completion of the Work.

C. PROTECTION OF PROPERTY AND SURFACE STRUCTURES

Trees, shrubbery, fences, poles and all other property and surface structures shall be protected during construction operations unless their removal for purposes of construction is authorized by the Engineer. Any fences, poles, or other man-made surface improvements which are moved or disturbed by the Contractor shall be restored to the original conditions, after construction is completed, at the Contractor's expense. Any trees, shrubbery or other vegetation which are approved for removal or ordered for removal by the Engineer in order to facilitate construction operations shall be removed completely, including stumps and roots, by the Contractor. Responsibility for any damage or claims for damage caused by construction operations to shrubbery or other landscape improvements which were not authorized for removal by the Engineer shall be assumed by the Contractor.

1-2.14 DEVIATIONS OCCASIONED BY STRUCTURES OR UTILITIES

Wherever obstructions are encountered during the progress of the Work and interfere to such an extent that an alteration in the plan is required, the Engineer shall have the authority to change the Plans and order a deviation from the line and grade or arrange with the owners of the structures for the removal, relocation or reconstruction of the obstructions. Where gas, water, telephone, electrical, hot water, steam, or other existing utilities are an impediment to the vertical or horizontal alignment of the proposed pipe line, the Engineer shall order a change in grade or alignment or shall direct the Contractor to arrange with the owners of the utilities for their removal.

1-2.15 INTERRUPTION TO UTILITIES

The Contractor shall proceed with caution in the excavation and preparation of the trench so that the exact location of underground structures may be determined. Prior to proceeding with trench excavation, the Contractor shall contact all utility companies in the area to aid in locating their underground services.

The Contractor shall take all reasonable precautions against damage to existing utilities. However, in the event of a break in an existing water main, gas main, sewer or underground cable, he shall immediately notify the responsible official of the organization operating the utility interrupted. The Contractor shall lend all possible assistance in restoring services and shall assume all cost, charges, or claims connected with the interruption and repair of such services if the location of said utility was marked by the owner thereof prior to excavation.

1-2.16 MAINTENANCE OF TRAFFIC AND CLOSING OF STREETS

The Contractor shall carry on the Work in a manner which will cause a minimum of interruption to traffic, and may close to through travel not more than two consecutive blocks, including the cross street intersected. Where traffic must cross open trenches, the Contractor shall provide suitable bridges at street intersections and driveways. The Contractor shall post suitable signs indicating that a street is closed and necessary detour signs for the proper maintenance of traffic. Prior to closing of any streets, the Contractor shall notify responsible municipal authorities at least five (5) days in advance of the starting of the Work, unless otherwise approved by the municipality.

1-2.17 CONSTRUCTION IN EASEMENTS

In easements across private property, the Contractor shall confine all operations in the easement area and shall be responsible and liable for all damage outside of the easement area. Trees, fences, shrubbery or other type of surface improvements located in the easements will require protection during construction. The provisions of Section 1-2.14C above shall apply to all easement areas as well as to public right-of-way. Precautions shall be taken by adequate sheeting or other approved method to prevent any cave-in or subsidence beyond the easement limits or damage to improvements within the easement. In general, the easement area is intended to provide reasonable access and working area for efficient operation by the Contractor. Where easement space for efficient operation is not provided, the Contractor shall be responsible for organizing his operations to perform within the restrictions shown on the Plans. The Owner shall make available to the Contractor a copy of the construction easements.

1-2.18 UNDERGROUND CONDUIT CONSTRUCTED IN TUNNEL

A. GENERAL

Where shown on the plans or where specifically authorized by the Engineer, pipe lines shall be constructed in tunnel. This work will be made in accordance with requirements of any permits obtained by the Owner from railroads or state or county highway departments for tunnel work or in accordance with the following paragraph.

B. MATERIALS

Pipe materials shall be as shown on the Plans or as described in the Special Provisions.

C. EXCAVATION AND LAYING

Requirements for excavation and laying and for joints shall be those applicable for the type of pipe line involved, unless otherwise specified.

Before starting excavations for tunnel shafts or jacking or augering pits, the Contractor shall submit drawings of proposed sheeting and bracing arrangements which have been prepared, signed and sealed by a structural Engineer registered in the State of Illinois for Work in Illinois and by a structural Engineer registered in the State of Indiana for Work in Indiana.

An adequate ventilation system shall be provided to properly ventilate all parts of the tunnel.

D. METHODS OF CONSTRUCTION

1. The tunnel shall be only of sufficient width and height to provide free working space. The sides and roof of the tunnel shall be braced sufficiently to support the external loads and to prevent caving, bulging, and settlement of the earth.
2. The Contractor shall backfill all tunnels with well compacted sand, fine gravel or stone screenings as rapidly as the conditions permit.
3. The backfill material shall be deposited in the tunnel in such a manner as not to injure or disturb the pipe. The filling of the tunnel shall be carried on simultaneously on both sides of the pipe in such a manner that injurious side pressures do not occur. Special care shall be taken to compact the backfill under the haunches of the pipe. The remainder of the tunnel, or such portion of the remainder as may be possible, shall then be backfilled by one of the following methods, at the option of the Contractor.
 - a. The material shall be deposited in uniform layers not to exceed twelve inches (12") thick (loose measure) and such layer either inundated or deposited in water.

- b. The tunnel shall be backfilled with loose material or only partly backfilled at a time, if necessary, and settlement secured in either case by introducing water through holes jetted into the material to a point approximately two feet (2') above the top of the pipe.
4. If neither of the above methods is practicable or can be used for only a portion of the backfill, the remainder of the tunnel shall be completely backfilled with material carefully deposited in uniform layers and each layer compacted by ramming or tamping with appropriate tools.
5. When sheeting and bracing have been used, sufficient bracing shall be left across the trench as the backfilling progresses to hold the sides and top firmly in place without caving or settlement before the backfilling has been placed. This bracing may be removed as soon as practicable.
6. Any depressions which may develop within the area involved in the construction operations due to settlement of the backfilling material shall be filled.

E. USE OF CASING PIPE

The Contractor may use metal casing pipe as a tunnel liner in place of timber shoring for tunnel sections. The design data for such pipe, including, but not necessarily limited to, the diameter, gauge, type of pipe, method of placing and installation will be submitted for the owner's review. The void space between tunnel liners or casing pipe and the carrier pipe shall be filled with compacted sand or other approved material.

F. JACKING OR BORING OF PIPE

The Contractor may, subject to the approval of the Owner, use special cast iron or specially designed reinforced concrete jacking pipe jacked and/or bored into position with or without tunnel liners, for tunneled sections pipe.

G. MEASUREMENT AND PAYMENT

Underground conduit constructed in tunnel will be paid for at the unit prices Bid for "Underground Conduit Constructed in Tunnel" for the various type and sizes for the actual length of tunnel Work. Payment shall include all labor, materials and equipment necessary to construct the conduit and tunnel, complete in place, including excavation and backfill, shoring and bracing, furnishing and laying casing pipe where required and carrier pipe, and all other Work necessary for a complete installation.

1-2-19 SANITARY SEWERS

A. GENERAL

The methods of excavating and backfilling sanitary sewer pipe shall be in compliance with the latest edition of the Illinois Department of Transportation, "Standard Specifications for Road and Bridge Construction", and the Metropolitan Water Reclamation District of Greater Chicago, "Manual of Procedure", latest revision. Where there is a conflict of these specifications, the MWRDGC, "Manual of Procedure" shall be used.

B. MATERIAL

Pipe material shall be as shown on the Plans or as described in the Special Provisions. No substitution of material shall be made without written approval from the Owner.

C. EXCAVATION AND BEDDING

The trench shall be excavated to an elevation to allow for the following bedding.

Bedding, other than concrete embedment, shall consist of gravel, crushed gravel, crushed stone or crushed slag, 1/4" to 1" in size. As a minimum, the material shall conform to the requirements of Article 1004.01 of the State Specifications or ASTM Designation C-33. The gradation shall conform to Section 1004, gradation CA 11 or CA 13 or to ASTM Gradation No. 67. The pipe shall be laid so that it will be uniformly supported and the entire length of the pipe barrel will have full bearing. No blocking of any kind shall be used to adjust the pipe to grade except when used with embedment concrete. Bedding shall be required for all sewer construction, except ductile iron pipe, and shall be of a thickness equal to 1/4 of the outside diameter of the sewer pipe with a maximum thickness of eight inches (8") but shall not be less than four inches (4").

Where unsuitable material is encountered at the grade established, all such unsuitable soil shall be removed under the pipe and for the width of the trench, and shall be replaced with well compacted bedding material, to the satisfaction of the Engineer.

Where rock is encountered, it shall be removed below grade and replaced with a cushion of well compacted bedding material having a thickness under the pipe of not less than eight inches (8").

The cost of furnishing, placing and compacting bedding material will be considered as incidental work and no additional compensation will be allowed.

D. BACKFILLING

The backfilling of the sanitary sewer pipe trench shall be the same as for storm sewer pipe described in Section 550.07 of the Standard Specifications.

E. METHOD OF MEASUREMENT

The method of measurement shall be the same as for storm sewer pipe described in Section 550.09 of the Standard Specifications except measurements will be made to the center of manholes.

F. BASIS OF PAYMENT

This work will be paid for at the Contract unit price per foot for "Sanitary Sewer" of the type and diameter specified and measured as specified.

"Trench Backfill", when specified, will be measured and paid for at the Contract unit price per foot unless otherwise stated in the Special Provisions or contract documents.

1-2.20 WATER MAINS

A. GENERAL

The method of excavating and backfilling water mains shall be in compliance with the latest edition of the Illinois Department of Transportation, "Standard Specifications for Road and Bridge Construction," and those below.

B. MATERIAL

Pipe material shall be as shown on the Plans or as described in the Special Provisions. No substitution of material shall be made without written approval of the Owner.

C. EXCAVATION AND BEDDING

The trench shall be excavated to an elevation to allow the minimum cover over the pipe as called for on the plans. Provision must be made by the Contractor to allow for any future cuts to be made to the ground over the pipe to assure that the minimum cover is maintained.

Bedding as described in Section 1-2.21C for sanitary sewers shall be required for all water mains, except ductile iron pipe that requires no bedding. The method of bedding for unsuitable material and where rock is encountered shall also comply with the conditions of that Section.

The cost of furnishing, placing and compacting bedding material will be considered as incidental work and no additional compensation will be allowed.

D. BACKFILLING

The backfilling of the water main pipe shall be the same as for storm sewer pipe as described in Section 550.07 of the Standard Specifications except that the moist fine aggregate backfill to the elevation of the center of the pipe will not be required for ductile iron pipe. For PVC or any other type of pipe, the moist fine aggregate shall be

brought to a level 12" above the top of the pipe and it shall be compacted as described in that Section.

E. METHOD OF MEASUREMENT

"Water main" pipe of the different types and diameters will be measured by the lineal foot in place.

Unless they are listed as separate Bid items, the water main item shall include all fittings required and all other material, except trench backfill within the specified trench.

F. BASIS OF PAYMENT

This work will be paid for at the Contract unit price per lineal foot for "Water main" of the type and diameter specified and measured as specified.

"Trench Backfill", when specified, will be measured and paid for at the Contract unit price per foot, unless otherwise specified in the special provisions or contract documents.

SECTION 2. RESTORATION OF SURFACES

2-1 GENERAL

Restoration of surfaces shall include the removal of the existing surface, the disposal of surplus material, and the construction of new surfaces as indicated on the plans or Special Provisions. The type of surface restoration required shall be shown on the Plans or described in the Special Provisions.

2-2 CONSTRUCTION DETAILS

2-2.01 TEMPORARY SURFACE OVER TRENCH

Wherever conduits are constructed under traveled roadways, driveways, sidewalks, or other traveled surfaces, a temporary surface shall be placed over the top of the trench as soon as possible after compaction, as specified above, has been satisfactorily completed. The temporary surface shall consist of a minimum of six inches (6") of coarse aggregate conforming to the current specifications of the State Specifications for Grade No. CA-9 or CA-10. The top of the temporary surface shall be smooth and meet the grade of the adjacent undisturbed surface. The temporary surface shall be maintained at the Contractor's expense until final restoration of the street surface is completed, unless specific items for temporary aggregate is specified. No permanent restoration of street surface shall be initiated until authorized by the Engineer.

2-2.02 REMOVAL OF PAVEMENT, SIDEWALK, DRIVEWAY AND CURB

Wherever the pipe is located along or across an improved surface, the width of the trench shall be held as nearly as possible to the maximum width specified in Section 1-2.02. Where brick or concrete pavement, sidewalk, driveway or curbing is cut, the width of the cut shall exceed the actual width of the top of the trench by twelve inches (12") on each side or a total of two feet (2'). Exposed surfaces of portland cement or asphaltic concrete shall be cut with a pavement saw before breaking. Care shall be taken in cutting to insure that a straight joint is sawed.

2-2.03 REPLACEMENT OF PERMANENT TYPE PAVEMENT, SIDEWALKS, DRIVEWAYS, CURBS, GUTTERS AND STRUCTURES.

The Contractor shall restore (unless otherwise specified or ordered by the Engineer) all permanent type pavements, sidewalks, driveways, curbs, gutters, shrubbery, fences, poles and other property and surface structures removed or disturbed during or as a result of construction operations to a condition which is equal in appearance and quality to the condition that existed before the Work began. The surface of all improvements shall be constructed of the same material and match in appearance the surface of the improvement which was removed. Where trench backfill is used, the restoration shall be made as soon as possible after jetting of the backfill has been completed.

2-2.04 REPLACING EXISTING TEMPORARY STREET AND ALLEY SURFACES

A. GENERAL

For the purpose of this specification, all existing street and alley surfaces shall be considered temporary except:

(1) concrete or brick pavements; (2) an asphaltic concrete or a bituminous treated surface over a soil cement, concrete, crushed stone or selected gravel base. Specifically included as temporary street surfaces, shall be compacted earth, cinders, shale, mixtures of gravel and earth or crushed stone and earth, whether or not these respective materials are further stabilized by road oil or bituminous surface treatment. This work should not be confused with Temporary Surface Over Trench as specified in Section 2-2.01.

Where conduits are constructed under temporary street or alley surfaces, or where such surfaces are used for the placement of backfill material or are disturbed by construction operations, the Contractor shall reconstruct, by grading and shaping, the entire width of roadway, and any drainage facilities which may have existed, to the original condition at the Contractor's expense, including that portion within the specified trench width where removal and restoration is paid for under a separate payment item.

Where, in the opinion of the Engineer, the conduit is located in the traveled portion of the temporary street or alley traveled surface, a new temporary surface shall be constructed over the trench, as specified in Section 2-2.01 of this Division. After this surface has been placed, it shall be maintained by the Contractor until final restoration is authorized. Just prior to final restoration, the entire width of the street to be restored shall be scarified. For final surface restoration, the Contractor shall apply a bituminous treatment to the entire width of the traveled surface, as ordered by the Engineer. The bituminous treatment shall consist of the application of a bituminous prime coat and a bituminous surface treatment corresponding to the materials and construction methods described in the State Specifications for bituminous surface treatment, Class A-1, A-2, or A-3 as specified, or shown in the bid items.

The Engineer reserves the right to order the omission of Bituminous Surface Treatment in any locations where such omission may be, in his opinion, in the public interest.

B. MEASUREMENT

Measurement for purposes of payment shall be computed by using the actual length and width of surface to which treatment is applied, in accordance with these Specifications.

C. PAYMENT

The cost of final restoration of the surface shall be paid for at the contract unit price per foot, unless so stated in the Special Provisions or for all State of Illinois projects, for "Bituminous Surface Treatment", of the type specified. Such price shall include the cost of all labor and materials necessary to provide the bituminous treatment as specified.

2-2.05 DISPOSAL OF SURPLUS EXCAVATED MATERIAL

Surplus excavated material not needed for backfill shall be promptly removed from the site to locations provided by the Contractor. The cost of removal and disposal of surplus excavated materials will be included in the respective unit prices for pipeline or conduit construction and no additional payment will be allowed therefor.

2-2.06 CLEANING UP

All surplus materials and all tools and temporary structures shall be removed from the site by the Contractor. All dirt, rubbish and excess earth from the excavation shall be hauled to a dump provided by the Contractor and the construction site left clean and acceptable to the Owner at the earliest possible date.

SECTION 3. FINISHING AND CLEAN UP FOR UNDERGROUND CONDUITS

3-1 CLEAN UP

Before acceptance of underground conduits construction, all pipes, manholes, catch basins, fire hydrants and other appurtenances shall be cleaned of all debris and foreign material.

After all backfill has been completed, the ground surface shall be shaped to conform to the contour of adjacent surfaces. General clean up of the entire construction area shall otherwise conform to applicable requirements specified.

INDEX
FOR
SUPPLEMENTAL SPECIFICATIONS
AND RECURRING SPECIAL PROVISIONS

Adopted January 1, 2018

This index contains a listing of SUPPLEMENTAL SPECIFICATIONS, frequently used RECURRING SPECIAL PROVISIONS, and LOCAL ROADS AND STREETS RECURRING SPECIAL PROVISIONS.

ERRATA Standard Specifications for Road and Bridge Construction
(Adopted 4-1-16) (Revised 1-1-18)

SUPPLEMENTAL SPECIFICATIONS

<u>Std. Spec. Sec.</u>		<u>Page No.</u>
106	Control of Materials	1
403	Bituminous Surface Treatment (Class A-1, A-2, A-3)	2
404	Micro-Surfacing and Slurry Sealing	3
405	Cape Seal	14
420	Portland Cement Concrete Pavement	24
442	Pavement Patching	26
502	Excavation for Structures	27
503	Concrete Structures	29
504	Precast Concrete Structures	32
542	Pipe Culverts	33
586	Sand Backfill for Vaulted Abutments	34
630	Steel Plate Beam Guardrail	36
631	Traffic Barrier Terminals	39
670	Engineer's Field Office and Laboratory	40
701	Work Zone Traffic Control and Protection	41
704	Temporary Concrete Barrier	42
781	Raised Reflective Pavement Markers	44
888	Pedestrian Push-Button	45
1003	Fine Aggregates	46
1004	Coarse Aggregates	47
1006	Metals	50
1020	Portland Cement Concrete	51
1050	Poured Joint Sealers	53
1069	Pole and Tower	55
1077	Post and Foundation	56
1096	Pavement Markers	57
1101	General Equipment	58
1102	Hot-Mix Asphalt Equipment	59
1103	Portland Cement Concrete Equipment	61
1106	Work Zone Traffic Control Devices	63



Check Sheet For Recurring Special Provisions



The Following Recurring Special Provisions Indicated By An "X" Are Applicable To This Contract And Are Included By Reference:

Recurring Special Provisions

<u>Check Sheet #</u>		<u>Page No.</u>
1	<input type="checkbox"/> Additional State Requirements for Federal-Aid Construction Contracts	64
2	<input type="checkbox"/> Subletting of Contracts (Federal-Aid Contracts)	67
3	<input type="checkbox"/> EEO	68
4	<input type="checkbox"/> Specific EEO Responsibilities Non Federal-Aid Contracts	78
5	<input type="checkbox"/> Required Provisions - State Contracts	83
6	<input type="checkbox"/> Asbestos Bearing Pad Removal	89
7	<input type="checkbox"/> Asbestos Waterproofing Membrane and Asbestos Hot-Mix Asphalt Surface Removal	90
8	<input type="checkbox"/> Temporary Stream Crossings and In-Stream Work Pads	91
9	<input type="checkbox"/> Construction Layout Stakes Except for Bridges	92
10	<input type="checkbox"/> Construction Layout Stakes	95
11	<input type="checkbox"/> Use of Geotextile Fabric for Railroad Crossing	98
12	<input type="checkbox"/> Subsealing of Concrete Pavements	100
13	<input type="checkbox"/> Hot-Mix Asphalt Surface Correction	104
14	<input type="checkbox"/> Pavement and Shoulder Resurfacing	106
15	<input type="checkbox"/> Patching with Hot-Mix Asphalt Overlay Removal	107
16	<input type="checkbox"/> Polymer Concrete	109
17	<input type="checkbox"/> PVC Pipeliner	111
18	<input type="checkbox"/> Bicycle Racks	112
19	<input type="checkbox"/> Temporary Portable Bridge Traffic Signals	114
20	<input type="checkbox"/> Work Zone Public Information Signs	116
21	<input type="checkbox"/> Nighttime Inspection of Roadway Lighting	117
22	<input type="checkbox"/> English Substitution of Metric Bolts	118
23	<input type="checkbox"/> Calcium Chloride Accelerator for Portland Cement Concrete	119
24	<input type="checkbox"/> Quality Control of Concrete Mixtures at the Plant	120
25	<input checked="" type="checkbox"/> Quality Control/Quality Assurance of Concrete Mixtures	128
26	<input type="checkbox"/> Digital Terrain Modeling for Earthwork Calculations	144
27	<input type="checkbox"/> Reserved	146
28	<input type="checkbox"/> Preventive Maintenance - Bituminous Surface Treatment	147
29	<input type="checkbox"/> Reserved	153
30	<input type="checkbox"/> Reserved	154
31	<input type="checkbox"/> Reserved	155
32	<input type="checkbox"/> Temporary Raised Pavement Markers	156
33	<input type="checkbox"/> Restoring Bridge Approach Pavements Using High-Density Foam	157
34	<input type="checkbox"/> Portland Cement Concrete Inlay or Overlay	160
35	<input type="checkbox"/> Portland Cement Concrete Partial Depth Hot-Mix Asphalt Patching	164

The Following Local Roads And Streets Recurring Special Provisions Indicated By An "X" Are Applicable To This Contract And Are Included By Reference:

Local Roads And Streets Recurring Special Provisions

<u>Check Sheet #</u>		<u>Page No.</u>
LRS 1	Reserved	168
LRS 2	<input type="checkbox"/> Furnished Excavation	169
LRS 3	<input checked="" type="checkbox"/> Work Zone Traffic Control Surveillance	170
LRS 4	<input checked="" type="checkbox"/> Flaggers in Work Zones	171
LRS 5	<input type="checkbox"/> Contract Claims	172
LRS 6	<input type="checkbox"/> Bidding Requirements and Conditions for Contract Proposals	173
LRS 7	<input type="checkbox"/> Bidding Requirements and Conditions for Material Proposals	179
LRS 8	Reserved	185
LRS 9	<input type="checkbox"/> Bituminous Surface Treatments	186
LRS 10	Reserved	187
LRS 11	<input type="checkbox"/> Employment Practices	188
LRS 12	<input type="checkbox"/> Wages of Employees on Public Works	190
LRS 13	<input type="checkbox"/> Selection of Labor	192
LRS 14	<input type="checkbox"/> Paving Brick and Concrete Paver Pavements and Sidewalks	193
LRS 15	<input type="checkbox"/> Partial Payments	196
LRS 16	<input type="checkbox"/> Protests on Local Lettings	197
LRS 17	<input type="checkbox"/> Substance Abuse Prevention Program	198
LRS 18	<input type="checkbox"/> Multigrade Cold Mix Asphalt	199

BDE SPECIAL PROVISIONS
For the August 3 and September 21, 2018 Lettings

The following special provisions indicated by an "x" are applicable to this contract and will be included by the Project Development and Implementation Section of the BD&E. An * indicates a new or revised special provision for the letting.

<u>File Name</u>	<u>#</u>	<u>Special Provision Title</u>	<u>Effective</u>	<u>Revised</u>
80099	1	Accessible Pedestrian Signals (APS)	April 1, 2003	Jan. 1, 2014
80382	2	✓ Adjusting Frames and Grates	April 1, 2017	
80274	3	Aggregate Subgrade Improvement	April 1, 2012	April 1, 2016
80192	4	Automated Flagger Assistance Device	Jan. 1, 2008	
80173	5	Bituminous Materials Cost Adjustments	Nov. 2, 2006	Aug. 1, 2017
80241	6	Bridge Demolition Debris	July 1, 2009	
5026I	7	Building Removal-Case I (Non-Friable and Friable Asbestos)	Sept. 1, 1990	April 1, 2010
5048I	8	Building Removal-Case II (Non-Friable Asbestos)	Sept. 1, 1990	April 1, 2010
5049I	9	Building Removal-Case III (Friable Asbestos)	Sept. 1, 1990	April 1, 2010
5053I	10	Building Removal-Case IV (No Asbestos)	Sept. 1, 1990	April 1, 2010
80366	11	Butt Joints	July 1, 2016	
80386	12	Calcium Aluminate Cement for Class PP-5 Concrete Patching	Nov. 1, 2017	
80396	13	Class A and B Patching	Jan. 1, 2018	
80384	14	Compensable Delay Costs	June 2, 2017	
80198	15	Completion Date (via calendar days)	April 1, 2008	
80199	16	Completion Date (via calendar days) Plus Working Days	April 1, 2008	
80293	17	Concrete Box Culverts with Skews > 30 Degrees and Design Fills ≤ 5 Feet	April 1, 2012	July 1, 2016
80311	18	Concrete End Sections for Pipe Culverts	Jan. 1, 2013	April 1, 2016
80277	19	Concrete Mix Design – Department Provided	Jan. 1, 2012	April 1, 2016
80261	20	✓ Construction Air Quality – Diesel Retrofit	June 1, 2010	Nov. 1, 2014
80387	21	Contrast Preformed Plastic Pavement Marking	Nov. 1, 2017	
* 80029	22	Disadvantaged Business Enterprise Participation	Sept. 1, 2000	April 2, 2018
80378	23	Dowel Bar Inserter	Jan. 1, 2017	Jan. 1, 2018
80388	24	Equipment Parking and Storage	Nov. 1, 2017	
80229	25	Fuel Cost Adjustment	April 1, 2009	Aug. 1, 2017
80304	26	Grooving for Recessed Pavement Markings	Nov. 1, 2012	Nov. 1, 2017
* 80246	27	✓ Hot-Mix Asphalt – Density Testing of Longitudinal Joints	Jan. 1, 2010	Aug. 1, 2018
* 80398	28	Hot-Mix Asphalt – Longitudinal Joint Sealant	Aug. 1, 2018	
* 80399	29	Hot-Mix Asphalt – Oscillatory Roller	Aug. 1, 2018	
* 80347	30	Hot-Mix Asphalt – Pay for Performance Using Percent Within Limits – Jobsite Sampling	Nov. 1, 2014	Aug. 1, 2018
80383	31	Hot-Mix Asphalt – Quality Control for Performance	April 1, 2017	Nov. 1, 2017
80376	32	✓ Hot-Mix Asphalt – Tack Coat	Nov. 1, 2016	
80392	33	Lights on Barricades	Jan. 1, 2018	
80336	34	Longitudinal Joint and Crack Patching	April 1, 2014	April 1, 2016
* 80393	35	Manholes, Valve Vaults, and Flat Slab Tops	Jan. 1, 2018	March 2, 2018
* 80400	36	Mast Arm Assembly and Pole	Aug. 1, 2018	
80045	37	Material Transfer Device	June 15, 1999	Aug. 1, 2014
80394	38	Metal Flared End Section for Pipe Culverts	Jan. 1, 2018	April 1, 2018
80165	39	Moisture Cured Urethane Paint System	Nov. 1, 2006	Jan. 1, 2010
80349	40	Pavement Marking Blackout Tape	Nov. 1, 2014	April 1, 2016
80371	41	Pavement Marking Removal	July 1, 2016	
80390	42	Payments to Subcontractors	Nov. 2, 2017	
80377	43	Portable Changeable Message Signs	Nov. 1, 2016	April 1, 2017
80389	44	✓ Portland Cement Concrete	Nov. 1, 2017	
80359	45	Portland Cement Concrete Bridge Deck Curing	April 1, 2015	Nov. 1, 2017
* 80401	46	Portland Cement Concrete Pavement Connector for Bridge Approach	Aug. 1, 2018	

File Name	#	Special Provision Title	Effective	Revised
		Slab		
80385	47	Portland Cement Concrete Sidewalk	Aug. 1, 2017	
80300	48	Preformed Plastic Pavement Marking Type D - Inlaid	April 1, 2012	April 1, 2016
80328	49	Progress Payments	Nov. 2, 2013	
34261	50	Railroad Protective Liability Insurance	Dec. 1, 1986	Jan. 1, 2006
80157	51	Railroad Protective Liability Insurance (5 and 10)	Jan. 1, 2006	
80306	52	Reclaimed Asphalt Pavement (RAP) and Reclaimed Asphalt Shingles (RAS)	Nov. 1, 2012	Jan. 1, 2018
80395	53	Sloped Metal End Section for Pipe Culverts	Jan. 1, 2018	
80340	54	Speed Display Trailer	April 2, 2014	Jan. 1, 2017
80127	55	Steel Cost Adjustment	April 2, 2004	Aug. 1, 2017
* 80397	56	Subcontractor and DBE Payment Reporting	April 2, 2018	
80391	57	Subcontractor Mobilization Payments	Nov. 2, 2017	
80317	58	Surface Testing of Hot-Mix Asphalt Overlays	Jan. 1, 2013	April 1, 2016
80298	59	Temporary Pavement Marking (NOTE: This special provision was previously named "Pavement Marking Tape Type IV".)	April 1, 2012	April 1, 2017
20338	60	Training Special Provisions	Oct. 15, 1975	
80318	61	Traversable Pipe Grate for Concrete End Sections (NOTE: This special provision was previously named "Traversable Pipe Grate".)	Jan. 1, 2013	Jan. 1, 2018
80288	62	Warm Mix Asphalt	Jan. 1, 2012	April 1, 2016
80302	63	Weekly DBE Trucking Reports	June 2, 2012	April 2, 2015
80071	64	Working Days	Jan. 1, 2002	

The following special provisions are in the 2018 Supplemental Specifications and Recurring Special Provisions.

File Name	Special Provision Title	New Location	Effective	Revised
80368	Light Tower	Article 1069.08	July 1, 2016	
80369	Mast Arm Assembly and Pole	Article 1077.03(a)(1)	July 1, 2016	
80338	Portland Cement Concrete Partial Depth Hot-Mix Asphalt Patching	Recurring CS #35	April 1, 2014	April 1, 2016
80379	Steel Plate Beam Guardrail	Articles 630.02, 630.05, 630.06, and 630.08	Jan. 1, 2017	
80381	Traffic Barrier Terminal, Type 1 Special	Article 631.04	Jan. 1, 2017	
80380	Tubular Markers	Articles 701.03, 701.15, 701.18, and 1106.02	Jan. 1, 2017	

The following special provisions require additional information from the designer. The additional information needs to be submitted as a separate document. The Project Development and Implementation section will then include the information in the applicable special provision. The Special Provisions are:

- Bridge Demolition Debris
- Building Removal - Case I
- Building Removal - Case II
- Building Removal - Case III
- Building Removal-Case IV
- Completion Date
- Completion Date Plus Working Days
- DBE Participation
- Material Transfer Device
- Railroad Protective Liability Insurance
- Training Special Provisions
- Working Days

ADJUSTING FRAMES AND GRATES (BDE)

Effective: April 1, 2017

Add the following to Article 602.02 of the Standard Specifications:

- “(s) High Density Expanded Polystyrene Adjusting Rings
with Polyurea Coating (Note 4) 1043.04
- (t) Expanded Polypropylene (EPP) Adjusting Rings (Note 5) 1043.05

Note 4. High density expanded polystyrene adjusting rings with polyurea coating shall meet the design load requirements of AASHTO HS20/25. The rings may be used to adjust the frames and grates of drainage and utility structures up to a maximum of 6 in. (150 mm). They shall be installed and sealed underneath the frames according to the manufacturer’s specifications.

Note 5. Riser rings fabricated from EPP may be used to adjust the frames and grates of drainage and utility structures up to a maximum of 6 in. (150 mm). An adhesive meeting ASTM C 920, Type S, Grade N5, Class 25 shall be used with EPP adjustment rings. The top ring of the adjustment stack shall be a finish ring with grooves on the lower surface and flat upper surface. The joints between all manhole adjustment rings and the frame and cover shall be sealed using the approved adhesive. In lieu of the use of an adhesive, an internal or external mechanical frame-chimney seal may be used for watertight installation. EPP adjustment rings shall not be used with heat shrinkable infiltration barriers.”

Add the following to Section 1043 of the Standard Specifications:

“1043.04 High Density Expanded Polystyrene Adjusting Rings with Polyurea Coating. High density expanded polystyrene adjustment rings with polyurea coating shall be designed and tested to meet or exceed an HS25 wheel load according to the AASHTO Standard Specifications for Highway Bridges (AASHTO M306 HS-25). The raw material suppliers shall provide certifications of quality or testing using the following ASTM standards, and upon request, certify that only virgin material was used in the manufacturing of the expanded polystyrene rings.

Physical Property	Test Standard	Value	
		3.0 lb/cu ft	4.5 lb/cu ft
Compression Resistance at 10% deformation	ASTM D 1621	50 - 70	70 - 90
at 5% deformation		45 - 60	60 - 80
at 2% deformation		15 - 20	20 - 40
Flexural Strength	ASTM D 790	90 - 120	130 - 200
Water Absorption	ASTM D 570	2.0%	1.7%
Coefficient of Linear Expansion	ASTM D 696	2.70E-06 in./in./°F	2.80E-06 in./in./°F
Sheer Strength	ASTM D 732	55	80

Tensile Strength	ASTM D 1623	70 - 90	130 - 140
Water Vapor Transmission	ASTM C 355	0.82 – 0.86 perm – in.	

High density expanded polystyrene adjustment rings with polyurea coating shall have no void areas, cracks, or tears. The actual diameter or length shall not vary more than 0.125 in. (3 mm) from the specified diameter or length. Variations in height are limited to ± 0.063 in. (± 1.6 mm). Variations shall not exceed 0.25 in. (6 mm) from flat (dish, bow, or convoluting edge) or 0.125 in. (3 mm) for bulges or dips in the surface.

1043.05 Expanded Polypropylene (EPP) Adjusting Rings. The EPP adjusting rings shall be manufactured using a high compression molding process to produce a minimum finished density of 7.5 lb/cu ft (120 g/l). The EPP rings shall be made of materials meeting ASTM D 3575 and ASTM D 4819-13. The grade adjustments shall be designed and tested according to the AASHTO Standard Specifications for Highway Bridges (AASHTO M 306 HS-25).

Grade rings shall contain upper and lower keyways (tongue and groove) for proper vertical alignment and sealing. The top ring, for use directly beneath the cast iron frame, shall have keyways (grooves) on the lower surface with a flat upper surface.

Adhesive or sealant used for watertight installation of the manhole grade adjustment rings shall meet ASTM C 920, Type S, Grade NS, Class 25, Uses NT, T, M, G, A, and O.

EPP adjustment rings shall have no void areas, cracks, or tears. The actual diameter or length shall not vary more than 0.125 in. (3 mm) from the specified diameter or length. Variations in height are limited to ± 0.063 in. (± 1.6 mm). Variations shall not exceed 0.25 in. (6 mm) from flat (dish, bow, or convoluting edge) or 0.125 in. (3 mm) for bulges or dips in the surface."

CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)

Effective: June 1, 2010

Revised: November 1, 2014

The reduction of emissions of particulate matter (PM) for off-road equipment shall be accomplished by installing retrofit emission control devices. The term "equipment" refers to diesel fuel powered devices rated at 50 hp and above, to be used on the jobsite in excess of seven calendar days over the course of the construction period on the jobsite (including rental equipment).

Contractor and subcontractor diesel powered off-road equipment assigned to the contract shall be retrofitted using the phased in approach shown below. Equipment that is of a model year older than the year given for that equipment's respective horsepower range shall be retrofitted:

Effective Dates	Horsepower Range	Model Year
June 1, 2010 ^{1/}	600-749	2002
	750 and up	2006
June 1, 2011 ^{2/}	100-299	2003
	300-599	2001
	600-749	2002
	750 and up	2006
June 1, 2012 ^{2/}	50-99	2004
	100-299	2003
	300-599	2001
	600-749	2002
	750 and up	2006

1/ Effective dates apply to Contractor diesel powered off-road equipment assigned to the contract.

2/ Effective dates apply to Contractor and subcontractor diesel powered off-road equipment assigned to the contract.

The retrofit emission control devices shall achieve a minimum PM emission reduction of 50 percent and shall be:

- a) Included on the U.S. Environmental Protection Agency (USEPA) *Verified Retrofit Technology List* (<http://www.epa.gov/cleandiesel/verification/verif-list.htm>), or verified by the California Air Resources Board (CARB) (<http://www.arb.ca.gov/diesel/verdev/vt/cvt.htm>); or
- b) Retrofitted with a non-verified diesel retrofit emission control device if verified retrofit emission control devices are not available for equipment proposed to be used on the project, and if the Contractor has obtained a performance certification from the retrofit

device manufacturer that the emission control device provides a minimum PM emission reduction of 50 percent.

Note: Large cranes (Crawler mounted cranes) which are responsible for critical lift operations are exempt from installing retrofit emission control devices if such devices adversely affect equipment operation.

Diesel powered off-road equipment with engine ratings of 50 hp and above, which are unable to be retrofitted with verified emission control devices or if performance certifications are not available which will achieve a minimum 50 percent PM reduction, may be granted a waiver by the Department if documentation is provided showing good faith efforts were made by the Contractor to retrofit the equipment.

Construction shall not proceed until the Contractor submits a certified list of the diesel powered off-road equipment that will be used, and as necessary, retrofitted with emission control devices. The list(s) shall include (1) the equipment number, type, make, Contractor/rental company name; and (2) the emission control devices make, model, USEPA or CARB verification number, or performance certification from the retrofit device manufacturer. Equipment reported as fitted with emissions control devices shall be made available to the Engineer for visual inspection of the device installation, prior to being used on the jobsite.

The Contractor shall submit an updated list of retrofitted off-road construction equipment as retrofitted equipment changes or comes on to the jobsite. The addition or deletion of any diesel powered equipment shall be included on the updated list.

If any diesel powered off-road equipment is found to be in non-compliance with any portion of this special provision, the Engineer will issue the Contractor a diesel retrofit deficiency deduction.

Any costs associated with retrofitting any diesel powered off-road equipment with emission control devices shall be considered as included in the contract unit prices bid for the various items of work involved and no additional compensation will be allowed. The Contractor's compliance with this notice and any associated regulations shall not be grounds for a claim.

Diesel Retrofit Deficiency Deduction

When the Engineer determines that a diesel retrofit deficiency exists, a daily monetary deduction will be imposed for each calendar day or fraction thereof the deficiency continues to exist. The calendar day(s) will begin when the time period for correction is exceeded and end with the Engineer's written acceptance of the correction. The daily monetary deduction will be \$1,000.00 for each deficiency identified.

The deficiency will be based on lack of diesel retrofit emissions control.

If a Contractor accumulates three diesel retrofit deficiency deductions for the same piece of equipment in a contract period, the Contractor will be shutdown until the deficiency is corrected.

Such a shutdown will not be grounds for any extension of the contract time, waiver of penalties, or be grounds for any claim.

80261

HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE)

Effective: January 1, 2010

Revised: August 1, 2018

Description. This work shall consist of testing the density of longitudinal joints as part of the quality control/quality assurance (QC/QA) of hot-mix asphalt (HMA). Work shall be according to Section 1030 of the Standard Specifications except as follows.

Quality Control/Quality Assurance (QC/QA). Delete the second and third sentence of the third paragraph of Article 1030.05(d)(3) of the Standard Specifications.

Add the following paragraphs to the end of Article 1030.05(d)(3) of the Standard Specifications:

“Longitudinal joint density testing shall be performed at each random density test location. Longitudinal joint testing shall be located at a distance equal to the lift thickness or a minimum of 4 in. (100 mm), from each pavement edge. (i.e. for a 5 in. (125 mm) lift the near edge of the density gauge or core barrel shall be within 5 in. (125 mm) from the edge of pavement.) Longitudinal joint density testing shall be performed using either a correlated nuclear gauge or cores.

- a. Confined Edge. Each confined edge density shall be represented by a one-minute nuclear density reading or a core density and shall be included in the average of density readings or core densities taken across the mat which represents the Individual Test.
- b. Unconfined Edge. Each unconfined edge joint density shall be represented by an average of three one-minute density readings or a single core density at the given density test location and shall meet the density requirements specified herein. The three one-minute readings shall be spaced 10 ft (3 m) apart longitudinally along the unconfined pavement edge and centered at the random density test location.

When a longitudinal joint sealant (LJS) is applied, longitudinal joint density testing will not be required on the joint(s) sealed.”

Revise the Density Control Limits table in Article 1030.05(d)(4) of the Standard Specifications to read:

“Mixture Composition	Parameter	Individual Test (includes confined edges)	Unconfined Edge Joint Density Minimum
IL-4.75	Ndesign = 50	93.0 – 97.4% ^{1/}	91.0%
IL-9.5	Ndesign = 90	92.0 – 96.0%	90.0%
IL-9.5,IL-9.5L	Ndesign < 90	92.5 – 97.4%	90.0%
IL-19.0	Ndesign = 90	93.0 – 96.0%	90.0%
IL-19.0, IL-19.0L	Ndesign < 90	93.0 ^{2/} – 97.4%	90.0%

SMA	Ndesign = 50 & 80	93.5 – 97.4%	91.0%”
-----	-------------------	--------------	--------

80246

HOT-MIX ASPHALT – TACK COAT (BDE)

Effective: November 1, 2016

Revise Article 1032.06(a) of the Standard Specifications to read:

“(a) Anionic Emulsified Asphalt. Anionic emulsified asphalts shall be according to AASHTO M 140. SS-1h emulsions used as a tack coat shall have the cement mixing test waived.”

80376

PORTLAND CEMENT CONCRETE (BDE)

Effective: November 1, 2017

Revise the Air Content % of Class PP Concrete in Table 1 Classes of Concrete and Mix Design Criteria in Article 1020.04 of the Standard Specifications to read:

"TABLE 1. CLASSES OF CONCRETE AND MIX DESIGN CRITERIA		
Class of Conc.	Use	Air Content %
PP	Pavement Patching Bridge Deck Patching (10)	4.0 - 8.0"
	PP-1	
	PP-2	
	PP-3	
	PP-4	
	PP-5	

Revise Note (4) at the end of Table 1 Classes of Concrete and Mix Design Criteria in Article 1020.04 of the Standard Specifications to read:

"(4) For all classes of concrete, the maximum slump may be increased to 7 in (175 mm) when a high range water-reducing admixture is used. For Class SC, the maximum slump may be increased to 8 in. (200 mm). For Class PS, the maximum slump may be increased to 8 1/2 in. (215 mm) if the high range water-reducing admixture is the polycarboxylate type."

80389

SPECIAL
PROVISIONS

VILLAGE OF TINLEY PARK

TINLEY PARK CONVENTION CENTER PARKING LOT IMPROVEMENTS

SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction", adopted April 1, 2016; the latest editions of the "Supplemental Specifications and Interim Special Provisions" and the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways"; the "Manual of Test Procedures for Materials" in effect on the date of the invitation for bids; the Division I General Requirements and Covenants; and the Division II Technical Specifications which apply to and govern the proposed improvement in Cook County, and in case of conflict with any part, or parts, of said specifications, the said Special Provisions shall take precedence and shall govern.

However, in all cases, the Division I General Requirements and Covenants of the specifications shall take precedence over the Division 100 General Requirements and Covenants of the Standard Specifications for Road and Bridge Construction and shall govern.

SCOPE OF WORK

The work to be performed at this location will consist of Class D patching, removal and replacement of hot-mix asphalt surface course, pavement markings, and all incidental and collateral work necessary to complete the improvements as shown on the exhibits and as described herein. Final patching locations are subject to change based on field conditions and will be marked in the field by the Village or Authorized Representative. Coordination of work on this lot must be done well in advance due to Convention Center events. Full closure of the lots will not be allowed, and work must be completed in stages.

The quantities called for in this contract indicate the approximate amount of work to be expected. The actual amounts for the various items may vary depending upon actual field conditions. The Village reserves the right to reduce or increase the scope of project quantities and to delete entire line items. It shall be understood and agreed upon that the unit prices for these items shall prevail throughout the period of the contract and that no additional compensation per unit price or otherwise will be allowed for any increase or decrease in the quantities including, but not limited to, decreases due to the deletion of an entire location/section of the improvement. No increase in unit price will be allowed if method of construction changes due to decreased quantity.

PREQUALIFICATION

The Contractor shall have sufficient experience, as determined by the Owner and his representatives, in the field of municipal parking lot construction/reconstruction and underground work to warrant release of the bid documents. The contractor shall provide such documentation as is deemed necessary upon request. If this information is not satisfactorily completed, the bid documents shall be withheld.

BASIS OF AWARD

The Village will award either Option 1 or Option 2 at their sole discretion. All contractors are required to submit costs for both options with their bid. If a bid contains pricing for only one Option it will be considered non-compliant and may be grounds for bid rejection.

FUNDING LIMITS

The Owner has allotted a limited amount of funding for the project. However, the Owner reserves the right to reduce and/or eliminate individual pay items after the award is made based on the allowable funding.

PREFERENCE TO VETERANS

Attention is called to assure compliance with Illinois Compiled Statutes Veteran's Preference Act 330 ILCS 55/. "In the employment and appointment to fill positions in the construction, addition to, or alteration of all public works undertaken or contracted for by the state, or by any political subdivision thereof, preference shall be given to persons who have been members of the armed forces or allies of armed forces of allies of the United States in time of hostilities with a foreign country..."

WAGE RATES

This contract calls for the construction of a "public work," within the meaning of the Illinois Prevailing Wage Act, 820 ILCS 130/.01 *et seq.* ("the Act"). The Act requires contractors and subcontractors to pay laborers, workers and mechanics performing services on public works projects no less than the "prevailing rate of wages" (hourly cash wages plus fringe benefits) in the county where the work is performed. For information regarding current prevailing wage rates, please refer to the Illinois Department of Labor's website at: <http://www.state.il.us/agency/idol/rates/rates.HTM>. All contractors and subcontractors rendering services under this contract must comply with all requirements of the Act, including but not limited to, all wage, notice and record keeping duties.

INSURANCE COVERAGE

The Insurance Requirements can be found in Section 7 of the General Requirements "Legal Relations and Responsibility to the Public". The Contractor and any Subcontractors shall obtain and thereafter keep in force for the term of the contract the insurance coverage specified in this section. The Contractor shall not commence work under the Contract until all the insurance required by this section or any Special Provision has been obtained.

Section 7-2.02E Pollution Liability WILL be required as part of this project.

Section 7-2.02F Professional Liability WILL NOT be required as part of this project.

PUBLIC CONSTRUCTION ACT, 30 ILCS 557/1

Pursuant to the home rule powers of the Village, Public Construction Act 30 ILCS 557/1 shall not be applicable to this contract.

WORK HOURS

The following work hours shall be kept unless written permission is received from the Village of Tinley Park. The Contractor may prosecute work between the hours of 7:00 a.m. and dusk each workday. No work, including the startup of machinery can occur outside these hours. However, no work will be permitted between dusk and 7:00 a.m., on Sundays, or on holidays, without prior written permission of the Village.

COORDINATION/SCHEDULING OF WORK

The Contractor shall be advised that the work of all subcontractors will be coordinated by the General Contractor and not by the Village or their authorized representative.

Because of limited parking, the work in the lots must be phased. The main lot must be completed in two phases as only one half of the lot will be allowed to be closed down at any one time. Work will be split in the south half and north half for the main lot. Once one phase is 100% complete including striping, work can begin on the second phase. The southeast lot can be shut down all at once but not at the same time as the main lot phases.

All equipment parking and work in general must be coordinated with the Convention Center event schedule. There will be days when the parking lot is completely unavailable for construction. All work must be 100% completed before these dates for each Phase (Main parking lot North, Main parking lot South and Southeast parking lot).

✘ Represents dates that at the time of the letting are known that the parking lot is unavailable for construction due to business reasons. These dates are subject to change and additional dates can be added.

June 2018						
Sun	Mon	Tue	Wed	Thu	Fri	Sat
					1	2
3	4	5	6	7	8	9
10	11	12	13	14	✘	16
17	18	19	20	21	22	23
24	25	26	27	28	29	30

July 2018						
Sun	Mon	Tue	Wed	Thu	Fri	Sat
1	2	3	4	5	6	7
8	9	10	11	12	13	✘
15	16	17	18	19	20	21
22	23	24	25	26	27	28
29	30	31				

August 2018						
Sun	Mon	Tue	Wed	Thu	Fri	Sat
			1	2	3	4
5	6	7	8	9	10	11
12	✘	✘	✘	16	17	18
19	20	21	22	23	24	✘
26	27	✘	✘	30	31	

September 2018						
Sun	Mon	Tue	Wed	Thu	Fri	Sat
						1
2	3	4	5	6	7	8
9	10	11	12	13	14	15
16	17	18	19	20	✘	✘
23	24	25	26	✘	✘	29
30						

October 2018						
Sun	Mon	Tue	Wed	Thu	Fri	Sat
	1	2	✘	✘	✘	6
7	8	9	10	11	✘	✘
✘	15	16	17	18	✘	✘
21	22	23	24	25	26	27
28	29	30	31			

November 2018						
Sun	Mon	Tue	Wed	Thu	Fri	Sat
				1	2	3
4	5	6	7	8	9	10
11	12	13	14	15	16	17
18	19	20	21	22	23	24
25	26	27	28	29	30	

All equipment must be removed from the parking lot during all holiday weekends at the request of the Village.

Priming/tacking of the parking lot must be done on the day of paving.

Prior to HMA surface removal, all curb removal and replacement and curb slot restoration must be completed.

Sweeping will be required after grinding operations and within 24 hours before paving.

Any irrigation systems, brick pavers, decorative rock, special corner landscaping, mailboxes, etc., within the ROW disturbed during construction will be the Contractors responsibility to repair and shall be included in the unit price for the various removal items.

Contractor is expected to inspect all locations before beginning work and have all material on hand to complete the project. No compensation will be had for inadequate inventory, shipping, trucking or re-stocking of materials.

Stockpiling of material and end of day clean up- **Stockpiles shall not impede traffic, parking or access at any time. Any areas disturbed by stockpiles shall be restored to existing conditions and shall be considered incidental to the contract.**

At the end of each working day, the contractor shall provide a steel plate, barricades, warning tape and any other safety measures deemed necessary by the Village/Engineer over the excavated area so that traffic, parking or access is not impeded during non-working hours. Access to the property shall be maintained at all times. Placement of temporary aggregate in the roadway and in driveway areas disturbed by the construction shall be used until final

conditions are met. Street clean up and sweeping is also required at the end of each working day. The cost for materials and traffic control items necessary to meet these requirements shall be considered incidental to the contract.

All water use shall be coordinated with the Village and be in compliance with their rules and regulations.

PUBLIC UTILITIES

There are existing underground and above ground public and private, municipal and non-municipal utilities at the site, such as, but not necessarily limited to electrical and telephone cables including fiber-optic facilities, natural gas pipes, sewers, and water main, etc. All due notifications, vertical/horizontal separations, and other safety precautions required by the owners/operators of the facilities being crossed shall be observed by the contractor and/or all sub-contractors at all times. Any damage caused by the construction to any of the existing facilities on-site shall be promptly repaired to the satisfaction of the owners/operators of the facility involved, at no additional compensation.

It shall be the contractor's responsibility to very carefully inspect the site, identify and locate both horizontally and vertically all existing facilities, contact their owner/operators for their notification, separation, and safety requirements, and follow such requirements very carefully. It shall be the Contractor's responsibility to notify J.U.L.I.E. at least 48 hours prior to excavation to verify locations of all utilities.

The contractor shall protect and save harmless the Village of Tinley Park and Robinson Engineering, Ltd from any claim(s) of damage resulting from his/her activities at the site or from failing to undertake due and proper safety measures to avoid such damage to any utilities during the construction.

The contractor shall repair any damage to any of the utilities, caused by his/her work, to the satisfaction of the involved utility and the Village of Tinley Park at no additional compensation. The cost of compliance with this provision shall be considered incidental to the contract and will not be compensated for separately.

GEOTECHNICAL INFORMATION

Pavement cores were taken for a portion of the project and are provided for the Contractor's reference. The Contractor shall conduct any additional subsurface exploration deemed necessary in order to perform the work as required.

The Village and Authorized Representative assumes no responsibility in regard to the nature of the information or the conditions which may be encountered during construction. The Bidder may satisfy themselves prior to bidding, by such methods as they may prefer, including their own borings/cores with the Village's consent, as to the nature of the pavement cross section and/or subsurface conditions, including any obstructions, which may be encountered during construction. Failure to make such borings shall not relieve him of the responsibility for carrying out to successful completion the work contemplated by the Project Documents for the price specified in the Bid.

TRAFFIC CONTROL PLAN

Effective: September 30, 1985

Revised: January 1, 2007

Traffic Control shall be in accordance with the applicable sections of the Standard Specifications, the Supplemental Specifications, and the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the Resident Engineering Representative at least 72 hours in advance of beginning work.

STANDARDS: 701006-05, 701301-04, 701311-03, 701501-06, 701801-06, 701901-07

DISTRICT ONE DETAILS: TC-10, TC-13

SPECIAL PROVISIONS: Traffic Control Plan, Maintenance of Roadways

The Contractor shall not remove any traffic control or safety devices until the entire job is complete. The Contractor shall obtain, erect, maintain and remove all signs, barricades, flagmen and other traffic control devices as may be necessary for the purpose of regulating, warning or guiding traffic. Placement and maintenance of all traffic control devices shall be in accordance with the applicable parts of Article 107.14 of the Standard Specifications and the Illinois Manual on Uniform Traffic Control Devices for Streets and Highways and the attached special provisions. The Contractor is solely responsible for ensuring all traffic control devices are installed and maintained in accordance with applicable state standards.

Work Zone Traffic Control will not be paid for separately but will be considered incidental to the contract.
--

The Contractor is hereby advised that notification to all affected residents is his responsibility including the placement of No Parking signs at least 48 hours prior to paving operations. In addition, signage indicating road conditions such as "Bump", "Rough Surface", "Fresh Oil", "Dip", etc., as requested by the Village will also be required at no additional expense.

MAINTENANCE OF ROADWAYS

Effective: September 30, 1985

Revised: November 1, 1996

Beginning on the date that work begins on this project, the Contractor shall assume responsibility for normal maintenance of all existing roadways within the limits of the improvement. This normal maintenance shall include all repair work deemed necessary by the Engineer, but shall not include snow removal operations. Traffic control and protection for maintenance of roadways will be provided by the Contractor as required by the Engineer.

If items of work have not been provided in the contract, or otherwise specified for payment, such items, including the accompanying traffic control and protection required by the Engineer, will be paid for in accordance with Article 109.04 of the Standard Specifications.

MATERIAL INSPECTION REPORTS

The Contractor shall be responsible for material inspection required for various items incorporated in this project. Also, all documentation is to be submitted to the Village or Authorized Representative, immediately following completion of this project. Five percent (5%) of the final contract amount due the Contractor will be withheld pending receipt of said documentation.

GUARANTEE

All materials and equipment shall be guaranteed for a period of one (1) year from the date of written acceptance by the Owner. Upon receipt of notice from the Owner of failure of any part of the improvements during the guarantee period, replacement of the improvements shall be furnished and installed by the Contractor at no additional cost to the Village of Tinley Park.

COMPLETION SCHEDULE

The contractor is advised that all work shall be completed on or before **November 21, 2018**. Penalties for the completion date and any other restrictions outlined herein shall be assessed at the rate of \$1,000 per calendar day.

TRACKING OF QUANTITIES

During the course of the contract, the Contractor shall maintain a list of each location for which work was performed along with the individual quantities and cost breakdown. This tracking will help ensure that the funding allotment is not exceeded during the work. It is the responsibility of the Contractor to ensure his work does not exceed the funding limits established by the Village.

VIDEO OF CONSTRUCTION AREA

Prior to the start of any construction or excavation, the contractor shall video record the existing conditions in the area of the construction area. The video shall be done on standard color DVD. The contractor shall supply the Village or Authorized Representative with two copies of the video prior to starting construction. The video shall include the following:

- | | | |
|----------------------|-----------------------|-------------------------------|
| 1. Full right-of-way | 2. Parkway condition | 3. Pavement condition |
| 4. Curb condition | 5. Driveway condition | 6. Existing manholes |
| 7. Fire hydrants | 8. Fences | 9. Trees and landscaped areas |

The video recordings shall also supply a continuous audio record of the location (preferably with address), all anticipated problem areas, items, and features for the complete area to be affected by the construction.

The video recording shall be made on a DVD or other approved equal and shall conform to Japan Electronics and Information Technology Industries Association (JEITA) standards. The format of recording and type of media used shall remain the same throughout the project. When the recorded video information is replayed and reviewed, it shall be free of electrical interference.

The audio portion of the composite signal shall be sufficiently free of electrical interference, background noise, and heavy foreign or regional accents to provide an oral report that is clear and complete and easily discernible. The audio portion of the video report shall be recorded by the operating technician on the video as they are being produced and shall include references to the street address and type of construction to be performed at the site as specified in the plans. Audio comments pertaining to special circumstances, which may arise during the excavation, shall also be included. Dubbing the audio information onto the video tract after the video is completed will not be permitted.

Video recordings shall be enclosed in vinyl plastic containers, which shall clearly indicate the date the video was taken, the designated section(s) of construction contained on the tape, and the label "Village of Tinley Park Convention Center Parking Lot Improvements (Project #18-R0455)." One (1) copy of the finished video shall be delivered to the Village or Authorized Representative prior to commencing excavation.

The surface condition of excavated areas after final restoration shall be the same or better than the pre-construction site conditions as shown in the video. The cost of video and log preparation shall not be compensated for separately but shall be considered incidental to the contract.

The surface condition of excavated areas after final restoration shall be the same or better than the pre-construction site conditions as shown in the videotape. The cost of videotaping and log preparation shall not be compensated for separately but shall be considered incidental to the contract.

CLEAN CONSTRUCTION OR DEMOLITION DEBRIS (CCDD) REQUIREMENTS PER 35 IAC 1100

If the Contractor is planning on disposing of uncontaminated soils at an Illinois Environmental Protection Agency (IEPA) permitted CCDD facility, the work shall be conducted in accordance with the criteria set forth in 35 Illinois Administrative Code (IAC) 1100 as amended on August 27, 2012. The following protocol must be followed:

1. The Contractor must identify in writing the name / location of the Contractor's intended CCDD facility to the Owner (or Engineer) prior to the commencement of any construction activities.
2. The Owner (or Engineer) will contact the Contractor's CCDD facility to identify the laboratory testing or certifications required for disposal acceptance.
3. The Contractor will assist the Owner (or Engineer) in obtaining the sample(s) through the use of the Contractor's equipment at locations determined by the Owner (or Engineer). The Contractor shall expose soils at one or more distinct locations as directed by the Owner (or Engineer). The Contractor may need to remove pavement, sidewalk or other surface improvements to expose the soil. The Owner (or Engineer) will determine the number, location and depth of the samples that will need to be collected for characterization of the excess soil that will be generated during the construction project.
4. The Owner (or Engineer) will be responsible for the sampling / testing of the soil and preparation of the required certification form.
5. The samples will be run with standard 5 to 7 working day turnaround time unless a rush is required by the Contractor. If so, the Contractor will be responsible for additional fees associated with fast-tracking the samples.
6. Once the appropriate certifications have been prepared, the Contractor will be responsible for all hauling/disposal of material at the CCDD facility.

The work contained within this special provision shall be considered incidental to the contract.

The owner will test for the following: VOC's, SVOC's, Pesticides, RCRA 8 total metals and pH. If the Contractor elects to utilize a CCDD facility that requires the full MAC list, the Contractor will be responsible for paying all sampling costs above \$1,000.

If any contaminated soil is encountered that requires landfill disposal as a non-special waste, special waste or hazardous waste, it will be paid for per Article 109.04 of the Standard Specifications.

SAW CUT JOINTS

The removal and/or replacement of any driveways, pavement, curb, sidewalk, etc. shall be accomplished by means of a straight saw cut joint, at the direction of the Village or Authorized Representative. This work shall not be paid for separately but will be included in the unit price bid for the various removal items.

REMOVE EXISTING PARKING BLOCKS

This work shall consist of the removal and proper disposal of existing parking blocks at locations directed by the Village or Authorized Representative. The Contractor shall take special care to not damage the adjacent sidewalk during the removal and disposal of the parking blocks. Any damage to the adjacent sidewalk shall be repaired at the contractor's expense.

This work will be paid for at the contract unit price per EACH for REMOVE EXISTING PARKING BLOCKS, which price shall include all labor, equipment and materials required to complete the work as specified herein.

CONCRETE PARKING BLOCKS

Concrete parking blocks shall be installed at locations as directed by the Village or Authorized Representative. The parking blocks shall be Precast Reinforced Concrete measuring 7-feet long, 10-inches wide and 5-inches high. The parking blocks shall be anchored to the HMA pavement utilizing anchor pins.

This work shall be paid for at the contract unit price per EACH for CONCRETE PARKING BLOCKS.

HOT-MIX ASPHALT SURFACE REMOVAL, 4"

This work shall be in accordance with the applicable portions of Sections 406 and 440 of the Standard Specifications. All of the hot-mix asphalt shall be removed to the existing aggregate base, and the Contractor shall receive no additional compensation if the depth removed exceeds the approximate four-inch (4") depth. Any additional excavation or aggregate base removal necessary to provide the four-inch (4") hot-mix asphalt overlay shall be considered incidental to the PREPARATION OF BASE and HOT-MIX ASPHALT SURFACE REMOVAL, 4" pay items.

Once the asphalt surface is removed, the Contractor shall prepare the base and add aggregate in any void areas, which shall be paid for at the contract unit price bid per SQUARE YARD of PREPARATION OF BASE and per TON of AGGREGATE BASE REPAIR.

This work will be paid for at the contract unit price bid per SQUARE YARD of HOT-MIX ASPHALT SURFACE REMOVAL, 4" which shall include all labor, equipment, and any other appurtenances necessary to complete the work as specified above.

DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED OR RECONSTRUCTED

This work shall consist of the adjustment and/or reconstruction of drainage and utility structures at those locations as indicated in the plans or as directed by the engineer in the field.

The existing pavement around each structure to be adjusted or reconstructed shall be removed by a straight, saw-cut joint.

All structures requiring frame and lid adjustment, or reconstruction shall also be cleaned to the satisfaction of the Engineer in accordance with Article 602.15. This work shall not be paid for separately but shall be considered included in the cost of the adjustment or reconstruction.

Any trench backfill needed to fill in the area around the adjusted or reconstructed structure will not be paid for separately, but considered incidental to the structure being adjusted or reconstructed.

After adjustment or reconstruction is completed, the pavement around the structure shall be replaced with HMA binder (IL-19.00 mm), N50. The binder will be placed on a compacted, prepared subgrade, and the thickness shall match existing conditions. The pavement replacement will not be paid for separately but shall be considered incidental to the structure being adjusted or reconstructed.

The General Contractor shall be responsible for coordinating this work with the subcontractor, not the Village or their authorized representative. This work shall be completed in accordance with the applicable portions of Section 602 of the Standard Specifications. ***All adjustments shall be made with rubber adjustment rings unless otherwise directed by the Engineer. The cost for the rubber adjustment rings will be paid for separately and shall not be included in the cost of the structure adjustment.***

Concrete will not be allowed to fill the gap between the structure and the existing pavement. A full depth patch will be required for adjustments not within the curb and the cost of that work will be incidental to the adjustment. This work will be paid for at the contract unit price EACH for DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED and for DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED.

RUBBER ADJUSTING RINGS

This work shall consist of the adjustment and/or reconstruction of drainage and utility structures at those locations as directed by the Village or Authorized Representative in the field using rubber fibrepolyurethane prepolymer composite adjusting rings as approved by the Village or Authorized Representative. This pay item reflects the cost of the material only. Installation shall be included in the pay item for the drainage and utility structures to be adjusted. Tapered adjusting rings shall be used where necessary to match the profile of the pavement. In order to minimize the number of rings used, thicker rings shall be used where practical (i.e one 3-inch ring rather than 3-one-inch rings) as determined by the Engineer in the field. The Contractor shall examine all adjustments in the field prior to ordering materials.

This work will be paid for at the contract unit price EACH for RUBBER ADJUSTING RINGS.

STEEL ADJUSTING RINGS

This work shall consist of the adjustment and/or reconstruction of drainage and utility structures at those locations as directed by the Village or Authorized Representative in the field using steel adjusting rings. This pay item reflects the cost of the material only which shall be in accordance with Article 1006.04 of the Standard Specifications. Installation shall be included in the pay item for the drainage and utility structures to be adjusted.

This work will be paid for at the contract unit price EACH for STEEL ADJUSTING RINGS.

PROJECT HOT-MIX ASPHALT MIXTURE REQUIREMENT CHART

OPTION 1

HOT-MIX ASPHALT MIXTURE REQUIREMENT CHART	
ITEM	AIR VOIDS @ Ndes
RESURFACING	
HMA Surface Course, Mix "D", N50 (IL 9.5 mm); 2"	4% @ 50 Gyr.
PATCHING	
Class D Patches (HMA Binder IL-19mm); 4"	4% @ 70 Gyr.

OPTION 2

HOT-MIX ASPHALT MIXTURE REQUIREMENT CHART	
ITEM	AIR VOIDS @ Ndes
RESURFACING-MAIN LOT	
HMA Surface Course, Mix "D", N50 (IL 9.5 mm); 2"	4% @ 50 Gyr.
RESURFACING-SOUTHEAST LOT	
HMA Surface Course, Mix "D", N50 (IL 9.5 mm); 1.75"	4% @ 50 Gyr.
HMA Binder, IL-19.0, N50; 2.25"	4% @ 50 Gyr.

The "AC Type" for Non-Polymerized HMA the "AC Type" shall be "PG 64-22" unless modified by District One Special Provisions. For Use of Recycled Materials, see Special Provisions.

The unit weight used to calculate all Hot-Mix Asphalt Surface Mixtures is 112 lbs/sq yd/in.

TOPSOIL FURNISH AND PLACE, 4" (SPECIAL)

This work shall consist of the furnishing and placing of four inches (4") of pulverized topsoil at all areas disturbed by the construction. All work shall be done in accordance with Sections 211 of the Standard Specifications with the exception the timeframe. All topsoil must be placed within 14 days of the curb replacement regardless of the schedule

for the sod replacement. If this topsoil is not placed the Contractor will be charged \$500 per day after day 14 in liquidated damages. In addition, if the Village has to undertake this work, the Contractor will be responsible for the cost to the Village to procure the work and this amount will be withheld from any amount due the Contractor by the Village.

If, in the opinion of the Engineer, more surface area than necessary has been damaged, it shall be replaced by the Contractor as specified herein without additional compensation. The maximum width for restoration will be three feet (3').

This work, including the topsoil, pulverizing, etc. shall be paid for at the contract unit price per SQUARE YARD for TOPSOIL FURNISH AND PLACE, 4" (SPECIAL).

SODDING, SPECIAL

This work shall consist of preparing the ground surface, fertilizing the areas to be sodded and furnishing and placing the sod. All work shall be in accordance with the applicable portions of Section 252 of the Standard Specifications. **The maximum pay width shall be three (3') feet unless specifically directed otherwise by the engineer.**

180 pounds of fertilizer nutrients per acre shall be applied at a 1:1:1 ratio as follows:

- | | |
|-----------------------------------|------------|
| 1. Nitrogen Fertilizer Nutrient | 60 lb/acre |
| 2. Phosphorus Fertilizer Nutrient | 60 lb/acre |
| 3. Potassium Fertilizer Nutrient | 60 lb/acre |

Watering shall be done as directed by the Engineer, in accordance with Article 252.08 of the Standard Specifications.

This work shall be measured in place and the area calculated in square yards and shall be paid for at the contract unit price per SQUARE YARD for SODDING, SPECIAL, which price shall be full compensation for all labor, equipment, and material needed to complete the work as specified in these Special Provisions.

VILLAGE OF TINLEY PARK LOCAL VENDOR PURCHASING POLICY

The Village of Tinley Park believes it is important to provide local vendors with opportunities to provide goods and services to the Village of Tinley Park. This belief is based upon the fact that the active uses of commercial properties in Tinley Park benefits the community through stabilization of property tax, the creation of local sales tax and the provision of employment opportunities for citizens of the community and surrounding region. In an effort to promote the aforementioned benefits, the Village of Tinley Park wishes to provide local vendors with preferential treatment when competing for contracts with the Village. A local vendor is defined as a business that has an actual business location within the Village of Tinley Park and is licensed by the Village. The Village will not award a contract to a local vendor when the difference between the local vendors bid and the otherwise lowest responsive and responsible bid exceeds the applicable percentage indicated as follows. As such, when considering contracts, the Village of Tinley Park reserves the right to forego the lowest responsive and responsible bid exceeds the applicable percentage indicated as follows. As such, when considering contracts, the Village of Tinley Park reserves the right to forego the lowest responsive and responsible bid in favor of a local vendor under the following circumstances:

<u>Contract Value</u>	<u>Range (up to a maximum of)</u>
\$0 to \$250,000	5%
\$250,000 to \$500,000	4%
\$500,000 to \$750,000	3%
\$750,000 to \$1,000,000	2%
\$1,000,000 to \$2,000,000	1%

Under no circumstances will any contract be awarded to a local vendor when the local vendor's bid exceeds the lowest responsive and responsible bid by \$25,000 or more.

This policy shall ONLY apply if formal notice of the aforementioned criteria is provided as part of the bid specifications. In addition, it should be noted that the Village of Tinley Park shall not be obligated to forego the low bidder in favor of the local vendor under any circumstances. However, this policy simply provides the Village with the option of doing so when applicable. Furthermore, this policy shall not apply in any situation where any portion of the contract amount is being paid with funds other than Village monies. Specifically, this policy shall not apply in any situation where the Village has received a grant or otherwise received a source of funds other than its own funds.

RESPONSIBLE BIDDER

For any construction project undertaken by the Village to which the Illinois Prevailing Wage Act, 820 ILCS 130/0.01 et seq. is applicable, in order to be considered a "responsible bidder" on Village Public Works Projects, a bidder must comply with the following criteria, and submit acceptable evidence of such compliance, in addition to any other requirements as determined from time to time by the Village for the specific type of work to be performed:

- (a) Compliance with all applicable laws and Village Codes and Ordinances prerequisite to doing business in Illinois and in the Village;
- (b) Compliance with:
 - a. Submittal of Federal Employer Tax Identification Number or Social Security Number (for individual), and
 - b. Provisions of Section 2000e of Chapter 21, Title 42 of the United States Code and Federal Executive Order No. 11246 as amended by Federal Executive Order No. 11375 (known as the Equal Employment Opportunity Provisions);
- (c) Furnishing certificates of insurance indicating at least the following coverages at minimum limits established by the Village: general liability, workers' compensation, completed operations, automobile, hazardous occupation, product liability, and professional liability;
- (d) Compliance with all provisions of the Illinois Prevailing Wage Act, including wages, medical and hospitalization insurance and retirement for those trades covered by the Act;
- (e) Participation in apprenticeship and training programs approved by and registered with the United States Department of Labor's Bureau of Apprenticeship and Training;
- (f) Compliance with the applicable provisions of the Illinois Human Rights Act and the rules of the Illinois Human Rights Commission, including the adoption of a written sexual harassment policy;
- (g) Furnishing of required performance and payment bonds;
- (h) Furnishing certification of no delinquency in the payment of any tax administered by the Illinois Department of Revenue;

- (i) Furnishing certification that the bidder is not barred from bidding or contracting as a result of a violation of either Section 33E or 33E-4 of Chapter 720, Article 5 of the Illinois Compiled Statutes; and
- (j) Furnishing evidence that the bidder has not only the financial responsibility but also the ability to respond to the needs of the Village by the discharge of the contractor's obligations in accordance with what is expected or demanded under the terms of the contract.

FRICITION AGGREGATE (DISTRICT 1)

Effective: January 1, 2011

Revised: April 29, 2016

Revise Article 1004.03(a) of the Standard Specifications to read:

"1004.03 Coarse Aggregate for Hot-Mix Asphalt (HMA). The aggregate shall be according to Article 1004.01 and the following.

- (a) Description. The coarse aggregate for HMA shall be according to the following table.

Use	Mixture	Aggregates Allowed
Class A	Seal or Cover	<u>Allowed Alone or in Combination</u> ^{5/} : Gravel Crushed Gravel Carbonate Crushed Stone Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Steel Slag Crushed Concrete
HMA Low ESAL	Stabilized Subbase or Shoulders	<u>Allowed Alone or in Combination</u> ^{5/} : Gravel Crushed Gravel Carbonate Crushed Stone Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Steel Slag ^{1/} Crushed Concrete
HMA High ESAL Low ESAL	Binder IL-19.0 or IL-19.0L SMA Binder	<u>Allowed Alone or in Combination</u> ^{5/6/} : Crushed Gravel Carbonate Crushed Stone ^{2/} Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Concrete ^{3/}

Use	Mixture	Aggregates Allowed	
HMA High ESAL Low ESAL	C Surface and Leveling Binder IL-9.5 or IL-9.5L SMA Ndesign 50 Surface	<u>Allowed Alone or in Combination</u> ^{5/} : Crushed Gravel Carbonate Crushed Stone ^{2/} Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Steel Slag ^{4/} Crushed Concrete ^{3/}	
HMA High ESAL	D Surface and Leveling Binder IL-9.5 SMA Ndesign 50 Surface	<u>Allowed Alone or in Combination</u> ^{5/} : Crushed Gravel Carbonate Crushed Stone (other than Limestone) ^{2/} Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Steel Slag ^{4/} Crushed Concrete ^{3/}	
		<u>Other Combinations Allowed:</u>	
		<i>Up to...</i>	<i>With...</i>
		25% Limestone	Dolomite
		50% Limestone	Any Mixture D aggregate other than Dolomite
75% Limestone	Crushed Slag (ACBF) or Crushed Sandstone		
HMA High ESAL	E Surface IL-9.5 SMA Ndesign 80 Surface	<u>Allowed Alone or in Combination</u> ^{5/ 6/} : Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Steel Slag No Limestone.	
		<u>Other Combinations Allowed:</u>	
		<i>Up to...</i>	<i>With...</i>
		50% Dolomite ^{2/}	Any Mixture E aggregate

Use	Mixture	Aggregates Allowed	
		75% Dolomite ^{2/}	Crushed Sandstone, Crushed Slag (ACBF), Crushed Steel Slag, or Crystalline Crushed Stone
		75% Crushed Gravel ^{2/} or Crushed Concrete ^{3/}	Crushed Sandstone, Crystalline Crushed Stone, Crushed Slag (ACBF), or Crushed Steel Slag
HMA High ESAL	F Surface IL-9.5 SMA Ndesign 80 Surface	<u>Allowed Alone or in Combination</u> ^{5/ 6/} :	
		Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Steel Slag No Limestone.	
		<u>Other Combinations Allowed:</u>	
		<i>Up to...</i>	<i>With...</i>
		50% Crushed Gravel ^{2/} , Crushed Concrete ^{3/} , or Dolomite ^{2/}	Crushed Sandstone, Crushed Slag (ACBF), Crushed Steel Slag, or Crystalline Crushed Stone

- 1/ Crushed steel slag allowed in shoulder surface only.
- 2/ Carbonate crushed stone (limestone) and/or crushed gravel shall not be used in SMA Ndesign 80. In SMA Ndesign 50, carbonate crushed stone shall not be blended with any of the other aggregates allowed alone in Ndesign 50 SMA binder or Ndesign 50 SMA surface.
- 3/ Crushed concrete will not be permitted in SMA mixes.
- 4/ Crushed steel slag shall not be used as leveling binder.
- 5/ When combinations of aggregates are used, the blend percent measurements shall be by volume."
- 6/ Combining different types of aggregate will not be permitted in SMA Ndesign 80."

GROUND TIRE RUBBER (GTR) MODIFIED ASPHALT BINDER (DISTRICT 1)

Effective: June 26, 2006

Revised: April 1, 2016

Add the following to the end of article 1032.05 of the Standard Specifications:

"(c) Ground Tire Rubber (GTR) Modified Asphalt Binder. A quantity of 10.0 to 14.0 percent GTR (Note 1) shall be blended by dry unit weight with a PG 64-28 to make a GTR 70-28 or a PG 58-28 to make a GTR 64-28. The base PG 64-28 and PG 58-28 asphalt binders shall meet the requirements of Article 1032.05(a). Compatible

polymers may be added during production. The GTR modified asphalt binder shall meet the requirements of the following table.

Test	Asphalt GTR 70-28	Grade	Asphalt Grade GTR 64-28
Flash Point (C.O.C.), AASHTO T 48, °F (°C), min.	450 (232)		450 (232)
Rotational Viscosity, AASHTO T 316 @ 275 °F (135 °C), Poises, Pa·s, max.	30 (3)		30 (3)
Softening Point, AASHTO T 53, °F (°C), min.	135 (57)		130 (54)
Elastic Recovery, ASTM D 6084, Procedure A (sieve waived) @ 77 °F, (25 °C), aged, ss, 100 mm elongation, 5 cm/min., cut immediately, %, min.	65		65

Note 1. GTR shall be produced from processing automobile and/or light truck tires by the ambient grinding method. GTR shall not exceed 1/16 in. (2 mm) in any dimension and shall contain no free metal particles or other materials. A mineral powder (such as talc) meeting the requirements of AASHTO M 17 may be added, up to a maximum of four percent by weight of GTR to reduce sticking and caking of the GTR particles. When tested in accordance with Illinois modified AASHTO T 27, a 50 g sample of the GTR shall conform to the following gradation requirements:

Sieve Size	Percent Passing
No. 16 (1.18 mm)	100
No. 30 (600 μm)	95 ± 5
No. 50 (300 μm)	> 20

Add the following to the end of Note 1. of article 1030.03 of the Standard Specifications:

"A dedicated storage tank for the Ground Tire Rubber (GTR) modified asphalt binder shall be provided. This tank must be capable of providing continuous mechanical mixing throughout by continuous agitation and recirculation of the asphalt binder to provide a uniform mixture. The tank shall be heated and capable of maintaining the temperature of the asphalt binder at 300 °F to 350 °F (149 °C to 177 °C). The asphalt binder metering systems of dryer drum plants shall be calibrated with the actual GTR modified asphalt binder material with an accuracy of ± 0.40 percent."

Revise 1030.02(c) of the Standard Specifications to read:

"(c) RAP Materials (Note 5)1031"

Add the following note to 1030.02 of the Standard Specifications:

Note 5. When using reclaimed asphalt pavement and/or reclaimed asphalt shingles, the maximum asphalt binder replacement percentage shall be according to the most recent special provision for recycled materials.

HMA MIXTURE DESIGN REQUIREMENTS (D-1)

Effective: January 1, 2013

Revised: January 1, 2018

1) Design Composition and Volumetric Requirements

Revise the table in Article 406.06(d) of the Standard Specifications to read:

"MINIMUM COMPACTED LIFT THICKNESS	
Mixture Composition	Thickness, in. (mm)
IL-4.75	3/4 (19)
SMA-9.5, IL-9.5, IL-9.5L	1 1/2 (38)
SMA-12.5	2 (50)
IL-19.0, IL-19.0L	2 1/4 (57)"

Revise the table in Article 1004.03(c) of the Standard Specifications to read:

"Use	Size/Application	Gradation No.
Class A-1, 2, & 3	3/8 in. (10 mm) Seal	CA 16
Class A-1	1/2 in. (13 mm) Seal	CA 15
Class A-2 & 3	Cover	CA 14
HMA High ESAL	IL-19.0 IL-9.5	CA 11 ^{1/} CA 16, CA 13 ^{3/}
HMA Low ESAL	IL-19.0L IL-9.5L Stabilized Subbase or Shoulders	CA 11 ^{1/} CA 16
SMA ^{2/}	1/2 in. (12.5mm) Binder & Surface IL 9.5 Surface	CA13 ^{3/} , CA14 or CA16 CA16, CA 13 ^{3/}

1/ CA 16 or CA 13 may be blended with the gradations listed.

2/ The coarse aggregates used shall be capable of being combined with stone sand, slag sand, or steel slag sand meeting the FA/FM 20 gradation and mineral filler to meet the approved mix design and the mix requirements noted herein.

3/ CA 13 shall be 100 percent passing the 1/2 in. (12.5mm) sieve.

Revise Article 1004.03(e) of the Supplemental Specifications to read:

“(e) Absorption. For SMA the coarse aggregate shall also have water absorption \leq 2.0 percent.”

Revise the last paragraph of Article 1102.01 (a) (5) of the Standard Specifications to read:

“IL-4.75 and Stone Matrix Asphalt (SMA) mixtures which contain aggregate having absorptions greater than or equal to 2.0 percent, or which contain steel slag sand, shall have minimum surge bin storage plus haul time of 1.5 hours.”

Revise the nomenclature table in Article 1030.01 of the Standard Specifications to read:

“High ESAL	IL-19.0 binder; IL-9.5 surface; IL-4.75; SMA-12.5, SMA-9.5
Low ESAL	IL-19.0L binder; IL-9.5L surface; Stabilized Subbase (HMA) ^{1/} ; HMA Shoulders ^{2/}

1/ Uses 19.0L binder mix.

2/ Uses 19.0L for lower lifts and 9.5L for surface lift.”

Revise Article 1030.02 of the Standard Specifications and Supplemental Specifications to read:

“**1030.02 Materials.** Materials shall be according to the following.

Item	Article/Section
(a) Coarse Aggregate	1004.03
(b) Fine Aggregate	1003.03
(c) RAP Material	1031
(d) Mineral Filler	1011
(e) Hydrated Lime	1012.01
(f) Slaked Quicklime (Note 1)	
(g) Performance Graded Asphalt Binder (Note 2)	1032
(h) Fibers (Note 3)	
(i) Warm Mix Asphalt (WMA) Technologies (Note 4)	

Note 1. Slaked quicklime shall be according to ASTM C 5.

Note 2. The asphalt binder shall be an SBS PG 76-28 when the SMA is used on a full-depth asphalt pavement and SBS PG 76-22 when used as an overlay, except where modified herein. The asphalt binder shall be an Elvaloy or SBS PG 76-22 for IL-4.75, except where modified herein. The elastic recovery shall be a minimum of 80.

Note 3. A stabilizing additive such as cellulose or mineral fiber shall be added to the SMA mixture according to Illinois Modified AASHTO M 325. The stabilizing additive shall meet the Fiber Quality Requirements listed in Illinois Modified AASHTO M 325. Prior to approval and use of fibers, the Contractor shall submit a notarized certification by the producer of these materials stating they meet these requirements. Reclaimed Asphalt Shingles (RAS) may be used in Stone Matrix Asphalt (SMA) mixtures designed with an SBA polymer modifier as a fiber additive if the mix design with RAS included meets AASHTO T305 requirements. The RAS shall be from a certified source that produces either Type I or Type 2. Material shall meet requirements noted herein and the actual dosage rate will be determined by the Engineer.

Note 4. Warm mix additives or foaming processes shall be selected from the current Bureau of Materials and Physical Research Approved List, "Warm Mix Asphalt Technologies".

Revise Article 1030.04(a)(1) of the Standard Specifications and the Supplemental Specifications to read

" (1) High ESAL Mixtures. The Job Mix Formula (JMF) shall fall within the following limits.

High ESAL, MIXTURE COMPOSITION (% PASSING) ^{1/}										
Sieve Size	IL-19.0 mm		SMA ^{4/} IL-12.5 mm		SMA ^{4/} IL-9.5 mm		IL-9.5 mm		IL-4.75 mm	
	min	max	min	max	min	max	min	max	min	max
1 1/2 in (37.5 mm)										
1 in. (25 mm)		100								
3/4 in. (19 mm)	90	100		100						
1/2 in. (12.5 mm)	75	89	80	100		100		100		100
3/8 in. (9.5 mm)				65	90	100	90	100		100
#4 (4.75 mm)	40	60	20	30	36	50	34	69	90	100
#8 (2.36 mm)	20	42	16	24 ^{5/}	16	32 ^{5/}	34 ^{6/}	52 ^{2/}	70	90
#16 (1.18 mm)	15	30					10	32	50	65
#30 (600 μm)			12	16	12	18				
#50 (300 μm)	6	15					4	15	15	30
#100 (150 μm)	4	9					3	10	10	18
#200 (75 μm)	3	6	7.0	9.0 ^{3/}	7.5	9.5 ^{3/}	4	6	7	9 ^{3/}
Ratio Dust/Asphalt Binder		1.0		1.5		1.5		1.0		1.0

- 1/ Based on percent of total aggregate weight.
- 2/ The mixture composition shall not exceed 44 percent passing the #8 (2.36 mm) sieve for surface courses with N_{design} = 90.
- 3/ Additional minus No. 200 (0.075 mm) material required by the mix design shall be mineral filler, unless otherwise approved by the Engineer.

- 4/ The maximum percent passing the #635 (20 μm) sieve shall be ≤ 3 percent.
- 5/ When establishing the Adjusted Job Mix Formula (AJMF) the percent passing the #8 (2.36 mm) sieve shall not be adjusted above the percentage stated on the table.
- 6/ When establishing the Adjusted Job Mix Formula (AJMF) the percent passing the #8 (2.36 mm) sieve shall not be adjusted below 34 percent.

Revise Article 1030.04(b)(1) of the Standard Specifications to read:

- “(1) High ESAL Mixtures. The target value for the air voids of the HMA shall be 4.0 percent and for IL-4.75 it shall be 3.5 percent at the design number of gyrations. The VMA and VFA of the HMA design shall be based on the nominal maximum size of the aggregate in the mix, and shall conform to the following requirements.

VOLUMETRIC REQUIREMENTS High ESAL				
Ndesign	Voids in the Mineral Aggregate (VMA), % minimum			Voids Filled with Asphalt Binder (VFA), %
	IL-19.0	IL-9.5	IL-4.75 ^{1/}	
50	13.5	15.0	18.5	65 – 78 ^{2/}
70				65 - 75
90				

1/ Maximum Draindown for IL-4.75 shall be 0.3 percent

2/ VFA for IL-4.75 shall be 72-85 percent”

Replace Article 1030.04(b)(3) of the Standard Specifications with the following:

- “(3) SMA Mixtures.

Volumetric Requirements SMA ^{1/}			
Ndesign	Design Air Voids Target %	Voids in the Mineral Aggregate (VMA), % min.	Voids Filled with Asphalt (VFA), %
80 ^{4/}	3.5	17.0 ^{2/}	75 - 83
		16.0 ^{3/}	

1/ Maximum draindown shall be 0.3 percent. The draindown shall be determined at the JMF asphalt binder content at the mixing temperature plus 30 °F.

- 2/ Applies when specific gravity of coarse aggregate is ≥ 2.760 .
- 3/ Applies when specific gravity of coarse aggregate is < 2.760 .
- 4/ Blending of different types of aggregate will not be permitted.
For surface course, the coarse aggregate can be crushed steel slag, crystalline crushed stone or crushed sandstone. For binder course, coarse aggregate shall be crushed stone (dolomite), crushed gravel, crystalline crushed stone, or crushed sandstone.

Add to the end of Article 1030.05 (d) (2) a. of the Standard Specifications:

“During production, the Contractor shall test SMA mixtures for draindown according to AASHTO T305 at a frequency of 1 per day of production.”

Delete last sentence of the second paragraph of Article 1102.01(a) (4) b. 2.

Add to the end of Article 1102.01 (a) (4) b. 2.:

“As an option, collected dust (baghouse) may be used in lieu of manufactured mineral filler according to the following:

- (a.) Sufficient collected dust (baghouse) is available for production of the SMA mix for the entire project.
- (b.) A mix design was prepared based on collected dust (baghouse).

2) Design Verification and Production

Revise Article 1030.04 (d) of the Standard Specifications to read:

“(d) Verification Testing. High ESAL, IL-4.75, and SMA mix designs submitted for verification will be tested to ensure that the resulting mix designs will pass the required criteria for the Hamburg Wheel Test (IL mod AASHTO T-324) and the Tensile Strength Test (IL mod AASHTO T-283). The Department will perform a verification test on gyratory specimens compacted by the Contractor. If the mix fails the Department’s verification test, the Contractor shall make the necessary changes to the mix and resubmit compacted specimens to the Department for verification. If the mix fails again, the mix design will be rejected.

All new and renewal mix designs will be required to be tested, prior to submittal for Department verification and shall meet the following requirements:

- (1)Hamburg Wheel Test criteria. The maximum allowable rut depth shall be 0.5 in. (12.5 mm). The minimum number of wheel passes at the 0.5 in. (12.5 mm) rut depth criteria shall be

based on the high temperature binder grade of the mix as specified in the mix requirements table of the plans.

Illinois Modified AASHTO T 324 Requirements ^{1/}

Asphalt Binder Grade	# Repetitions	Max Rut Depth (mm)
PG 70 -XX (or higher)	20,000	12.5
PG 64 -XX (or lower)	10,000	12.5

- 1/ When produced at temperatures of 275 ± 5 °F (135 ± 3 °C) or less, loose Warm Mix Asphalt shall be oven aged at 270 ± 5 °F (132 ± 3 °C) for two hours prior to gyratory compaction of Hamburg Wheel specimens.

Note: For SMA Designs (N-80) the maximum rut depth is 6.0 mm at 20,000 repetitions.
For IL 4.75mm Designs (N-50) the maximum rut depth is 9.0mm at 15,000 repetitions.

- (2) Tensile Strength Criteria. The minimum allowable conditioned tensile strength shall be 60 psi (415 kPa) for non-polymer modified performance graded (PG) asphalt binder and 80 psi (550 kPa) for polymer modified PG asphalt binder. The maximum allowable unconditioned tensile strength shall be 200 psi (1380 kPa)."

Production Testing. Revise first paragraph of Article 1030.06(a) of the Standard Specifications to read:

"(a) High ESAL, IL-4.75, WMA, and SMA Mixtures. For each contract, a 300 ton (275 metric tons) test strip, except for SMA mixtures it will be 400 ton (363 metric ton), will be required at the beginning of HMA production for each mixture at the beginning of each construction year according to the Manual of Test Procedures for Materials "Hot Mix Asphalt Test Strip Procedures". At the request of the Producer, the Engineer may waive the test strip if previous construction during the current construction year has demonstrated the constructability of the mix using Department test results."

Add the following after the sixth paragraph in Article 1030.06 (a) of the Standard Specifications:

"The Hamburg Wheel test shall also be conducted on all HMA mixtures from a sample taken within the first 500 tons (450 metric tons) on the first day of production or during start up with a split reserved for the Department. The mix sample shall be tested according to the Illinois Modified AASHTO T 324 and shall meet the requirements specified herein. Mix production shall not exceed 1500 tons (1350 metric tons) or one day's production, whichever comes first, until the testing is completed and the mixture is found to be in conformance. The requirement to cease mix production may be waived if the plant produced mixture demonstrates conformance prior to start of mix production for a contract. If the mixture fails to meet the Hamburg Wheel criteria, no further mixture will be accepted until the Contractor takes such action as is necessary to furnish a mixture meeting the criteria"

Method of Measurement:

Add the following after the fourth paragraph of Article 406.13 (b):

"The plan quantities of SMA mixtures shall be adjusted using the actual approved binder and surface Mix Design's G_{mb}."

Basis of Payment.

Replace the fourth paragraph of Article 406.14 of the Standard Specifications with the following:

"Stone matrix asphalt will be paid for at the contract unit price per ton (metric ton) for POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, of the mixture composition and Ndesign specified; and POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, of the mixture composition and Ndesign specified."

RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (DISTRICT 1)

Effective: November 1, 2012

Revise: January 1, 2018

Revise Section 1031 of the Standard Specifications to read:

"SECTION 1031. RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES

1031.01 Description. Reclaimed asphalt pavement and reclaimed asphalt shingles shall be according to the following.

- (a) Reclaimed Asphalt Pavement (RAP). RAP is the material resulting from cold milling or crushing an existing hot-mix asphalt (HMA) pavement. RAP will be considered processed FRAP after completion of both crushing and screening to size. The Contractor shall supply written documentation that the RAP originated from routes or airfields under federal, state, or local agency jurisdiction.
- (b) Reclaimed Asphalt Shingles (RAS). Reclaimed asphalt shingles (RAS). RAS is from the processing and grinding of preconsumer or post-consumer shingles. RAS shall be a clean and uniform material with a maximum of 0.5 percent unacceptable material, as defined in Central Bureau of Materials Policy Memorandum, "Reclaimed Asphalt Shingle (RAS) Sources", by weight of RAS. All RAS used shall come from a Central Bureau of Materials approved processing facility where it shall be ground and processed to 100 percent passing the 3/8 in. (9.5 mm) sieve and 90 percent passing the #4 (4.75 mm) sieve. RAS shall meet the testing requirements specified herein. In addition, RAS shall meet the following Type 1 or Type 2 requirements.
 - (1) Type 1. Type 1 RAS shall be processed, preconsumer asphalt shingles salvaged from the manufacture of residential asphalt roofing shingles.
 - (2) Type 2. Type 2 RAS shall be processed post-consumer shingles only, salvaged from residential, or four unit or less dwellings not subject to the National Emission Standards for Hazardous Air Pollutants (NESHAP).

1031.02 Stockpiles. RAP and RAS stockpiles shall be according to the following.

(a) RAP Stockpiles. The Contractor shall construct individual, sealed RAP stockpiles meeting one of the following definitions. Additional processed RAP (FRAP) shall be stockpiled in a separate working pile, as designated in the QC Plan, and only added to the sealed stockpile when test results for the working pile are complete and are found to meet tolerances specified herein for the original sealed FRAP stockpile. Stockpiles shall be sufficiently separated to prevent intermingling at the base. All stockpiles (including unprocessed RAP and FRAP) shall be identified by signs indicating the type as listed below (i.e. "Non- Quality, FRAP #4 or Type 2 RAS", etc...).

- (1) Fractionated RAP (FRAP). FRAP shall consist of RAP from Class I, HMA (High and Low ESAL) or equivalent mixtures. The coarse aggregate in FRAP shall be crushed aggregate and may represent more than one aggregate type and/or quality, but shall be at least C quality. All FRAP shall be processed prior to testing and sized into fractions with the separation occurring on or between the #4 (4.75 mm) and 1/2 in. (12.5 mm) sieves. Agglomerations shall be minimized such that 100 percent of the RAP in the coarse fraction shall pass the maximum sieve size specified for the mix the FRAP will be used in.
- (2) Restricted FRAP (B quality) stockpiles shall consist of RAP from Class I, HMA (High ESAL), or HMA (High ESAL). If approved by the Engineer, the aggregate from a maximum 3.0 in. (75 mm) single combined pass of surface/binder milling will be classified as B quality. All millings from this application will be processed into FRAP as described previously.
- (3) Conglomerate. Conglomerate RAP stockpiles shall consist of RAP from Class I, HMA (High and Low ESAL) or equivalent mixtures. The coarse aggregate in this RAP shall be crushed aggregate and may represent more than one aggregate type and/or quality, but shall be at least C quality. This RAP may have an inconsistent gradation and/or asphalt binder content prior to processing. All conglomerate RAP shall be processed (FRAP) prior to testing. Conglomerate RAP stockpiles shall not contain steel slag or other expansive material as determined by the Department.
- (4) Conglomerate "D" Quality (DQ). Conglomerate DQ RAP stockpiles shall consist of RAP from HMA shoulders, bituminous stabilized subbases or HMA (Low ESAL)/HMA (Low ESAL) IL-19.0L binder mixture. The coarse aggregate in this RAP may be crushed or round but shall be at least D quality. This RAP may have an inconsistent gradation and/or asphalt binder content. Conglomerate DQ RAP stockpiles shall not contain steel slag or other expansive material as determined by the Department.
- (5) Non-Quality. RAP stockpiles that do not meet the requirements of the stockpile categories listed above shall be classified as "Non-Quality".

RAP or FRAP containing contaminants, such as earth, brick, sand, concrete, sheet asphalt, bituminous surface treatment (i.e. chip seal), pavement fabric, joint sealants, plant cleanout etc., will be unacceptable unless the contaminants are removed to the satisfaction of the Engineer. Sheet asphalt shall be stockpiled separately.

(b) RAS Stockpiles. Type 1 and Type 2 RAS shall be stockpiled separately and shall be sufficiently separated to prevent intermingling at the base. Each stockpile shall be signed indicating what type of RAS is present.

However, a RAS source may submit a written request to the Department for approval to blend mechanically a specified ratio of Type 1 RAS with Type 2 RAS. The source will not be permitted to change the ratio of the blend without the Department prior written approval. The Engineer's written approval will be required, to mechanically blend RAS with any fine aggregate produced under the AGCS, up to an equal weight of RAS, to improve workability. The fine aggregate shall be "B Quality" or better from an approved Aggregate

Gradation Control System source. The fine aggregate shall be one that is approved for use in the HMA mixture and accounted for in the mix design and during HMA production.

Records identifying the shingle processing facility supplying the RAS, RAS type, and lot number shall be maintained by project contract number and kept for a minimum of three years.

1031.03 Testing. FRAP and RAS testing shall be according to the following.

- (a) FRAP Testing. When used in HMA, the FRAP shall be sampled and tested either during processing or after stockpiling. It shall also be sampled during HMA production.
 - (1) During Stockpiling. For testing during stockpiling, washed extraction samples shall be run at the minimum frequency of one sample per 500 tons (450 metric tons) for the first 2000 tons (1800 metric tons) and one sample per 2000 tons (1800 metric tons) thereafter. A minimum of five tests shall be required for stockpiles less than 4000 tons (3600 metric tons).
 - (2) Incoming Material. For testing as incoming material, washed extraction samples shall be run at a minimum frequency of one sample per 2000 tons (1800 metric tons) or once per week, whichever comes first.
 - (3) After Stockpiling. For testing after stockpiling, the Contractor shall submit a plan for approval to the District proposing a satisfactory method of sampling and testing the RAP/FRAP pile either in-situ or by restockpiling. The sampling plan shall meet the minimum frequency required above and detail the procedure used to obtain representative samples throughout the pile for testing.

Before extraction, each field sample of FRAP, shall be split to obtain two samples of test sample size. One of the two test samples from the final split shall be labeled and stored for Department use. The Contractor shall extract the other test sample according to Department procedure. The Engineer reserves the right to test any sample (split or Department-taken) to verify Contractor test results.

- (b) RAS Testing. RAS shall be sampled and tested during stockpiling according to Central Bureau of Materials Policy Memorandum, "Reclaimed Asphalt Shingle (RAS) Sources". The Contractor shall also sample as incoming material at the HMA plant.
 - (1) During Stockpiling. Washed extraction and testing for unacceptable materials shall be run at the minimum frequency of one sample per 200 tons (180 metric tons) for the first 1000 tons (900 metric tons) and one sample per 1000 tons (900 metric tons) thereafter. A minimum of five samples are required for stockpiles less than 1000 tons (900 metric tons). Once a ≤ 1000 ton (900 metric ton), five-sample/test stockpile has been established it shall be sealed. Additional incoming RAS shall be in a separate working pile as designated in the Quality Control plan and only added to the sealed stockpile when the test results of the working pile are complete and are found to meet the tolerances specified herein for the original sealed RAS stockpile.
 - (2) Incoming Material. For testing as incoming material at the HMA plant, washed extraction shall be run at the minimum frequency of one sample per 250 tons (227 metric tons). A minimum of five samples are required for stockpiles less than 1000 tons (900 metric tons). The incoming material test results shall meet the tolerances specified herein.

The Contractor shall obtain and make available all test results from start of the initial stockpile sampled and tested at the shingle processing facility in accordance with the facility's QC Plan.

Before extraction, each field sample shall be split to obtain two samples of test sample size. One of the two test samples from the final split shall be labeled and stored for Department use. The Contractor shall extract the other test sample according to Department procedures. The Engineer reserves the right to test any sample (split or Department-taken) to verify Contractor test results.

1031.04 Evaluation of Tests. Evaluation of test results shall be according to the following.

- (a) Evaluation of FRAP Test Results. All test results shall be compiled to include asphalt binder content, gradation and, when applicable (for slag), G_{mm} . A five test average of results from the original pile will be used in the mix designs. Individual extraction test results run thereafter, shall be compared to the average used for the mix design, and will be accepted if within the tolerances listed below.

Parameter	FRAP
No. 4 (4.75 mm)	± 6 %
No. 8 (2.36 mm)	± 5 %
No. 30 (600 μ m)	± 5 %
No. 200 (75 μ m)	± 2.0 %
Asphalt Binder	± 0.3 %
G_{mm}	± 0.03 ^{1/}

- 1/ For stockpile with slag or steel slag present as determined in the current Manual of Test Procedures Appendix B 21, "Determination of Reclaimed Asphalt Pavement Aggregate Bulk Specific Gravity".

If any individual sieve and/or asphalt binder content tests are out of the above tolerances when compared to the average used for the mix design, the FRAP stockpile shall not be used in Hot-Mix Asphalt unless the FRAP representing those tests is removed from the stockpile. All test data and acceptance ranges shall be sent to the District for evaluation.

The Contractor shall maintain a representative moving average of five tests to be used for Hot-Mix Asphalt production.

With the approval of the Engineer, the ignition oven may be substituted for extractions according to the ITP, "Calibration of the Ignition Oven for the Purpose of Characterizing Reclaimed Asphalt Pavement (RAP)" or Illinois Modified AASHTO T-164-11, Test Method A.

- (b) Evaluation of RAS Test Results. All of the test results, with the exception of percent unacceptable materials, shall be compiled and averaged for asphalt binder content and gradation. A five test average of results from the original pile will be used in the mix designs. Individual test results run thereafter, when compared to the average used for the mix design, will be accepted if within the tolerances listed below.

Parameter	RAS
No. 8 (2.36 mm)	± 5 %
No. 16 (1.18 mm)	± 5 %
No. 30 (600 μ m)	± 4 %
No. 200 (75 μ m)	± 2.5 %
Asphalt Binder Content	± 2.0 %

If any individual sieve and/or asphalt binder content tests are out of the above tolerances when compared to the average used for the mix design, the RAS shall not be used in Hot-Mix Asphalt unless the RAS representing those tests is removed from the stockpile. All test data and acceptance ranges shall be sent to the District for evaluation.

- (c) Quality Assurance by the Engineer. The Engineer may witness the sampling and splitting conduct assurance tests on split samples taken by the Contractor for quality control testing a minimum of once a month.

The overall testing frequency will be performed over the entire range of Contractor samples for asphalt binder content and gradation. The Engineer may select any or all split samples for assurance testing. The test results will be made available to the Contractor as soon as they become available.

The Engineer will notify the Contractor of observed deficiencies.

Differences between the Contractor's and the Engineer's split sample test results will be considered acceptable if within the following limits.

Test Parameter	Acceptable Limits of Precision	
	FRAP	RAS
% Passing: ^{1/}		
1/2 in.	5.0%	
No. 4	5.0%	
No. 8	3.0%	4.0%
No. 30	2.0%	4.0%
No. 200	2.2%	4.0%
Asphalt Binder Content	0.3%	3.0%
G _{mm}	0.030	

1/ Based on washed extraction.

In the event comparisons are outside the above acceptable limits of precision, the Engineer will immediately investigate.

- (d) Acceptance by the Engineer. Acceptable of the material will be based on the validation of the Contractor's quality control by the assurance process.

1031.05 Quality Designation of Aggregate in RAP and FRAP.

- (a) RAP. The aggregate quality of the RAP for homogeneous, conglomerate, and conglomerate "D" quality stockpiles shall be set by the lowest quality of coarse aggregate in the RAP stockpile and are designated as follows.

- (1) RAP from Class I, HMA (High ESAL), or (Low ESAL) IL-9.5L surface mixtures are designated as containing Class B quality coarse aggregate.
- (2) RAP from HMA (Low ESAL) IL-19.0L binder mixture is designated as Class D quality coarse aggregate.

- (3) RAP from Class I, HMA (High ESAL) binder mixtures, bituminous base course mixtures, and bituminous base course widening mixtures are designated as containing Class C quality coarse aggregate.
 - (4) RAP from bituminous stabilized subbase and BAM shoulders are designated as containing Class D quality coarse aggregate.
- (b) FRAP. If the Engineer has documentation of the quality of the FRAP aggregate, the Contractor shall use the assigned quality provided by the Engineer.

If the quality is not known, the quality shall be determined as follows. Fractionated RAP stockpiles containing plus #4 (4.75 mm) sieve coarse aggregate shall have a maximum tonnage of 5,000 tons (4,500 metric tons). The Contractor shall obtain a representative sample witnessed by the Engineer. The sample shall be a minimum of 50 lb (25 kg). The sample shall be extracted according to Illinois Modified AASHTO T 164 by a consultant laboratory prequalified by the Department for the specified testing. The consultant laboratory shall submit the test results along with the recovered aggregate to the District Office. The cost for this testing shall be paid by the Contractor. The District will forward the sample to the Central Bureau of Materials Aggregate Lab for MicroDeval Testing, according to ITP 327. A maximum loss of 15.0 percent will be applied for all HMA applications. The fine aggregate portion of the fractionated RAP shall not be used in any HMA mixtures that require a minimum of "B" quality aggregate or better, until the coarse aggregate fraction has been determined to be acceptable thru a MicroDeval Testing.

1031.06 Use of FRAP and/or RAS in HMA. The use of FRAP and/or RAS shall be the Contractor's option when constructing HMA in all contracts.

- (a) FRAP. The use of FRAP in HMA shall be as follows.
- (1) Coarse Aggregate Size (after extraction). The coarse aggregate in all FRAP shall be equal to or less than the nominal maximum size requirement for the HMA mixture to be produced.
 - (2) Steel Slag Stockpiles. FRAP stockpiles containing steel slag or other expansive material, as determined by the Department, shall be homogeneous and will be approved for use in HMA (High ESAL and Low ESAL) mixtures regardless of lift or mix type.
 - (3) Use in HMA Surface Mixtures (High and Low ESAL). FRAP stockpiles for use in HMA surface mixtures (High and Low ESAL) shall have coarse aggregate that is Class B quality or better. FRAP shall be considered equivalent to limestone for frictional considerations unless produced/screened to minus 3/8 inch.
 - (4) Use in HMA Binder Mixtures (High and Low ESAL), HMA Base Course, and HMA Base Course Widening. FRAP stockpiles for use in HMA binder mixtures (High and Low ESAL), HMA base course, and HMA base course widening shall be FRAP in which the coarse aggregate is Class C quality or better.
 - (5) Use in Shoulders and Subbase. FRAP stockpiles for use in HMA shoulders and stabilized subbase (HMA) shall be FRAP, Restricted FRAP, conglomerate, or conglomerate DQ.
- (b) RAS. RAS meeting Type 1 or Type 2 requirements will be permitted in all HMA applications as specified herein.
- (c) FRAP and/or RAS Usage Limits. Type 1 or Type 2 RAS may be used alone or in conjunction with FRAP in HMA mixtures up to a maximum of 5.0 percent by weight of the total mix.

When FRAP is used alone or FRAP is used in conjunction with RAS, the percent of virgin asphalt binder replacement (ABR) shall not exceed the amounts indicated in the table below for a given N Design.

Max Asphalt Binder Replacement for FRAP with RAS Combination

HMA Mixtures ^{1/2/4/}	Maximum % ABR			
	Ndesign	Binder/Leveling Binder	Surface	Polymer Modified ^{3/}
30L		50	40	30
50		40	35	30
70		40	30	30
90		40	30	30
4.75 mm N-50				40
SMA N-80				30

- 1/ For Low ESAL HMA shoulder and stabilized subbase, the percent asphalt binder replacement shall not exceed 50 % of the total asphalt binder in the mixture.
- 2/ When the binder replacement exceeds 15 % for all mixes, except for SMA and IL-4.75, the high and low virgin asphalt binder grades shall each be reduced by one grade (i.e. 25 % binder replacement using a virgin asphalt binder grade of PG64-22 will be reduced to a PG58-28). When constructing full depth HMA and the ABR is less than 15 %, the required virgin asphalt binder grade shall be PG64-28.
- 3/ When the ABR for SMA or IL-4.75 is 15 % or less, the required virgin asphalt binder shall be SBS PG76-22 and the elastic recovery shall be a minimum of 80. When the ABR for SMA or IL-4.75 exceeds 15%, the virgin asphalt binder grade shall be SBS PG70-28 and the elastic recovery shall be a minimum of 80.
- 4/ When FRAP or RAS is used alone, the maximum percent asphalt binder replacement designated on the table shall be reduced by 10 %.

1031.07 HMA Mix Designs. At the Contractor's option, HMA mixtures may be constructed utilizing RAP/FRAP and/or RAS material meeting the detailed requirements specified herein.

- (a) FRAP and/or RAS. FRAP and /or RAS mix designs shall be submitted for verification. If additional FRAP or RAS stockpiles are tested and found to be within tolerance, as defined under "Evaluation of Tests" herein, and meet all requirements herein, the additional FRAP or RAS stockpiles may be used in the original design at the percent previously verified.
- (b) RAS. Type 1 and Type 2 RAS are not interchangeable in a mix design.

The RAP, FRAP and RAS stone specific gravities (G_{sb}) shall be according to the "Determination of Aggregate Bulk (Dry) Specific Gravity (G_{sb}) or Reclaimed Asphalt Pavement (RAP) and Reclaimed Asphalt Shingles (RAS)" procedure in the Department's Manual of Test Procedures for Materials.

1031.08 HMA Production. HMA production utilizing FRAP and/or RAS shall be as follows.

To remove or reduce agglomerated material, a scalping screen, gator, crushing unit, or comparable sizing device approved by the Engineer shall be used in the RAS and FRAP feed system to remove or reduce oversized material. .

If during mix production, corrective actions fail to maintain FRAP, RAS or QC/QA test results within control tolerances or the requirements listed herein the Contractor shall cease production of the mixture containing FRAP or RAS and conduct an investigation that may require a new mix design.

- (a) RAS. RAS shall be incorporated into the HMA mixture either by a separate weight depletion system or by using the RAP weigh belt. Either feed system shall be interlocked with the aggregate feed or weigh system to maintain correct proportions for all rates of production and batch sizes. The portion of RAS shall be controlled accurately to within ± 0.5 percent of the amount of RAS utilized. When using the weight depletion system, flow indicators or sensing devices shall be provided and interlocked with the plant controls such that the mixture production is halted when RAS flow is interrupted.
- (b) HMA Plant Requirements. HMA plants utilizing FRAP and/or RAS shall be capable of automatically recording and printing the following information.

(1) Dryer Drum Plants.

- a. Date, month, year, and time to the nearest minute for each print.
- b. HMA mix number assigned by the Department.
- c. Accumulated weight of dry aggregate (combined or individual) in tons (metric tons) to the nearest 0.1 ton (0.1 metric ton).
- d. Accumulated dry weight of RAS and FRAP in tons (metric tons) to the nearest 0.1 ton (0.1 metric ton).
- e. Accumulated mineral filler in revolutions, tons (metric tons), etc. to the nearest 0.1 unit.
- f. Accumulated asphalt binder in gallons (liters), tons (metric tons), etc. to the nearest 0.1 unit.
- g. Residual asphalt binder in the RAS and FRAP material as a percent of the total mix to the nearest 0.1 percent.
- h. Aggregate RAS and FRAP moisture compensators in percent as set on the control panel. (Required when accumulated or individual aggregate and RAS and FRAP are printed in wet condition.)
- i. When producing mixtures with FRAP and/or RAS, a positive dust control system shall be utilized.
- j. Accumulated mixture tonnage.
- k. Dust Removed (accumulated to the nearest 0.1 ton (0.1 metric ton))

(2) Batch Plants.

- a. Date, month, year, and time to the nearest minute for each print.
- b. HMA mix number assigned by the Department.

- c. Individual virgin aggregate hot bin batch weights to the nearest pound (kilogram).
- d. Mineral filler weight to the nearest pound (kilogram).
- f. RAS and FRAP weight to the nearest pound (kilogram).
- g. Virgin asphalt binder weight to the nearest pound (kilogram).
- h. Residual asphalt binder in the RAS and FRAP material as a percent of the total mix to the nearest 0.1 percent.

The printouts shall be maintained in a file at the plant for a minimum of one year or as directed by the Engineer and shall be made available upon request. The printing system will be inspected by the Engineer prior to production and verified at the beginning of each construction season thereafter.

1031.09 RAP in Aggregate Surface Course and Aggregate Wedge Shoulders, Type B. The use of RAP or FRAP in aggregate surface course and aggregate shoulders shall be as follows.

- (a) Stockpiles and Testing. RAP stockpiles may be any of those listed in Article 1031.02, except "Non-Quality" and "FRAP". The testing requirements of Article 1031.03 shall not apply. RAP used shall be according to the current Central Bureau of Materials Policy Memorandum, "Reclaimed Asphalt Pavement (RAP) for Aggregate Applications".
- (b) Gradation. The RAP material shall meet the gradation requirements for CA 6 according to Article 1004.01(c), except the requirements for the minus No. 200 (75 μ m) sieve shall not apply. The sample for the RAP material shall be air dried to constant weight prior to being tested for gradation."

State of Illinois
Department of Transportation

SPECIAL PROVISION
FOR
QUALITY CONTROL/QUALITY ASSURANCE OF CONCRETE MIXTURES

Effective: April 1, 1992
Revised: January 1, 2015

Add the following to Section 1020 of the Standard Specifications:

"1020.16 Quality Control/Quality Assurance of Concrete Mixtures. This Article specifies the quality control responsibilities of the Contractor for concrete mixtures (except Class PC and PS concrete), cement aggregate mixture II, and controlled low-strength material incorporated in the project, and defines the quality assurance and acceptance responsibilities of the Engineer.

A list of quality control/quality assurance (QC/QA) documents is provided in Article 1020.16(g), Schedule D.

A Level I Portland Cement Concrete (PCC) Technician shall be defined as an individual who has successfully completed the Department's training for concrete testing.

A Level II Portland Cement Concrete (PCC) Technician shall be defined as an individual who has successfully completed the Department's training for concrete proportioning.

A Level III Portland Cement Concrete (PCC) Technician shall be defined as an individual who has successfully completed the Department's training for concrete mix design.

A Concrete Tester shall be defined as an individual who has successfully completed the Department's training to assist with concrete testing and is monitored on a daily basis.

Aggregate Technician shall be defined as an individual who has successfully completed the Department's training for gradation testing involving aggregate production and mixtures.

Mixture Aggregate Technician shall be defined as an individual who has successfully completed the Department's training for gradation testing involving mixtures.

Gradation Technician shall be defined as an individual who has successfully completed the Department's training to assist with gradation testing and is monitored on a daily basis.

- (a) Equipment/Laboratory. The Contractor shall provide a laboratory and test equipment to perform their quality control testing.

CHECK SHEET #25

The laboratory shall be of sufficient size and be furnished with the necessary equipment, supplies, and current published test methods for adequately and safely performing all required tests. The laboratory will be approved by the Engineer according to the current Bureau of Materials and Physical Research Policy Memorandum "Minimum Private Laboratory Requirements for Construction Materials Testing or Mix Design". Production of a mixture shall not begin until the Engineer provides written approval of the laboratory. The Contractor shall refer to the Department's "Required Sampling and Testing Equipment for Concrete" for equipment requirements.

Test equipment shall be maintained and calibrated as required by the appropriate test method, and when required by the Engineer. This information shall be documented on the Department's "Calibration of Concrete Testing Equipment" forms BMPR PCCQ01 through BMPR PCCQ09.

Test equipment used to determine compressive or flexural strength shall be calibrated each 12 month period by an independent agency, using calibration equipment traceable to the National Institute of Standards and Technology (NIST). The Contractor shall have the calibration documentation available at the test equipment location.

The Engineer will have unrestricted access to the plant and laboratory at any time to inspect measuring and testing equipment, and will notify the Contractor of any deficiencies. Defective equipment shall be immediately repaired or replaced by the Contractor.

- (b) **Quality Control Plan.** The Contractor shall submit, in writing, a proposed Quality Control (QC) Plan to the Engineer. The QC Plan shall be submitted a minimum of 45 calendar days prior to the production of a mixture. The QC Plan shall address the quality control of the concrete, cement aggregate mixture II, and controlled low-strength material incorporated in the project. The Contractor shall refer to the Department's "Model Quality Control Plan for Concrete Production" to prepare a QC Plan. The Engineer will respond in writing to the Contractor's proposed QC Plan within 15 calendar days of receipt.

Production of a mixture shall not begin until the Engineer provides written approval of the QC Plan. The approved QC Plan shall become a part of the contract between the Department and the Contractor, but shall not be construed as acceptance of any mixture produced.

The QC Plan may be amended during the progress of the work, by either party, subject to mutual agreement. The Engineer will respond in writing to a Contractor's proposed QC Plan amendment within 15 calendar days of receipt. The response will indicate the approval or denial of the Contractor's proposed QC Plan amendment.

- (c) **Quality Control by Contractor.** The Contractor shall perform quality control inspection, sampling, testing, and documentation to meet contract requirements. Quality control includes the recognition of obvious defects

CHECK SHEET #25

and their immediate correction. Quality control also includes appropriate action when passing test results are near specification limits, or to resolve test result differences with the Engineer. Quality control may require increased testing, communication of test results to the plant or the jobsite, modification of operations, suspension of mixture production, rejection of material, or other actions as appropriate. The Engineer shall be immediately notified of any failing tests and subsequent remedial action. Passing tests shall be reported no later than the start of the next work day.

When a mixture does not comply with specifications, the Contractor shall reject the material, unless the Engineer accepts the material for incorporation in the work, according to Article 105.03.

- (1) Personnel Requirements. The Contractor shall provide a Quality Control (QC) Manager who will have overall responsibility and authority for quality control. The jobsite and plant personnel shall be able to contact the QC Manager by cellular phone, two-way radio, or other methods approved by the Engineer.

The QC Manager shall visit the jobsite a minimum of once a week. A visit shall be performed the day of a bridge deck pour, the day a non-routine mixture is placed as determined by the Engineer, or the day a plant is anticipated to produce more than 1000 cu yd (765 cu m). Any of the three required visits may be used to meet the once per week minimum requirement.

The Contractor shall provide personnel to perform the required inspections, sampling, testing, and documentation in a timely manner. The Contractor shall refer to the Department's "Qualifications and Duties of Concrete Quality Control Personnel" document.

A Level I PCC Technician shall be provided at the jobsite during mixture production and placement, and may supervise concurrent pours on the project. For concurrent pours, a minimum of one Concrete Tester shall be required at each pour location. If the Level I PCC Technician is at one of the pour locations, a Concrete Tester is still required at the same location. Each Concrete Tester shall be able to contact the Level I PCC Technician by cellular phone, two-way radio, or other methods approved by the Engineer. A single Level I PCC Technician shall not supervise concurrent pours for multiple contracts.

A Level II PCC Technician shall be provided at the plant, or shall be available, during mixture production and placement. A Level II PCC Technician may supervise a maximum of three plants. Whenever the Level II PCC Technician is not at the plant during mixture production and placement, a Concrete Tester or Level I PCC Technician shall be present at the plant to perform any necessary concrete tests. The Concrete Tester, Level I PCC Technician, or other individual shall also be trained to perform any necessary aggregate moisture tests, if the Level II PCC Technician is not at the plant during mixture production and placement. The Concrete Tester, Level I PCC Technician, plant personnel, and jobsite personnel shall have the ability to contact the

CHECK SHEET #25

Level II PCC Technician by cellular phone, two-way radio, or other methods approved by the Engineer.

For a mixture which is produced and placed with a mobile portland cement concrete plant as defined in Article 1103.04, a Level II PCC Technician shall be provided. The Level II PCC Technician shall be present at all times during mixture production and placement. However, the Level II PCC Technician may request to be available if operations are satisfactory. Approval shall be obtained from the Engineer, and jobsite personnel shall have the ability to contact the Level II PCC Technician by cellular phone, two-way radio, or other methods approved by the Engineer.

A Concrete Tester, Mixture Aggregate Technician, and Aggregate Technician may provide assistance with sampling and testing. A Gradation Technician may provide assistance with testing. A Concrete Tester shall be supervised by a Level I or Level II PCC Technician. A Gradation Technician shall be supervised by a Level II PCC Technician, Mixture Aggregate Technician, or Aggregate Technician.

- (2) Required Plant Tests. Sampling and testing shall be performed at the plant, or at a location approved by the Engineer, to control the production of a mixture. The required minimum Contractor plant sampling and testing is indicated in Article 1020.16(g) Schedule A.
 - (3) Required Field Tests. Sampling and testing shall be performed at the jobsite to control the production of a mixture, and to comply with specifications for placement. For standard curing, after initial curing, and for strength testing, the location shall be approved by the Engineer. The required minimum Contractor jobsite sampling and testing is indicated in Article 1020.16(g), Schedule B.
- (d) Quality Assurance by Engineer. The Engineer will perform quality assurance tests on independent samples and split samples. An independent sample is a field sample obtained and tested by only one party. A split sample is one of two equal portions of a field sample, where two parties each receive one portion for testing. The Engineer may request the Contractor to obtain a split sample. Aggregate split samples and any failing strength specimen shall be retained until permission is given by the Engineer for disposal. The results of all quality assurance tests by the Engineer will be made available to the Contractor. However, Contractor split sample test results shall be provided to the Engineer before Department test results are revealed. The Engineer's quality assurance independent sample and split sample testing are indicated in Article 1020.16(g), Schedule C.
- (1) Strength Testing. For strength testing, Article 1020.09 shall apply, except the Contractor and Engineer strength specimens may be placed in the same field curing box for initial curing and may be cured in the same water storage tank for final curing.

CHECK SHEET #25

- (2) Comparing Test Results. Differences between the Engineer's and the Contractor's split sample test results will be considered reasonable if within the following limits:

Test Parameter	Acceptable Limits of Precision
Slump	0.75 in. (20 mm)
Air Content	0.9%
Compressive Strength	900 psi (6200 kPa)
Flexural Strength	90 psi (620 kPa)
Slump Flow (Self-Consolidating Concrete (SCC))	1.5 in. (40 mm)
Visual Stability Index (SCC)	Not Applicable
J-Ring (SCC)	1.5 in. (40 mm)
L-Box (SCC)	10 %
Hardened Visual Stability Index (SCC)	Not Applicable
Dynamic Segregation Index (SCC)	1.0 %
Flow (Controlled Low-Strength Material (CLSM))	1.5 in. (40 mm)
Strength (CLSM)	40 psi (275 kPa)
Aggregate Gradation	See "Guideline for Sample Comparison" in Appendix "A" of the Manual of Test Procedures for Materials.

When acceptable limits of precision have been met, but only one party is within specification limits, the failing test shall be resolved before the material may be considered for acceptance.

- (3) Test Results and Specification Limits.

- a. Split Sample Testing. If either the Engineer's or the Contractor's split sample test result is not within specification limits and the other party is within specification limits, immediate retests on a split sample shall be performed for slump, air content, slump flow, visual stability index, J-Ring, L-Box, dynamic segregation index, flow (CLSM), or aggregate gradation. A passing retest result by each party will require no further action. If either the Engineer's or Contractor's slump, air content, slump flow, visual stability index, J-Ring, L-Box, dynamic segregation index, flow (CLSM), or aggregate gradation split sample retest result is a failure; or if either the Engineer's or Contractor's strength or hardened visual stability index test result is a failure and the other party is within specification limits; the following actions shall be initiated to investigate the test failure:

1. The Engineer and the Contractor shall investigate the sampling method, test procedure, equipment condition, equipment calibration, and other factors.

CHECK SHEET #25

2. The Engineer or the Contractor shall replace test equipment, as determined by the Engineer.
3. The Engineer and the Contractor shall perform additional testing on split samples, as determined by the Engineer.

For aggregate gradation, jobsite slump, jobsite air content, jobsite slump flow, jobsite visual stability index, jobsite J-Ring, jobsite L-Box, jobsite dynamic segregation index, and jobsite flow (CLSM), if the failing split sample test result is not resolved according to 1., 2., or 3., and the mixture has not been placed, the Contractor shall reject the material; unless the Engineer accepts the material for incorporation in the work, according to Article 105.03. If the mixture has already been placed, or if a failing strength or hardened visual stability index test result is not resolved according to 1., 2., or 3., the material will be considered unacceptable.

If a continued trend of difference exists between the Engineer's and the Contractor's split sample test results, or if split sample test results exceed the acceptable limits of precision, the Engineer and the Contractor shall investigate according to items 1., 2., and 3.

- b. Independent Sample Testing. For aggregate gradation, jobsite slump, jobsite air content, jobsite slump flow, jobsite visual stability index, jobsite J-Ring, jobsite L-Box, jobsite dynamic segregation index, jobsite flow (CLSM), if the result of a quality assurance test on a sample independently obtained by the Engineer is not within specification limits, and the mixture has not been placed, the Contractor shall reject the material; unless the Engineer accepts the material for incorporation in the work, according to Article 105.03. If the mixture has already been placed or the Engineer obtains a failing strength or hardened visual stability index test result, the material will be considered unacceptable.
- (e) Acceptance by the Engineer. Final acceptance will be based on the Standard Specifications and the following:
- (1) The Contractor's compliance with all contract documents for quality control.
 - (2) Validation of Contractor quality control test results by comparison with the Engineer's quality assurance test results using split samples. Any quality control or quality assurance test determined to be flawed may be declared invalid only when reviewed and approved by the Engineer. The Engineer will declare a test result invalid only if it is proven that improper sampling or testing occurred. The test result is to be recorded and the reason for declaring the test invalid will be provided by the Engineer.

CHECK SHEET #25

- (3) Comparison of the Engineer's quality assurance test results with specification limits using samples independently obtained by the Engineer.

The Engineer may suspend mixture production, reject materials, or take other appropriate action if the Contractor does not control the quality of concrete, cement aggregate mixture II, or controlled low-strength material for acceptance. The decision will be determined according to (1), (2), or (3).

(f) Documentation.

- (1) Records. The Contractor shall be responsible for documenting all observations, inspections, adjustments to the mix design, test results, retest results, and corrective actions in a bound hardback field book, bound hardback diary, or appropriate Department form, which shall become the property of the Department. The documentation shall include a method to compare the Engineer's test results with the Contractor's results. The Contractor shall be responsible for the maintenance of all permanent records whether obtained by the Contractor, the consultants, the subcontractors, or the producer of the mixture. The Contractor shall provide the Engineer full access to all documentation throughout the progress of the work.

The Department's form BMPR MI504, form BMPR MI654, and form BMPR MI655 shall be completed by the Contractor, and shall be submitted to the Engineer weekly or as required by the Engineer. A correctly completed form BMPR MI504, form BMPR MI654, and form BMPR MI655 are required to authorize payment by the Engineer for applicable pay items.

- (2) Delivery Truck Ticket. The following information shall be recorded on each delivery ticket or in a bound hardback field book: initial revolution counter reading (final reading optional) at the jobsite, if the mixture is truck-mixed; time discharged at the jobsite; total amount of each admixture added at the jobsite; and total amount of water added at the jobsite.

- (g) Basis of Payment and Schedules. Quality Control/Quality Assurance of portland cement concrete mixtures will not be paid for separately, but shall be considered as included in the cost of the various concrete contract items.

CHECK SHEET #25

SCHEDULE A

CONTRACTOR PLANT SAMPLING AND TESTING			
Item	Test	Frequency	IL Modified AASHTO, IL Modified ASTM, or Illinois Test Procedure ^{1/}
Aggregates (Arriving at Plant)	Gradation ^{2/}	As needed to check source for each gradation number	ITP 2, ITP 11, ITP 27, and ITP 248
Aggregates (Stored at Plant in Stockpiles or Bins)	Gradation ^{2/}	2500 cu yd (1900 cu m) for each gradation number ^{3/}	ITP 2, ITP 11, ITP 27, and ITP 248
Aggregates (Stored at Plant in Stockpiles or Bins)	Moisture ^{4/} : Fine Aggregate	Once per week for moisture sensor, otherwise daily for each gradation number	Flask, Dunagan, Pychnometer Jar, or ITP 255
	Moisture ^{4/} : Coarse Aggregate	As needed to control production for each gradation number	Dunagan, Pychnometer Jar, or ITP 255
Mixture ^{5/}	Slump Air Content Unit Weight / Yield Slump Flow (SCC) Visual Stability Index (SCC) J-Ring (SCC) ^{6/} L-Box (SCC) ^{6/} Temperature	As needed to control production	R 60 and T 119 R 60 and T 152 or T 196 R 60 and T 121 ITP SCC-1 and ITP SCC-2 ITP SCC-1 and ITP SCC-2 ITP SCC-1 and ITP SCC-3 ITP SCC-1 and ITP SCC-4 R 60 and ASTM C 1064
Mixture (CLSM) ^{7/}	Flow Air Content Temperature	As needed to control production	ITP 307

- 1/ Refer to the Department's "Manual of Test Procedures for Materials".
- 2/ All gradation tests shall be washed. Testing shall be completed no later than 24 hours after the aggregate has been sampled.
- 3/ One per week (Sunday through Saturday) minimum, unless the stockpile has not received additional aggregate material since the previous test.

One per day minimum for a bridge deck pour, unless the stockpile has not received additional aggregate material since the previous test. The sample shall be taken and testing completed prior to the pour. The bridge deck aggregate sample may be taken the day before the pour or as approved by the Engineer.

- 4/ If the moisture test and moisture sensor disagree by more than 0.5 percent, retest. If the difference remains, adjust the moisture sensor to an average of two or more moisture tests. The Department's "Water/Cement Ratio Worksheet" form (BMPR PCCW01) shall be completed, when applicable.

CHECK SHEET #25

- 5/ The Contractor may also perform strength testing according to Illinois Modified AASHTO R 60, T 23, and T 22 or T 177; or water content testing according to Illinois Modified AASHTO T 318.

The Contractor may also perform other available self-consolidating concrete (SCC) tests at the plant to control mixture production.

- 6/ The Contractor shall select the J-Ring or L-Box test for plant sampling and testing.

- 7/ The Contractor may also perform strength testing according to ITP 307.

CHECK SHEET #25

SCHEDULE B

CONTRACTOR JOBSITE SAMPLING & TESTING ^{1/}			
Item	Measured Property	Random Sample Testing Frequency per Mix Design and per Plant ^{2/}	IL Modified AASHTO, IL Modified ASTM, or Illinois Test Procedure
Pavement, Shoulder, Base Course, Base Course Widening, Driveway Pavement, Railroad Crossing, Cement Aggregate Mixture II	Slump ^{3/ 4/}	1 per 500 cu yd (400 cu m) or minimum 1/day	R 60 and T 119
	Air Content ^{3/ 5/ 6/}	1 per 100 cu yd (80 cu m) or minimum 1/day	R 60 and T 152 or T 196
	Compressive Strength ^{7/ 8/} or Flexural Strength ^{7/ 8/}	1 per 1250 cu yd (1000 cu m) or minimum 1/day	R 60, T 22 and T 23 or R 60, T 177 and T 23
Bridge Approach Slab ^{9/} , Bridge Deck ^{9/} , Bridge Deck Overlay ^{9/} , Superstructure ^{9/} , Substructure, Culvert, Miscellaneous Drainage Structures, Retaining Wall, Building Wall, Drilled Shaft Pile & Encasement Footing, Foundation, Pavement Patching, Structural Repairs	Slump ^{3/ 4/}	1 per 50 cu yd (40 cu m) or minimum 1/day	R 60 and T 119
	Air Content ^{3/ 5/ 6/}	1 per 50 cu yd (40 cu m) or minimum 1/day	R 60 and T 152 or T 196
	Compressive Strength ^{7/ 8/} or Flexural Strength ^{7/ 8/}	1 per 250 cu yd (200 cu m) or minimum 1/day	R 60, T 22 and T 23 or R 60, T 177 and T 23
Seal Coat	Slump ^{3/}	1 per 250 cu yd (200 cu m) or minimum 1/day	R 60 and T 119
	Air Content ^{3/ 5/ 6/}	1 per 250 cu yd (200 cu m) or minimum 1/day when air is entrained	R 60 and T 152 or T 196
	Compressive Strength ^{7/ 8/} or Flexural Strength ^{7/ 8/}	1 per 250 cu yd (200 cu m) or minimum 1/day	R 60, T 22 and T 23 or R 60, T 177 and T 23

CHECK SHEET #25

CONTRACTOR JOBSITE SAMPLING & TESTING ^{1/}			
Curb, Gutter, Median, Barrier, Sidewalk, Slope Wall, Paved Ditch, Fabric Formed Concrete Revetment Mat ^{10/} , Miscellaneous Items, Incidental Items	Slump ^{3/ 4/}	1 per 100 cu yd (80 cu m) or minimum 1/day	R 60 and T 119
	Air Content ^{3/ 5/ 6/}	1 per 50 cu yd (40 cu m) or minimum 1/day	R 60 and T 152 or T 196
	Compressive Strength ^{7/ 8/} or Flexural Strength ^{7/ 8/}	1 per 400 cu yd (300 cu m) or minimum 1/day	R 60, T 22 and T 23 or R 60, T 177 and T 23
Items Using Self- Consolidating Concrete	Slump Flow ^{3/} VSI ^{3/} J-Ring ^{3/ 11/} L-Box ^{3/ 11/}	Perform at same frequency that is specified for the Item's slump	ITP SCC-1 & ITP SCC-2 ITP SCC-1 & ITP SCC-2 ITP SCC-1 & ITP SCC-3 ITP SCC-1 & ITP SCC-4
	HVSI ^{12/}	Minimum 1/day at start of production for that day	ITP SCC-1 and ITP SCC-6
	Dynamic Segregation Index (DSI)	Minimum 1/week at start of production for that week	ITP SCC-1 and ITP SCC-8 (Option C)
	Air Content ^{3/ 5/ 6/}	Perform at same frequency that is specified for the Item's air content	ITP SCC-1 and T 152 or T 196
	Compressive Strength ^{7/ 8/} or Flexural Strength ^{7/ 8/}	Perform at same frequency that is specified for the Item's strength	ITP SCC-1, T 22 and T 23 or ITP SCC-1, T 177 and T 23
All	Temperature ^{3/}	As needed to control production	R 60 and ASTM C 1064
Controlled Low- Strength Material (CLSM)	Flow, Air Content, Compressive Strength (28-day) ^{13/} , and Temperature	First truck load delivered and as needed to control production thereafter	ITP 307

1/ Sampling and testing of small quantities of curb, gutter, median, barrier, sidewalk, slope wall, paved ditch, miscellaneous items, and incidental items may be waived by the Engineer, if requested by the Contractor. However, quality control personnel are still required according to Article 1020.16(c)(1). The Contractor shall also provide recent evidence that similar material has been found to be satisfactory under normal sampling and testing

CHECK SHEET #25

procedures. The total quantity that may be waived for testing shall not exceed 100 cu yd (76 cu m) per contract.

If the Contractor's or Engineer's test result for any jobsite mixture test is not within the specification limits, all subsequent truck loads delivered shall be tested by the Contractor until the problem is corrected.

- 2/ If one mix design is being used for several construction items during a day's production, one testing frequency may be selected to include all items. The construction items shall have the same slump, air content, and water/cement ratio specifications. For self-consolidating concrete, the construction items shall have the same slump flow, visual stability index, J-Ring, L-Box, air content, and water/cement ratio specifications. The frequency selected shall equal or exceed the testing required for the construction item.

One sufficiently sized sample shall be taken to perform the required test(s). Random numbers shall be determined according to the Department's "Method for Obtaining Random Samples for Concrete". The Engineer will provide random sample locations.

- 3/ The temperature, slump, and air content tests shall be performed on the first truck load delivered, for each pour. For self-consolidating concrete, the temperature, slump flow, visual stability index, J-Ring or L-Box, and air content tests shall be performed on the first truck load delivered, for each pour. Unless a random sample is required for the first truck load, testing the first truck load does not satisfy random sampling requirements.
- 4/ The slump random sample testing frequency shall be a minimum 1/day for a construction item which is slipformed.
- 5/ If a pump or conveyor is used for placement, a correction factor shall be established to allow for a loss of air content during transport. The first three truck loads delivered shall be tested, before and after transport by the pump or conveyor, to establish the correction factor. Once the correction is determined, it shall be re-checked after an additional 50 cu yd (38 cu m) is pumped, or an additional 100 cu yd (76 cu m) is transported by conveyor. This shall continue throughout the pour. If the re-check indicates the correction factor has changed, a minimum of two truckloads is required to re-establish the correction factor. The correction factor shall also be re-established when significant changes in temperature, distance, pump or conveyor arrangement, and other factors have occurred. If the correction factor is greater than 3.0 percent, the Contractor shall take corrective action to reduce the loss of air content during transport by the pump or conveyor. The Contractor shall record all air content test results, correction factors, and corrected air contents. The corrected air content shall be reported on form BMPR MI654.
- 6/ If the Contractor's or Engineer's air content test result is within the specification limits, and 0.2 percent or closer to either limit, the next truck load delivered shall be tested by the Contractor. For example, if the specified air content range is 5.0 to 8.0 percent and the test result is 5.0, 5.1, 5.2, 7.8, 7.9, or 8.0 percent, the next truck shall be tested by the Contractor.

CHECK SHEET #25

- 7/ The test of record for strength shall be the day indicated in Article 1020.04. For cement aggregate mixture II, a strength requirement is not specified and testing is not required. Additional strength testing to determine early falsework and form removal, early pavement or bridge opening to traffic, or to monitor strengths is at the discretion of the Contractor. Strength shall be defined as the average of two 6 x 12 in. (150 x 300 mm) cylinder breaks, three 4 x 8 in. (100 x 200 mm) cylinder breaks, or two beam breaks for field tests. Per Illinois Modified AASHTO T 23, cylinders shall be 6 x 12 in. (150 x 300 mm) when the nominal maximum size of the coarse aggregate exceeds 1 in. (25 mm). Nominal maximum size is defined as the largest sieve which retains any of the aggregate sample particles.
- 8/ In addition to the strength test, a slump test, air content test, and temperature test shall be performed on the same sample. For self-consolidating concrete, a slump flow test, visual stability index test, J-Ring or L-Box test, air content test, and temperature test shall be performed on the same sample as the strength test. For mixtures pumped or conveyed, the Contractor shall sample according to Illinois Modified AASHTO R 60.
- 9/ The air content test will be required for each delivered truck load.
- 10/ For fabric formed concrete revetment mat, the slump test is not required and the flexural strength test is not applicable.
- 11/ The Contractor shall select the J-Ring or L-Box test for jobsite sampling and testing.
- 12/ In addition to the hardened visual stability index (HVSI) test, a slump flow test, visual stability index (VSI) test, J-Ring or L-Box test, air content test, and temperature test shall be performed on the same sample. The Contractor shall retain all hardened visual stability index cut cylinder specimens until the Engineer notifies the Contractor that the specimens may be discarded.
- 13/ The test of record for strength shall be the day indicated in Article 1019.04. In addition to the strength test, a flow test, air content test, and temperature test shall be performed on the same sample. The strength test may be waived by the Engineer if future removal of the material is not a concern.

CHECK SHEET #25

SCHEDULE C

ENGINEER QUALITY ASSURANCE INDEPENDENT SAMPLE TESTING		
Location	Measured Property	Testing Frequency ^{1/}
Plant	Gradation of aggregates stored in stockpiles or bins, Slump and Air Content	As determined by the Engineer.
Jobsite	Slump, Air Content, Slump Flow, Visual Stability Index, J-Ring, L-Box, Hardened Visual Stability Index, Dynamic Segregation Index, and Strength	As determined by the Engineer.
	Flow, Air Content, Strength (28-day), and Dynamic Cone Penetration for Controlled Low-Strength Material (CLSM)	As determined by the Engineer

ENGINEER QUALITY ASSURANCE SPLIT SAMPLE TESTING ^{2/}		
Location	Measured Property	Testing Frequency ^{1/}
Plant	Gradation of aggregates stored in stockpiles or bins	At the beginning of the project, the first test performed by the Contractor. Thereafter, a minimum of 10% of total tests required of the Contractor will be performed per aggregate gradation number and per plant.
	Slump, Air Content, Slump Flow (SCC), Visual Stability Index (SCC), J-Ring (SCC), and L-Box (SCC)	As determined by the Engineer.
Jobsite	Slump, Air Content ^{3/} , Slump Flow, Visual Stability Index, J-Ring and L-Box	At the beginning of the project, the first three tests performed by the Contractor. Thereafter, a minimum of 20% of total tests required of the Contractor will be performed per plant, which will include a minimum of one test per mix design.
	Hardened Visual Stability Index	As determined by the Engineer.
	Dynamic Segregation Index	As determined by the Engineer.
	Strength	At the beginning of the project, the first test performed by the Contractor. Thereafter, a minimum of 20% of total tests required of the Contractor will be performed per plant, which will include a minimum of one test per mix design.
	Flow, Air Content, and Strength (28-day) for Controlled Low-Strength Material (CLSM)	As determined by the Engineer.

CHECK SHEET #25

- 1/ The Engineer will perform the testing throughout the period of quality control testing by the Contractor.
- 2/ The Engineer will witness and take immediate possession of or otherwise secure the Department's split sample obtained by the Contractor.
- 3/ Before transport by pump or conveyor, a minimum of 20 percent of total tests required of the Contractor will be performed per mix design and per plant. After transport by pump or conveyor, a minimum of 20 percent of total tests required of the Contractor will be performed per mix design and per plant.

CHECK SHEET #25

SCHEDULE D

CONCRETE QUALITY CONTROL AND QUALITY ASSURANCE DOCUMENTS

- (a) Model Quality Control Plan for Concrete Production (*)
- (b) Qualifications and Duties of Concrete Quality Control Personnel (*)
- (c) Development of Gradation Bands on Incoming Aggregate at Mix Plants (*)
- (d) Required Sampling and Testing Equipment for Concrete (*)
- (e) Method for Obtaining Random Samples for Concrete (*)
- (f) Calibration of Concrete Testing Equipment (BMPR PCCQ01 through BMPR PCCQ09) (*)
- (g) Water/Cement Ratio Worksheet (BMPR PCCW01) (*)
- (h) Field/Lab Gradations (BMPR MI504) (*)
- (i) Concrete Air, Slump and Quantity (BMPR MI654) (*)
- (j) P.C. Concrete Strengths (BMPR MI655) (*)
- (k) Aggregate Technician Course or Mixture Aggregate Technician Course (*)
- (l) Portland Cement Concrete Tester Course (*)
- (m) Portland Cement Concrete Level I Technician Course - Manual of Instructions for Concrete Testing (*)
- (n) Portland Cement Concrete Level II Technician Course - Manual of Instructions for Concrete Proportioning (*)
- (o) Portland Cement Concrete Level III Technician Course - Manual of Instructions for Design of Concrete Mixtures (*)
- (p) Manual of Test Procedures for Materials

* Refer to Appendix C of the Department's "Manual of Test Procedures for Materials" for more information.

PREVAILING WAGES

**Prevailing Wage rates
for Cook County
effective Sept. 1, 2017**

Trade Title	Region	Type	Class	Base Wage	Fore-man Wage	M-F OT	OSA	OSH	H/W	Pension	Vacation	Training
ASBESTOS ABT-GEN	ALL	ALL		41.20	42.20	1.5	1.5	2	14.65	12.32	0.00	0.50
ASBESTOS ABT-MEC	ALL	BLD		37.46	39.96	1.5	1.5	2	11.62	11.06	0.00	0.72
BOILERMAKER	ALL	BLD		48.49	52.86	2	2	2	6.97	19.61	0.00	0.90
BRICK MASON	ALL	BLD		45.38	49.92	1.5	1.5	2	10.45	16.68	0.00	0.90
CARPENTER	ALL	ALL		46.35	48.35	1.5	1.5	2	11.79	18.87	0.00	0.63
CEMENT MASON	ALL	ALL		44.25	46.25	2	1.5	2	14.00	17.16	0.00	0.92
CERAMIC TILE FNShER	ALL	BLD		38.56	38.56	1.5	1.5	2	10.65	11.18	0.00	0.68
COMM. ELECT.	ALL	BLD		43.10	45.90	1.5	1.5	2	8.88	13.22	1.00	0.85
ELECTRIC PWR EQMT OP	ALL	ALL		50.50	55.50	1.5	1.5	2	11.69	16.69	0.00	3.12
ELECTRIC PWR GRNDMAN	ALL	ALL		39.39	55.50	1.5	1.5	2	9.12	13.02	0.00	2.43
ELECTRIC PWR LINEMAN	ALL	ALL		50.50	55.50	1.5	1.5	2	11.69	16.69	0.00	3.12
ELECTRICIAN	ALL	ALL		47.40	50.40	1.5	1.5	2	14.33	16.10	1.00	1.18
ELEVATOR CONSTRUCTOR	ALL	BLD		51.94	58.43	2	2	2	14.43	14.96	4.16	0.90
FENCE ERECTOR	ALL	ALL		39.58	41.58	1.5	1.5	2	13.40	13.90	0.00	0.40
GLAZIER	ALL	BLD		42.45	43.95	1.5	1.5	2	14.04	20.14	0.00	0.94
HT/FROST INSULATOR	ALL	BLD		50.50	53.00	1.5	1.5	2	12.12	12.96	0.00	0.72
IRON WORKER	ALL	ALL		47.33	49.33	2	2	2	14.15	22.39	0.00	0.35
LABORER	ALL	ALL		41.20	41.95	1.5	1.5	2	14.65	12.32	0.00	0.50
LATHER	ALL	ALL		46.35	48.35	1.5	1.5	2	11.79	18.87	0.00	0.63
MACHINIST	ALL	BLD		46.35	48.85	1.5	1.5	2	7.05	8.95	1.85	1.32
MARBLE FINISHERS	ALL	ALL		33.95	33.95	1.5	1.5	2	10.45	15.52	0.00	0.47
MARBLE MASON	ALL	BLD		44.63	49.09	1.5	1.5	2	10.45	16.28	0.00	0.59
MATERIAL TESTER I	ALL	ALL		31.20	31.20	1.5	1.5	2	14.65	12.32	0.00	0.50
MATERIALS TESTER II	ALL	ALL		36.20	36.20	1.5	1.5	2	14.65	12.32	0.00	0.50
MILLWRIGHT	ALL	ALL		46.35	48.35	1.5	1.5	2	11.79	18.87	0.00	0.63

OPERATING ENGINEER	ALL	BLD	1	50.10	54.10	2	2	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	BLD	2	48.80	54.10	2	2	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	BLD	3	46.25	54.10	2	2	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	BLD	4	44.50	54.10	2	2	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	BLD	5	53.85	54.10	2	2	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	BLD	6	51.10	54.10	2	2	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	BLD	7	53.10	54.10	2	2	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	FLT	1	55.90	55.90	1.5	1.5	2	18.05	13.60	1.90	1.30
OPERATING ENGINEER	ALL	FLT	2	54.40	55.90	1.5	1.5	2	18.05	13.60	1.90	1.30
OPERATING ENGINEER	ALL	FLT	3	48.40	55.90	1.5	1.5	2	18.05	13.60	1.90	1.30
OPERATING ENGINEER	ALL	FLT	4	40.25	55.90	1.5	1.5	2	18.05	13.60	1.90	1.30
OPERATING ENGINEER	ALL	FLT	5	57.40	55.90	1.5	1.5	2	18.05	13.60	1.90	1.30
OPERATING ENGINEER	ALL	FLT	6	38.00	55.90	1.5	1.5	2	18.05	13.60	1.90	1.30
OPERATING ENGINEER	ALL	HWY	1	48.30	52.30	1.5	1.5	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	HWY	2	47.75	52.30	1.5	1.5	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	HWY	3	45.70	52.30	1.5	1.5	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	HWY	4	44.30	52.30	1.5	1.5	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	HWY	5	43.10	52.30	1.5	1.5	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	HWY	6	51.30	52.30	1.5	1.5	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	HWY	7	49.30	52.30	1.5	1.5	2	18.80	14.35	2.00	1.30
ORNAMNTL IRON WORKER	ALL	ALL		46.75	49.25	2	2	2	13.90	19.79	0.00	0.75
PAINTER	ALL	ALL		45.55	51.24	1.5	1.5	1.5	11.56	11.44	0.00	1.87
PAINTER SIGNS	ALL	BLD		37.45	42.05	1.5	1.5	2	2.60	3.18	0.00	0.00
PILEDRIVER	ALL	ALL		46.35	48.35	1.5	1.5	2	11.79	18.87	0.00	0.63
PIPEFITTER	ALL	BLD		47.50	50.50	1.5	1.5	2	10.05	17.85	0.00	2.12
PLASTERER	ALL	BLD		42.75	45.31	1.5	1.5	2	14.00	15.71	0.00	0.89
PLUMBER	ALL	BLD		49.25	52.20	1.5	1.5	2	14.34	13.35	0.00	1.28
ROOFER	ALL	BLD		42.30	45.30	1.5	1.5	2	9.08	12.14	0.00	0.58
SHEETMETAL WORKER	ALL	BLD		43.50	46.98	1.5	1.5	2	11.03	23.43	0.00	0.78
SIGN HANGER	ALL	BLD		31.31	33.81	1.5	1.5	2	4.85	3.28	0.00	0.00

SPRINKLER FITTER	ALL	BLD		47.20	49.20	1.5	1.5	2	12.25	11.55	0.00	0.55
STEEL ERECTOR	ALL	ALL		42.07	44.07	2	2	2	13.45	19.59	0.00	0.35
STONE MASON	ALL	BLD		45.38	49.92	1.5	1.5	2	10.45	16.68	0.00	0.90
TERRAZZO FINISHER	ALL	BLD		40.54	40.54	1.5	1.5	2	10.65	12.76	0.00	0.73
TERRAZZO MASON	ALL	BLD		44.38	47.88	1.5	1.5	2	10.65	14.15	0.00	0.82
TILE MASON	ALL	BLD		45.49	49.49	1.5	1.5	2	10.65	13.88	0.00	0.86
TRAFFIC SAFETY WRKR	ALL	HWY		33.50	35.85	1.5	1.5	2	6.00	7.25	0.00	0.50
TRUCK DRIVER	E	ALL	1	35.60	36.25	1.5	1.5	2	8.56	11.50	0.00	0.15
TRUCK DRIVER	E	ALL	2	35.85	36.25	1.5	1.5	2	8.56	11.50	0.00	0.15
TRUCK DRIVER	E	ALL	3	36.05	36.25	1.5	1.5	2	8.56	11.50	0.00	0.15
TRUCK DRIVER	E	ALL	4	36.25	36.25	1.5	1.5	2	8.56	11.50	0.00	0.15
TRUCK DRIVER	W	ALL	1	35.98	36.53	1.5	1.5	2	8.25	10.14	0.00	0.15
TRUCK DRIVER	W	ALL	2	36.13	36.53	1.5	1.5	2	8.25	10.14	0.00	0.15
TRUCK DRIVER	W	ALL	3	36.33	36.53	1.5	1.5	2	8.25	10.14	0.00	0.15
TRUCK DRIVER	W	ALL	4	36.53	36.53	1.5	1.5	2	8.25	10.14	0.00	0.15
TUCKPOINTER	ALL	BLD		45.42	46.42	1.5	1.5	2	8.32	15.42	0.00	0.80

Legend

M-F OT Unless otherwise noted, OT pay is required for any hour greater than 8 worked each day, Mon through Fri. The number listed is the multiple of the base wage.

OSA Overtime pay required for every hour worked on Saturdays

OSH Overtime pay required for every hour worked on Sundays and Holidays

H/W Health/Welfare benefit

Explanations COOK COUNTY

The following list is considered as those days for which holiday rates of wages for work performed apply: New Years Day, Memorial Day, Fourth of July, Labor Day, Thanksgiving Day, Christmas Day and Veterans Day in some classifications/counties. Generally, any of these holidays which fall on a Sunday is celebrated on the following Monday. This then makes work performed on that Monday payable at the appropriate overtime rate for holiday pay. Common practice in a given local may alter certain days of celebration. If in doubt, please check with IDOL.

TRUCK DRIVERS (WEST) - That part of the county West of Barrington Road.

EXPLANATION OF CLASSES

ASBESTOS - GENERAL - removal of asbestos material/mold and hazardous materials from any place in a building, including mechanical systems where those mechanical systems are to be removed. This includes the removal of asbestos materials/mold and hazardous materials from ductwork or pipes in a building when the building is to be demolished at the time or at some close future date. ASBESTOS - MECHANICAL - removal of asbestos material from mechanical systems, such as pipes, ducts, and boilers, where the mechanical systems are to remain.

CERAMIC TILE FINISHER

The grouting, cleaning, and polishing of all classes of tile, whether for interior or exterior purposes, all burned, glazed or unglazed products; all composition materials, granite tiles, warning detectable tiles, cement tiles, epoxy composite materials, pavers, glass, mosaics, fiberglass, and all substitute materials, for tile made in tile-like units; all mixtures in tile like form of cement, metals, and other materials that are for and intended for use as a finished floor surface, stair treads, promenade roofs, walks, walls, ceilings, swimming pools, and all other places where tile is to form a finished interior or exterior. The mixing of all setting mortars including but not limited to thin-set mortars, epoxies, wall mud, and any other sand and cement mixtures or adhesives when used in the preparation, installation, repair, or maintenance of tile and/or similar materials. The handling and unloading of all sand, cement, lime, tile, fixtures, equipment, adhesives, or any other materials to be used in the preparation, installation, repair, or maintenance of tile and/or similar materials. Ceramic Tile Finishers shall fill all joints and voids regardless of method on all tile work, particularly and especially after installation of said tile work. Application of any and all protective coverings to all types of tile installations including, but not be limited to, all soap compounds, paper products, tapes, and all polyethylene coverings, plywood, masonite, cardboard, and any new type of products that may be used to protect tile installations, Blastrac equipment, and all floor scarifying equipment used in preparing floors to receive tile. The clean up and removal of all waste and materials. All demolition of existing tile floors and walls to be re-tiled.

COMMUNICATIONS ELECTRICIAN

Installation, operation, inspection, maintenance, repair and service of radio, television, recording, voice sound vision production and reproduction, telephone and telephone interconnect, facsimile, data apparatus, coaxial, fibre optic and wireless equipment, appliances and systems used for the transmission and reception of signals of any nature, business, domestic, commercial, education, entertainment, and residential purposes, including but not limited to, communication and telephone, electronic and sound equipment, fibre optic and data communication systems, and the performance of any task directly related to such installation or service whether at new or existing sites, such tasks to include the placing of wire and cable and electrical power conduit or other raceway work within the equipment room and pulling wire and/or cable through conduit and the installation of any incidental conduit, such that the employees covered hereby can complete any job in full.

MARBLE FINISHER

Loading and unloading trucks, distribution of all materials (all stone, sand, etc.), stocking of floors with material, performing all rigging for heavy work, the handling of all material that may be needed for the installation of such materials, building of scaffolding, polishing if needed, patching, waxing of material if damaged, pointing up, caulking, grouting and cleaning of marble, holding water on diamond or Carborundum blade or saw for setters cutting, use of tub saw or any other saw needed for preparation of material, drilling of holes for wires that anchor material set by setters, mixing up of molding plaster for installation of material, mixing up thin set for the installation of material, mixing up of sand to cement for the installation of material and such other work as may be required in helping a Marble Setter in the handling of all material in the erection or installation of interior marble, slate, travertine, art marble, serpentine, alberene stone, blue stone, granite and other stones (meaning as to stone any foreign or domestic materials as are specified and used in building interiors and exteriors and customarily known as stone in the trade), carrara, sanionyx, vitrolite and similar opaque glass and the laying of all marble tile, terrazzo tile, slate tile and precast tile, steps, risers treads, base, or any other materials that may be used as substitutes for any of the aforementioned materials and which are used on interior and exterior which are installed in a similar manner.

MATERIAL TESTER I: Hand coring and drilling for testing of materials; field inspection of uncured concrete and asphalt.

MATERIAL TESTER II: Field inspection of welds, structural steel, fireproofing, masonry, soil, facade, reinforcing steel, formwork, cured concrete, and concrete and asphalt batch plants; adjusting proportions of bituminous mixtures.

OPERATING ENGINEER - BUILDING

Class 1. Asphalt Plant; Asphalt Spreader; Autograde; Backhoes with Caisson Attachment; Batch Plant; Benoto (requires Two Engineers); Boiler and Throttle Valve; Caisson Rigs; Central Redi-Mix Plant; Combination Back Hoe Front End-loader Machine; Compressor and Throttle Valve; Concrete Breaker (Truck Mounted); Concrete Conveyor; Concrete Conveyor (Truck Mounted); Concrete Paver Over 27E cu. ft; Concrete Paver 27E cu. ft. and Under; Concrete Placer; Concrete Placing Boom; Concrete Pump (Truck Mounted); Concrete Tower; Cranes, All; Cranes, Hammerhead; Cranes, (GCI and similar Type); Creter Crane; Spider Crane; Crusher, Stone, etc.; Derricks, All; Derricks, Traveling; Formless Curb and Gutter Machine; Grader, Elevating; Grouting Machines; Heavy Duty Self-Propelled Transporter or Prime Mover; Highlift Shovels or Front Endloader 2-1/4 yd. and over; Hoists, Elevators, outside type rack and pinion and similar machines; Hoists, One, Two and Three Drum; Hoists, Two Tugger One Floor; Hydraulic Backhoes; Hydraulic Boom Trucks; Hydro Vac (and similar equipment); Locomotives, All; Motor Patrol; Lubrication Technician; Manipulators; Pile Drivers and Skid Rig; Post Hole Digger; Pre-Stress Machine; Pump Cretes Dual Ram; Pump Cretes: Squeeze Cretes-Screw Type Pumps; Gypsum Bulker and Pump; Raised and Blind Hole Drill; Roto Mill Grinder; Scoops - Tractor Drawn; Slip-Form Paver; Straddle Buggies; Operation of Tie Back Machine; Tournapull; Tractor with Boom and Side Boom; Trenching Machines.

Class 2. Boilers; Broom, All Power Propelled; Bulldozers; Concrete Mixer (Two Bag and Over); Conveyor, Portable; Forklift Trucks; Highlift Shovels or Front Endloaders under 2-1/4 yd.; Hoists, Automatic; Hoists, Inside Elevators; Hoists, Sewer Dragging Machine; Hoists, Tugger Single Drum;

Laser Screed; Rock Drill (Self-Propelled); Rock Drill (Truck Mounted); Rollers, All; Steam Generators; Tractors, All; Tractor Drawn Vibratory Roller; Winch Trucks with "A" Frame.

Class 3. Air Compressor; Combination Small Equipment Operator; Generators; Heaters, Mechanical; Hoists, Inside Elevators (remodeling or renovation work); Hydraulic Power Units (Pile Driving, Extracting, and Drilling); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Low Boys; Pumps, Well Points; Welding Machines (2 through 5); Winches, 4 Small Electric Drill Winches.

Class 4. Bobcats and/or other Skid Steer Loaders; Oilers; and Brick Forklift.

Class 5. Assistant Craft Foreman.

Class 6. Gradall.

Class 7. Mechanics; Welders.

OPERATING ENGINEERS - HIGHWAY CONSTRUCTION

Class 1. Asphalt Plant; Asphalt Heater and Planer Combination; Asphalt Heater Scarfire; Asphalt Spreader; Autograder/GOMACO or other similar type machines: ABG Paver; Backhoes with Caisson Attachment; Ballast Regulator; Belt Loader; Caisson Rigs; Car Dumper; Central Redi-Mix Plant; Combination Backhoe Front Endloader Machine, (1 cu. yd. Backhoe Bucket or over or with attachments); Concrete Breaker (Truck Mounted); Concrete Conveyor; Concrete Paver over 27E cu. ft.; Concrete Placer; Concrete Tube Float; Cranes, all attachments; Cranes, Tower Cranes of all types: Creter Crane; Spider Crane; Crusher, Stone, etc.; Derricks, All; Derrick Boats; Derricks, Traveling; Dredges; Elevators, Outside type Rack & Pinion and Similar Machines; Formless Curb and Gutter Machine; Grader, Elevating; Grader, Motor Grader, Motor Patrol, Auto Patrol, Form Grader, Pull Grader, Subgrader; Guard Rail Post Driver Truck Mounted; Hoists, One, Two and Three Drum; Heavy Duty Self-Propelled Transporter or Prime Mover; Hydraulic Backhoes; Backhoes with shear attachments up to 40' of boom reach; Lubrication Technician; Manipulators; Mucking Machine; Pile Drivers and Skid Rig; Pre-Stress Machine; Pump Cretes Dual Ram; Rock Drill - Crawler or Skid Rig; Rock Drill - Truck Mounted; Rock/Track Tamper; Roto Mill Grinder; Slip-Form Paver; Snow Melters; Soil Test Drill Rig (Truck Mounted); Straddle Buggies; Hydraulic Telescoping Form (Tunnel); Operation of Tieback Machine; Tractor Drawn Belt Loader; Tractor Drawn Belt Loader (with attached pusher - two engineers); Tractor with Boom; Tractaire with Attachments; Traffic Barrier Transfer Machine; Trenching; Truck Mounted Concrete Pump with Boom; Raised or Blind Hole Drills (Tunnel Shaft); Underground Boring and/or Mining Machines 5 ft. in diameter and over tunnel, etc; Underground Boring and/or Mining Machines under 5 ft. in diameter; Wheel Excavator; Widener (APSCO).

Class 2. Batch Plant; Bituminous Mixer; Boiler and Throttle Valve; Bulldozers; Car Loader Trailing Conveyors; Combination Backhoe Front Endloader Machine (Less than 1 cu. yd. Backhoe Bucket or over or with attachments); Compressor and Throttle Valve; Compressor, Common Receiver (3); Concrete Breaker or Hydro Hammer; Concrete Grinding Machine; Concrete Mixer or Paver 7S Series to and including 27 cu. ft.;

Concrete Spreader; Concrete Curing Machine, Burlap Machine, Belting Machine and Sealing Machine; Concrete Wheel Saw; Conveyor Muck Cars (Haglund or Similar Type); Drills, All; Finishing Machine - Concrete; Highlift Shovels or Front Endloader; Hoist - Sewer Dragging Machine; Hydraulic Boom Trucks (All Attachments); Hydro-Blaster; Hydro Excavating (excluding hose work); Laser Screed; All Locomotives, Dinky; Off-Road Hauling Units (including articulating) Non Self-Loading Ejection Dump; Pump Cretes: Squeeze Cretes - Screw Type Pumps, Gypsum Bulker and Pump; Roller, Asphalt; Rotary Snow Plows; Rototiller, Seaman, etc., self-propelled; Self-Propelled Compactor; Spreader - Chip - Stone, etc.; Scraper - Single/Twin Engine/Push and Pull; Scraper - Prime Mover in Tandem (Regardless of Size); Tractors pulling attachments, Sheeps Foot, Disc, Compactor, etc.; Tug Boats.

Class 3. Boilers; Brooms, All Power Propelled; Cement Supply Tender; Compressor, Common Receiver (2); Concrete Mixer (Two Bag and Over); Conveyor, Portable; Farm-Type Tractors Used for Mowing, Seeding, etc.; Forklift Trucks; Grouting Machine; Hoists, Automatic; Hoists, All Elevators; Hoists, Tugger Single Drum; Jeep Diggers; Low Boys; Pipe Jacking Machines; Post-Hole Digger; Power Saw, Concrete Power Driven; Pug Mills; Rollers, other than Asphalt; Seed and Straw Blower; Steam Generators; Stump Machine; Winch Trucks with "A" Frame; Work Boats; Tamper-Form-Motor Driven.

Class 4. Air Compressor; Combination - Small Equipment Operator; Directional Boring Machine; Generators; Heaters, Mechanical; Hydraulic Power Unit (Pile Driving, Extracting, or Drilling); Light Plants, All (1 through 5); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Vacuum Trucks (excluding hose work); Welding Machines (2 through 5); Winches, 4 Small Electric Drill Winches.

Class 5. SkidSteer Loader (all); Brick Forklifts; Oilers.

Class 6. Field Mechanics and Field Welders

Class 7. Dowell Machine with Air Compressor; Gradall and machines of like nature.

OPERATING ENGINEER - FLOATING

Class 1. Craft Foreman; Master Mechanic; Diver/Wet Tender; Engineer; Engineer (Hydraulic Dredge).

Class 2. Crane/Backhoe Operator; Boat Operator with towing endorsement; Mechanic/Welder; Assistant Engineer (Hydraulic Dredge); Leverman (Hydraulic Dredge); Diver Tender.

Class 3. Deck Equipment Operator, Machineryman, Maintenance of Crane (over 50 ton capacity) or Backhoe (115,000 lbs. or more); Tug/Launch Operator; Loader/Dozer and like equipment on Barge, Breakwater Wall, Slip/Dock, or Scow, Deck Machinery, etc.

Class 4. Deck Equipment Operator, Machineryman/Fireman (4 Equipment Units or More); Off Road Trucks; Deck Hand, Tug Engineer, Crane Maintenance (50 Ton Capacity and Under) or Backhoe Weighing (115,000 pounds or less); Assistant Tug Operator.

Class 5. Friction or Lattice Boom Cranes.

Class 6. ROV Pilot, ROV Tender

TERRAZZO FINISHER

The handling of sand, cement, marble chips, and all other materials that may be used by the Mosaic Terrazzo Mechanic, and the mixing, grinding, grouting, cleaning and sealing of all Marble, Mosaic, and Terrazzo work, floors, base, stairs, and wainscoting by hand or machine, and in addition, assisting and aiding Marble, Masonic, and Terrazzo Mechanics.

TRAFFIC SAFETY

Work associated with barricades, horses and drums used to reduce lane usage on highway work, the installation and removal of temporary lane markings, and the installation and removal of temporary road signs.

TRUCK DRIVER - BUILDING, HEAVY AND HIGHWAY CONSTRUCTION - EAST & WEST

Class 1. Two or three Axle Trucks. A-frame Truck when used for transportation purposes; Air Compressors and Welding Machines, including those pulled by cars, pick-up trucks and tractors; Ambulances; Batch Gate Lockers; Batch Hopperman; Car and Truck Washers; Carry-alls; Fork Lifts and Hoisters; Helpers; Mechanics Helpers and Greasers; Oil Distributors 2-man operation; Pavement Breakers; Pole Trailer, up to 40 feet; Power Mower Tractors; Self-propelled Chip Spreader; Skipman; Slurry Trucks, 2-man operation; Slurry Truck Conveyor Operation, 2 or 3 man; Teamsters; Unskilled Dumpman; and Truck Drivers hauling warning lights, barricades, and portable toilets on the job site.

Class 2. Four axle trucks; Dump Crets and Adgetors under 7 yards; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnapulls or Turnatrailers when pulling other than self-loading equipment or similar equipment under 16 cubic yards; Mixer Trucks under 7 yards; Ready-mix Plant Hopper Operator, and Winch Trucks, 2 Axles.

Class 3. Five axle trucks; Dump Crets and Adgetors 7 yards and over; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnatrailers or turnapulls when pulling other than self-loading equipment or similar equipment over 16 cubic yards; Explosives and/or Fission Material Trucks; Mixer Trucks 7 yards or over; Mobile Cranes while in transit; Oil Distributors, 1-man operation; Pole Trailer, over 40 feet; Pole and Expandable Trailers hauling material over 50 feet long; Slurry trucks, 1-man operation; Winch trucks, 3 axles or more; Mechanic--Truck Welder and Truck Painter.

Class 4. Six axle trucks; Dual-purpose vehicles, such as mounted crane trucks with hoist and accessories; Foreman; Master Mechanic; Self-loading equipment like P.B. and trucks with scoops on the front.

Other Classifications of Work:

For definitions of classifications not otherwise set out, the Department generally has on file such definitions which are available. If a task to be performed is not subject to one of the classifications of pay set out, the Department will upon being contacted state which neighboring county has such a classification and provide such rate, such rate being deemed to exist by reference in this document. If no neighboring county rate applies to the task, the Department shall undertake a special determination, such special determination being then deemed to have existed under this determination. If a project requires these, or any classification not listed, please contact IDOL at 217-782-1710 for wage rates or clarifications.

LANDSCAPING

Landscaping work falls under the existing classifications for laborer, operating engineer and truck driver. The work performed by landscape plantsman and landscape laborer is covered by the existing classification of laborer. The work performed by landscape operators (regardless of equipment used or its size) is covered by the classifications of operating engineer. The work performed by landscape truck drivers (regardless of size of truck driven) is covered by the classifications of truck driver.

MATERIAL TESTER & MATERIAL TESTER/INSPECTOR I AND II

Notwithstanding the difference in the classification title, the classification entitled "Material Tester I" involves the same job duties as the classification entitled "Material Tester/Inspector I". Likewise, the classification entitled "Material Tester II" involves the same job duties as the classification entitled "Material Tester/Inspector II".

**Prevailing Wage rates for
Will County effective
Sept. 1, 2017**

Trade Title	Region	Type	Class	Base Wage	Fore-man Wage	M-F OT	OSA	OSH	H/W	Pension	Vacation	Training
ASBESTOS ABT-GEN	ALL	ALL		41.20	42.20	1.5	1.5	2	14.65	12.32	0.00	0.50
ASBESTOS ABT-MEC	ALL	BLD		37.88	40.38	1.5	1.5	2	12.12	11.70	0.00	0.72
BOILERMAKER	ALL	BLD		48.49	52.86	2	2	2	6.97	19.61	0.00	0.90
BRICK MASON	ALL	BLD		45.38	49.92	1.5	1.5	2	10.45	16.68	0.00	0.90
CARPENTER	ALL	ALL		46.35	50.99	2	2	2	11.99	20.95	0.00	0.63
CEMENT MASON	ALL	ALL		42.00	44.00	2	1.5	2	10.00	23.97	0.00	0.50
CERAMIC TILE FNShER	ALL	BLD		38.56	38.56	1.5	1.5	2	10.65	11.18	0.00	0.68
COMMUNICATION TECH	ALL	BLD		34.50	36.00	1.5	1.5	2	14.62	12.69	1.50	0.72
ELECTRIC PWR EQMT OP	ALL	ALL		50.50	55.50	1.5	1.5	2	11.69	16.69	0.00	3.12
ELECTRIC PWR GRNDMAN	ALL	ALL		39.39	55.50	1.5	1.5	2	9.12	13.02	0.00	2.43
ELECTRIC PWR LINEMAN	ALL	ALL		50.50	55.50	1.5	1.5	2	11.69	16.69	0.00	3.12
ELECTRICIAN	ALL	BLD		42.50	46.33	1.5	1.5	2	15.47	17.44	3.50	1.20
ELEVATOR CONSTRUCTOR	ALL	BLD		51.94	58.43	2	2	2	14.43	14.96	4.16	0.90
GLAZIER	ALL	BLD		42.45	43.95	1.5	1.5	2	14.04	20.14	0.00	0.94
HT/FROST INSULATOR	ALL	BLD		50.50	53.00	1.5	1.5	2	12.12	12.96	0.00	0.72
IRON WORKER	ALL	ALL		42.50	46.75	2	2	2	11.26	24.59	0.00	0.85
LABORER	ALL	ALL		41.20	41.95	1.5	1.5	2	14.65	12.32	0.00	0.50
LATHER	ALL	ALL		46.35	50.99	2	2	2	11.99	20.95	0.00	0.63
MACHINIST	ALL	BLD		45.35	47.85	1.5	1.5	2	7.26	8.95	1.85	0.00
MARBLE FINISHERS	ALL	ALL		33.95	33.95	1.5	1.5	2	10.45	15.52	0.00	0.47
MARBLE MASON	ALL	BLD		44.63	49.09	1.5	1.5	2	10.45	16.28	0.00	0.59
MATERIAL TESTER I	ALL	ALL		31.20	31.20	1.5	1.5	2	14.65	12.32	0.00	0.50
MATERIALS TESTER II	ALL	ALL		36.20	36.20	1.5	1.5	2	14.65	12.32	0.00	0.50

MILLWRIGHT	ALL	ALL		46.35	50.99	2	2	2	11.99	20.95	0.00	0.63
OPERATING ENGINEER	ALL	BLD	1	50.10	54.10	2	2	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	BLD	2	48.80	54.10	2	2	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	BLD	3	46.25	54.10	2	2	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	BLD	4	44.50	54.10	2	2	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	BLD	5	53.85	54.10	2	2	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	BLD	6	51.10	54.10	2	2	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	BLD	7	53.10	54.10	2	2	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	FLT	1	55.90	55.90	1.5	1.5	2	18.05	13.60	1.90	1.30
OPERATING ENGINEER	ALL	FLT	2	54.40	55.90	1.5	1.5	2	18.05	13.60	1.90	1.30
OPERATING ENGINEER	ALL	FLT	3	48.40	55.90	1.5	1.5	2	18.05	13.60	1.90	1.30
OPERATING ENGINEER	ALL	FLT	4	40.25	55.90	1.5	1.5	2	18.05	13.60	1.90	1.30
OPERATING ENGINEER	ALL	FLT	5	57.40	55.90	1.5	1.5	2	18.05	13.60	1.90	1.30
OPERATING ENGINEER	ALL	FLT	6	38.00	55.90	1.5	1.5	2	18.05	13.60	1.90	1.30
OPERATING ENGINEER	ALL	HWY	1	48.30	52.30	1.5	1.5	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	HWY	2	47.75	52.30	1.5	1.5	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	HWY	3	45.70	52.30	1.5	1.5	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	HWY	4	44.30	52.30	1.5	1.5	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	HWY	5	43.10	52.30	1.5	1.5	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	HWY	6	51.30	52.30	1.5	1.5	2	18.80	14.35	2.00	1.30
OPERATING ENGINEER	ALL	HWY	7	49.30	52.30	1.5	1.5	2	18.80	14.35	2.00	1.30
PAINTER	ALL	ALL		45.55	51.24	1.5	1.5	1.5	11.56	11.44	0.00	1.87
PAINTER SIGNS	ALL	BLD		37.45	42.05	1.5	1.5	2	2.60	3.18	0.00	0.00
PILEDRIVER	ALL	ALL		46.35	50.99	2	2	2	11.99	20.95	0.00	0.63
PIPEFITTER	ALL	BLD		47.50	50.50	1.5	1.5	2	10.05	17.85	0.00	
PLASTERER	ALL	BLD		42.75	45.31	1.5	1.5	2	14.00	15.71	0.00	0.89
PLUMBER	ALL	BLD		49.25	52.20	1.5	1.5	2	14.34	13.35	0.00	1.28
ROOFER	ALL	BLD		42.30	45.30	1.5	1.5	2	9.08	12.14	0.00	0.58
SHEETMETAL WORKER	ALL	BLD		45.77	47.77	1.5	1.5	2	10.65	14.10	0.00	0.82
SPRINKLER FITTER	ALL	BLD		47.20	49.20	1.5	1.5	2	12.25	11.55	0.00	0.55
STONE MASON	ALL	BLD		45.38	49.92	1.5	1.5	2	10.45	16.68	0.00	0.90

TERRAZZO FINISHER	ALL	BLD		40.54	40.54	1.5	1.5	2	10.65	12.76	0.00	0.73
TERRAZZO MASON	ALL	BLD		44.38	47.88	1.5	1.5	2	10.65	14.15	0.00	0.82
TILE MASON	ALL	BLD		45.49	49.49	1.5	1.5	2	10.65	13.88	0.00	0.86
TRAFFIC SAFETY WRKR	ALL	HWY		33.50	35.10	1.5	1.5	2	8.25	5.50	0.00	0.25
TRUCK DRIVER	ALL	ALL	1	37.91	38.46	1.5	1.5	2	8.10	7.97	0.00	0.15
TRUCK DRIVER	ALL	ALL	2	38.06	38.46	1.5	1.5	2	8.10	7.97	0.00	0.15
TRUCK DRIVER	ALL	ALL	3	38.26	38.46	1.5	1.5	2	8.10	7.97	0.00	0.15
TRUCK DRIVER	ALL	ALL	4	38.46	38.46	1.5	1.5	2	8.10	7.97	0.00	0.15
TUCKPOINTER	ALL	BLD		45.42	46.42	1.5	1.5	2	8.32	15.42	0.00	0.80

Legend

M-F OT Unless otherwise noted, OT pay is required for any hour greater than 8 worked each day, Mon through Fri. The number listed is the multiple of the base wage.

OSA Overtime pay required for every hour worked on Saturdays

OSH Overtime pay required for every hour worked on Sundays and Holidays

H/W Health/Welfare benefit

Explanations WILL COUNTY

The following list is considered as those days for which holiday rates of wages for work performed apply: New Years Day, Memorial Day, Fourth of July, Labor Day, Thanksgiving Day, Christmas Day and Veterans Day in some classifications/counties. Generally, any of these holidays which fall on a Sunday is celebrated on the following Monday. This then makes work performed on that Monday payable at the appropriate overtime rate for holiday pay. Common practice in a given local may alter certain days of celebration. If in doubt, please check with IDOL.

EXPLANATION OF CLASSES

ASBESTOS - GENERAL - removal of asbestos material/mold and hazardous materials from any place in a building, including mechanical systems where those mechanical systems are to be removed. This includes the removal of asbestos materials/mold and hazardous materials from ductwork or pipes in a building when the building is to be demolished at the time or at some close future date.

ASBESTOS - MECHANICAL - removal of asbestos material from mechanical systems, such as pipes, ducts, and boilers, where the mechanical systems are to remain.

CERAMIC TILE FINISHER

The grouting, cleaning, and polishing of all classes of tile, whether for interior or exterior purposes, all burned, glazed or unglazed products; all composition materials, granite tiles, warning detectable tiles, cement tiles, epoxy composite materials, pavers, glass, mosaics, fiberglass, and all substitute materials, for tile made in tile-like units; all mixtures in tile like form of cement, metals, and other materials that are for and intended for use as a finished floor surface, stair treads, promenade roofs, walks, walls, ceilings, swimming pools, and all other places where tile is to form a finished interior or exterior. The mixing of all setting mortars including but not limited to thin-set mortars, epoxies, wall mud, and any other sand and cement mixtures or adhesives when used in the preparation, installation, repair, or maintenance of tile and/or similar materials. The handling and unloading of all sand, cement, lime, tile, fixtures, equipment, adhesives, or any other materials to be used in the preparation, installation, repair, or maintenance of tile and/or similar materials. Ceramic Tile Finishers shall fill all joints and voids regardless of method on all tile work, particularly and especially after installation of said tile work. Application of any and all protective coverings to all types of tile installations including, but not be limited to, all soap compounds, paper products, tapes, and all polyethylene coverings, plywood, masonite, cardboard, and any new type of products that may be used to protect tile installations, Blastrac equipment, and all floor scarifying equipment used in preparing floors to receive tile. The clean up and removal of all waste and materials. All demolition of existing tile floors and walls to be re-tiled.

COMMUNICATIONS TECHNICIAN

Installation, operation, inspection, maintenance, repair and service of radio, television, recording, voice, sound and vision production and reproduction, telephone and telephone interconnect, facsimile, equipment and appliances used for domestic, commercial, educational and entertainment purposes, pulling of wire through conduit but not the installation of conduit.

MARBLE FINISHER

Loading and unloading trucks, distribution of all materials (all stone, sand, etc.), stocking of floors with material, performing all rigging for heavy work, the handling of all material that may be needed for the installation of such materials, building of scaffolding, polishing if needed, patching, waxing of material if damaged, pointing up, caulking, grouting and cleaning of marble, holding water on diamond or Carborundum blade or saw for setters cutting, use of tub saw or any other saw needed for preparation of material, drilling of holes for wires that anchor material set by setters, mixing up of molding plaster for installation of material, mixing up thin set for the installation of material, mixing up of sand to cement for the installation of material and such other work as may be required in helping a Marble Setter in the handling of all material in the erection or installation of interior marble, slate, travertine, art marble, serpentine, alberene stone, blue stone, granite and other stones (meaning as to stone any foreign or domestic materials as are specified and used in building interiors and exteriors and customarily known as stone in the trade), carrara, sanionyx, vitrolite and similar opaque glass and the laying of all marble tile, terrazzo tile, slate tile and precast tile, steps, risers treads, base, or any other materials that may be used as substitutes for any of the aforementioned materials and which are used on interior and exterior which are installed in a similar manner.

MATERIAL TESTER I: Hand coring and drilling for testing of materials; field inspection of uncured concrete and asphalt.

MATERIAL TESTER II: Field inspection of welds, structural steel, fireproofing, masonry, soil, facade, reinforcing steel, formwork, cured concrete, and concrete and asphalt batch plants; adjusting proportions of bituminous mixtures.

OPERATING ENGINEER - BUILDING

Class 1. Asphalt Plant; Asphalt Spreader; Autograde; Backhoes with Caisson Attachment; Batch Plant; Benoto (requires Two Engineers); Boiler and Throttle Valve; Caisson Rigs; Central Redi-Mix Plant; Combination Back Hoe Front End-loader Machine; Compressor and Throttle Valve; Concrete Breaker (Truck Mounted); Concrete Conveyor; Concrete Conveyor (Truck Mounted); Concrete Paver Over 27E cu. ft; Concrete Paver 27E cu. ft. and Under; Concrete Placer; Concrete Placing Boom; Concrete Pump (Truck Mounted); Concrete Tower; Cranes, All; Cranes, Hammerhead; Cranes, (GCI and similar Type); Creter Crane; Spider Crane; Crusher, Stone, etc.; Derricks, All; Derricks, Traveling; Formless Curb and Gutter Machine; Grader, Elevating; Grouting Machines; Heavy Duty Self-Propelled Transporter or Prime Mover; Highlift Shovels or Front Endloader 2-1/4 yd. and over; Hoists, Elevators, outside type rack and pinion and similar machines; Hoists, One, Two and Three Drum; Hoists, Two Tugger One Floor; Hydraulic Backhoes; Hydraulic Boom Trucks; Hydro Vac (and similar equipment); Locomotives, All; Motor Patrol; Lubrication Technician; Manipulators; Pile Drivers and Skid Rig; Post Hole Digger; Pre-Stress Machine; Pump Cretes Dual Ram; Pump Cretes: Squeeze Cretes-Screw Type Pumps; Gypsum Bulker and Pump; Raised and Blind Hole Drill; Roto Mill Grinder; Scoops - Tractor Drawn; Slip-Form Paver; Straddle Buggies; Operation of Tie Back Machine; Tournapull; Tractor with Boom and Side Boom; Trenching Machines.

Class 2. Boilers; Broom, All Power Propelled; Bulldozers; Concrete Mixer (Two Bag and Over); Conveyor, Portable; Forklift Trucks; Highlift Shovels or Front Endloaders under 2-1/4 yd.; Hoists, Automatic; Hoists, Inside Elevators; Hoists, Sewer Dragging Machine; Hoists, Tugger Single Drum; Laser Screed; Rock Drill (Self-Propelled); Rock Drill (Truck Mounted); Rollers, All; Steam Generators; Tractors, All; Tractor Drawn Vibratory Roller; Winch Trucks with "A" Frame.

Class 3. Air Compressor; Combination Small Equipment Operator; Generators; Heaters, Mechanical; Hoists, Inside Elevators (remodeling or renovation work); Hydraulic Power Units (Pile Driving, Extracting, and Drilling); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Low Boys; Pumps, Well Points; Welding Machines (2 through 5); Winches, 4 Small Electric Drill Winches.

Class 4. Bobcats and/or other Skid Steer Loaders; Oilers; and Brick Forklift.

Class 5. Assistant Craft Foreman.

Class 6. Gradall.

Class 7. Mechanics; Welders.

OPERATING ENGINEERS - HIGHWAY CONSTRUCTION

Class 1. Asphalt Plant; Asphalt Heater and Planer Combination; Asphalt Heater Scarfire; Asphalt Spreader; Autograder/GOMACO or other similar type machines; ABG Paver; Backhoes with Caisson Attachment; Ballast Regulator; Belt Loader; Caisson Rigs; Car Dumper; Central Redi-Mix Plant; Combination Backhoe Front Endloader Machine, (1 cu. yd. Backhoe Bucket or over or with attachments); Concrete Breaker (Truck Mounted); Concrete Conveyor; Concrete Paver over 27E cu. ft.; Concrete Placer; Concrete Tube Float; Cranes, all attachments; Cranes, Tower Cranes of all types: Creter Crane; Spider Crane; Crusher, Stone, etc.; Derricks, All; Derrick Boats; Derricks, Traveling; Dredges; Elevators, Outside type Rack & Pinion and Similar Machines; Formless Curb and Gutter Machine; Grader, Elevating; Grader, Motor Grader, Motor Patrol, Auto Patrol, Form Grader, Pull Grader, Subgrader; Guard Rail Post Driver Truck Mounted; Hoists, One, Two and Three Drum; Heavy Duty Self-Propelled Transporter or Prime Mover; Hydraulic Backhoes; Backhoes with shear attachments up to 40' of boom reach; Lubrication Technician; Manipulators; Mucking Machine; Pile Drivers and Skid Rig; Pre-Stress Machine; Pump Cretes Dual Ram; Rock Drill - Crawler or Skid Rig; Rock Drill - Truck Mounted; Rock/Track Tamper; Roto Mill Grinder; Slip-Form Paver; Snow Melters; Soil Test Drill Rig (Truck Mounted); Straddle Buggies; Hydraulic Telescoping Form (Tunnel); Operation of Tieback Machine; Tractor Drawn Belt Loader; Tractor Drawn Belt Loader (with attached pusher - two engineers); Tractor with Boom; Tractaire with Attachments; Traffic Barrier Transfer Machine; Trenching; Truck Mounted Concrete Pump with

Boom; Raised or Blind Hole Drills (Tunnel Shaft); Underground Boring and/or Mining Machines 5 ft. in diameter and over tunnel, etc; Underground Boring and/or Mining Machines under 5 ft. in diameter; Wheel Excavator; Widener (APSCO).

Class 2. Batch Plant; Bituminous Mixer; Boiler and Throttle Valve; Bulldozers; Car Loader Trailing Conveyors; Combination Backhoe Front Endloader Machine (Less than 1 cu. yd. Backhoe Bucket or over or with attachments); Compressor and Throttle Valve; Compressor, Common Receiver (3); Concrete Breaker or Hydro Hammer; Concrete Grinding Machine; Concrete Mixer or Paver 7S Series to and including 27 cu. ft.; Concrete Spreader; Concrete Curing Machine, Burlap Machine, Belting Machine and Sealing Machine; Concrete Wheel Saw; Conveyor Muck Cars (Haglund or Similar Type); Drills, All; Finishing Machine - Concrete; Highlift Shovels or Front Endloader; Hoist - Sewer Dragging Machine; Hydraulic Boom Trucks (All Attachments); Hydro-Blaster; Hydro Excavating (excluding hose work); Laser Screed; All Locomotives, Dinky; Off-Road Hauling Units (including articulating) Non Self-Loading Ejection Dump; Pump Cretes: Squeeze Cretes - Screw Type Pumps, Gypsum Bulker and Pump; Roller, Asphalt; Rotary Snow Plows; Rototiller, Seaman, etc., self-propelled; Self-Propelled Compactor; Spreader - Chip - Stone, etc.; Scraper - Single/Twin Engine/Push and Pull; Scraper - Prime Mover in Tandem (Regardless of Size); Tractors pulling attachments, Sheeps Foot, Disc, Compactor, etc.; Tug Boats.

Class 3. Boilers; Brooms, All Power Propelled; Cement Supply Tender; Compressor, Common Receiver (2); Concrete Mixer (Two Bag and Over); Conveyor, Portable; Farm-Type Tractors Used for Mowing, Seeding, etc.; Forklift Trucks; Grouting Machine; Hoists, Automatic; Hoists, All Elevators; Hoists, Tugger Single Drum; Jeep Diggers; Low Boys; Pipe Jacking Machines; Post-Hole Digger; Power Saw, Concrete Power Driven; Pug Mills; Rollers, other than Asphalt; Seed and Straw Blower; Steam Generators; Stump Machine; Winch Trucks with "A" Frame; Work Boats; Tamper-Form-Motor Driven.

Class 4. Air Compressor; Combination - Small Equipment Operator; Directional Boring Machine; Generators; Heaters, Mechanical; Hydraulic Power Unit (Pile Driving, Extracting, or Drilling); Light Plants, All (1 through 5); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Vacuum Trucks (excluding hose work); Welding Machines (2 through 5); Winches, 4 Small Electric Drill Winches.

Class 5. SkidSteer Loader (all); Brick Forklifts; Oilers.

Class 6. Field Mechanics and Field Welders

Class 7. Dowell Machine with Air Compressor; Gradall and machines of like nature.

OPERATING ENGINEER - FLOATING

Class 1. Craft Foreman; Master Mechanic; Diver/Wet Tender; Engineer; Engineer (Hydraulic Dredge).

Class 2. Crane/Backhoe Operator; Boat Operator with towing endorsement; Mechanic/Welder; Assistant Engineer (Hydraulic Dredge); Leverman (Hydraulic Dredge); Diver Tender.

Class 3. Deck Equipment Operator, Machineryman, Maintenance of Crane (over 50 ton capacity) or Backhoe (115,000 lbs. or more); Tug/Launch Operator; Loader/Dozer and like equipment on Barge, Breakwater Wall, Slip/Dock, or Scow, Deck Machinery, etc.

Class 4. Deck Equipment Operator, Machineryman/Fireman (4 Equipment Units or More); Off Road Trucks; Deck Hand, Tug Engineer, Crane Maintenance (50 Ton Capacity and Under) or Backhoe Weighing (115,000 pounds or less); Assistant Tug Operator.

Class 5. Friction or Lattice Boom Cranes.

Class 6. ROV Pilot, ROV Tender

TRAFFIC SAFETY - work associated with barricades, horses and drums used to reduce lane usage on highway work, the installation and removal of temporary lane markings, and the installation and removal of temporary road signs.

TRUCK DRIVER - BUILDING, HEAVY AND HIGHWAY CONSTRUCTION

Class 1. Two or three Axle Trucks. A-frame Truck when used for transportation purposes; Air Compressors and Welding Machines, including those pulled by cars, pick-up trucks and tractors; Ambulances; Batch Gate Lockers; Batch Hopperman; Car and Truck Washers; Carry-alls; Fork Lifts and Hoisters; Helpers; Mechanics Helpers and Greasers; Oil Distributors 2-man operation; Pavement Breakers; Pole Trailer, up to 40 feet; Power Mower Tractors; Self-propelled Chip Spreader; Skipman; Slurry Trucks, 2-man operation; Slurry Truck Conveyor Operation, 2 or 3 man; Teamsters; Unskilled Dumpman; and Truck Drivers hauling warning lights, barricades, and portable toilets on the job site.

Class 2. Four axle trucks; Dump Crets and Adgetors under 7 yards; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnapulls or Turnatrailers when pulling other than self-loading equipment or similar equipment under 16 cubic yards; Mixer Trucks under 7 yards; Ready-mix Plant Hopper Operator, and Winch Trucks, 2 Axles.

Class 3. Five axle trucks; Dump Crets and Adgetors 7 yards and over; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnatrailers or turnapulls when pulling other than self-loading equipment or similar equipment over 16 cubic yards; Explosives and/or Fission Material Trucks; Mixer Trucks 7 yards or over; Mobile Cranes while in transit; Oil Distributors, 1-man operation; Pole Trailer, over 40 feet; Pole and Expandable Trailers hauling material over 50 feet long; Slurry trucks, 1-man operation; Winch trucks, 3 axles or more; Mechanic--Truck Welder and Truck Painter.

Class 4. Six axle trucks; Dual-purpose vehicles, such as mounted crane trucks with hoist and accessories; Foreman; Master Mechanic; Self-loading equipment like P.B. and trucks with scoops on the front.

TERRAZZO FINISHER

The handling of sand, cement, marble chips, and all other materials that may be used by the Mosaic Terrazzo Mechanic, and the mixing, grinding, grouting, cleaning and sealing of all Marble, Mosaic, and Terrazzo work, floors, base, stairs, and wainscoting by hand or machine, and in addition, assisting and aiding Marble, Masonic, and Terrazzo Mechanics.

Other Classifications of Work:

For definitions of classifications not otherwise set out, the Department generally has on file such definitions which are available. If a task to be performed is not subject to one of the classifications of pay set out, the Department will upon being contacted state which neighboring county has such a classification and provide such rate, such rate being deemed to exist by reference in this document. If no neighboring county rate applies to the task, the Department shall undertake a special determination, such special determination being then deemed to have existed under this determination. If a project requires these, or any classification not listed, please contact IDOL at 217-782-1710 for wage rates or clarifications.

LANDSCAPING

Landscaping work falls under the existing classifications for laborer, operating engineer and truck driver. The work performed by landscape plantsman and landscape laborer is covered by the existing classification of laborer. The work performed by landscape operators (regardless of equipment used or its size) is covered by the classifications of operating engineer. The work performed by landscape truck drivers (regardless of size of truck driven) is covered by the classifications of truck driver.

MATERIAL TESTER & MATERIAL TESTER/INSPECTOR I AND II

Notwithstanding the difference in the classification title, the classification entitled "Material Tester I" involves the same job duties as the classification entitled "Material Tester/Inspector I". Likewise, the classification entitled "Material Tester II" involves the same job duties as the classification entitled "Material Tester/Inspector II".

Appendix A

GEOTECHNICAL REPORT



April 13, 2018

Miss. Jennifer Prinz
Director of Engineering
Robinson Engineering, Ltd.
17000 S. Park Avenue
South Holland, Illinois 60473

Re: Pavement Cores
Tinley Park Convention Center
18451 Convention Center Drive
Tinley Park, Illinois 60477
GEOCON Project No. 18-G0382

Dear Miss. Prinz,

In accordance with your request, GEOCON Professional Services, LLC (GEOCON) has completed pavement cores to determine the HMA pavement section at various locations indicated on Figure 2. This letter presents our core thickness measurements and the results of field DCP testing.

Five (5) pavement cores were collected at locations indicated on the attached Figure 2. The cores were advanced using conventional hot mixed asphalt (HMA) rotary coring equipment. During the coring operations, the thickness of the HMA pavement and aggregate base was recorded. Field DCP testing was performed of the subgrade below the aggregate base. Results of the DCP tests were converted to Immediate Bearing Values (IBVs), which are presented in the following table:

Core No.	HMA Pavement Thickness (in.)	Base Course Thickness (in.)	Immediate Bearing Value
B-01	3.5	8.5	4.2
B-02	3.5	10.0	4.8
B-03	3.5	10.0	11.5
B-04	4.0*	10.0	5.5
B-05	4.0*	10.0	9.9

**Core retrieved varies from asphalt thickness in place*

Upon completion of each pavement core, a soil sample was obtained via split-barrel sampling techniques in accordance with ASTM Procedure D-1586. All samples were visually classified by a geotechnical engineer according to the AASHTO Soil Classification System (AASHTO M-145). Representative samples were tested in the laboratory to determine the natural moisture content of the soils. All moisture contents are expressed as a percentage of the dry weight of soil. Representative samples of the cohesive soils encountered in the borings were tested in the laboratory with a calibrated RIMAC spring tester to determine the approximate unconfined compressive strength of the soil sample.


Tinley Park Convention Center Pavement Cores
Tinley Park, Illinois
GEOCON Project No. 18-G0382

A grainsize analysis of the aggregate base course was performed from a composite sample of each boring. The results are attached.

Should you have any questions regarding the enclosed information, or if we could be of any other assistance, please feel free to call us at (815) 806-9981. We appreciate the opportunity to be of service on this project.

Sincerely,

GEOCON PROFESSIONAL SERVICES, LLC



Jenna Kooy
Project Engineer E.I.T.



Kenneth K. Rippey, PE
Senior Geotechnical Engineer

Attachment: Figure 1 Site Vicinity Diagram
 Figure 2 Boring Location Map
 Soil Boring Logs
 General Notes
 Grainsize Analysis of Base Course
 Photograph Log




9370 Laraway Road, Suite D
Frankfort, IL 60423
P. 815.806.9986 F. 815.464.8691

FIGURE 1
SITE VICINITY MAP
Tinley Park Convention Center
18451 Convention Center Drive
Tinley Park, IL 60477

PROJECT NUMBER:
18-G0382

DATE: April 2018



9370 Laraway Road, Suite D
Frankfort, IL 60423
P. 815.806.9986 F. 815.464.8691

FIGURE 2
BORING LOCATION DIAGRAM
Tinley Park Convention Center
18451 Convention Center Drive
Tinley Park, IL 60477

PROJECT NUMBER: 18-G0382

DATE: April 2018



CLIENT Robinson Engineering, Ltd PROJECT NAME Tinley Park Convention Center
 PROJECT NUMBER 18-G0382 PROJECT LOCATION 18451 Convention Center Dr, Tinley Park, IL
 DATE COMPLETED 4/7/18 LOGGED BY NJ DRILLING METHOD 3.25 in. I.D. HSA

DEPTH (ft)	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	IBV VALUE	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	ATTERBERG LIMITS			
													LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0			0-3.5" ASPHALT PAVEMENT													
	691.7															
			3.5-12" AGGREGATE BASE													
1	691.0															
			mottled brown and gray LEAN CLAY trace sand very stiff, moist													
2				SS 1	56	4-4-4 (8)	4.2	3.0	2.5	18.0						
	689.5															

Bottom of borehole at 2.5 feet.

GPS PAVEMENT LOG - GPS STD DATA TEMPLATE.GDT - 4/16/18 09:48 - K:\GINT\PROJECTS\18-G0382 TINLEY PARK CONVENTION CENTER ILLINOIS-REL.GPJ

COMPLETION DEPTH 2.5 ft GROUND ELEVATION 692 ft
 CAVE DEPTH ft BACKFILL Soil Cuttings
 GROUND WATER LEVELS:
 AT TIME OF DRILLING --- None
 AT END OF DRILLING --- Dry upon completion
 AFTER DRILLING ---

NOTES

Lines of Demarcation represent an **approximate** boundary between soil types. Variations may occur between sampling intervals and between boring locations, and the transition may be gradual. Dashed lines are indicative of potentially erratic or unknown changes.



CLIENT Robinson Engineering, Ltd PROJECT NAME Tinley Park Convention Center
 PROJECT NUMBER 18-G0382 PROJECT LOCATION 18451 Convention Center Dr, Tinley Park, IL
 DATE COMPLETED 4/7/18 LOGGED BY NJ DRILLING METHOD 3.25 in. I.D. HSA

DEPTH (ft)	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	IBV VALUE	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	ATTERBERG LIMITS			
													LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0			0-3.5" ASPHALT PAVEMENT													
	691.7		3.5-13.5" AGGREGATE BASE													
1	690.9		mottled brown and gray LEAN CLAY trace sand, trace gravel very stiff, moist	SS 1	89	7-4-4 (8)	4.8	2.5	2.4	14.3						
2																
	689.4															

Bottom of borehole at 2.6 feet.

COMPLETION DEPTH 2.625 ft GROUND ELEVATION 692 ft
 CAVE DEPTH ft BACKFILL Soil Cuttings
 GROUND WATER LEVELS:
 AT TIME OF DRILLING — None
 AT END OF DRILLING — Dry upon completion
 AFTER DRILLING ---

NOTES

Lines of Demarcation represent an **approximate** boundary between soil types. Variations may occur between sampling intervals and between boring locations, and the transition may be gradual. Dashed lines are indicative of potentially erratic or unknown changes.

GPS PAVEMENT LOG - GPS STD DATA TEMPLATE.GDT - 4/16/18 09:48 - K:\GINT\PROJECTS\18-G0382 TINLEY PARK CONVENTION CENTER ILLINOIS-REL.GPJ



CLIENT Robinson Engineering, Ltd PROJECT NAME Tinley Park Convention Center
 PROJECT NUMBER 18-G0382 PROJECT LOCATION 18451 Convention Center Dr, Tinley Park, IL
 DATE COMPLETED 4/7/18 LOGGED BY NJ DRILLING METHOD 3.25 in. I.D. HSA

DEPTH (ft)	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	IBV VALUE	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	ATTERBERG LIMITS			
													LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0			0-3.5" ASPHALT PAVEMENT													
	691.7															
			3.5-13.5" AGGREGATE BASE													
1																
	690.8															
			mottled brown and gray LEAN CLAY trace sand, trace gravel very stiff, moist	SS 1	89	11-7-6 (13)	11.5	3.5	3.4	18.2						
2																
	689.3															

Bottom of borehole at 2.8 feet.

COMPLETION DEPTH 2.75 ft GROUND ELEVATION 692 ft
 CAVE DEPTH ft BACKFILL Soil Cuttings
 GROUND WATER LEVELS:
 AT TIME OF DRILLING — None
 AT END OF DRILLING — Dry upon completion
 AFTER DRILLING —

NOTES

Lines of Demarcation represent an **approximate** boundary between soil types. Variations may occur between sampling intervals and between boring locations, and the transition may be gradual. Dashed lines are indicative of potentially erratic or unknown changes.

GPS PAVEMENT LOG - GPS STD DATA TEMPLATE.GDT - 4/16/18 09:48 - K:\GINT\PROJECTS\18-G0382 TINLEY PARK CONVENTION CENTER ILLINOIS-REL.GPJ



CLIENT Robinson Engineering, Ltd PROJECT NAME Tinley Park Convention Center
 PROJECT NUMBER 18-G0382 PROJECT LOCATION 18451 Convention Center Dr, Tinley Park, IL
 DATE COMPLETED 4/7/18 LOGGED BY NJ DRILLING METHOD 3.25 in. I.D. HSA

DEPTH (ft)	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	IBV VALUE	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	ATTERBERG LIMITS			
													LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0			0-4" ASPHALT PAVEMENT													
	691.7															
			4-14" AGGREGATE BASE													
1	690.8															
			mottled brown and gray LEAN CLAY trace sand, trace gravel hard, moist	SS 1	89	4-5-5 (10)	5.5	4.25	4.2	23.2						
2																
	689.3															

Bottom of borehole at 2.7 feet.

COMPLETION DEPTH 2.66 ft GROUND ELEVATION 692 ft
 CAVE DEPTH ft BACKFILL Soil Cuttings
 GROUND WATER LEVELS:
 AT TIME OF DRILLING — None
 AT END OF DRILLING — Dry upon completion
 AFTER DRILLING —

NOTES

HMA Asphalt: 3 inch core, 1 inch degraded

Lines of Demarcation represent an **approximate** boundary between soil types. Variations may occur between sampling intervals and between boring locations, and the transition may be gradual. Dashed lines are indicative of potentially erratic or unknown changes.

GPS PAVEMENT LOG - GPS STD DATA TEMPLATE.GDT - 4/16/18 09:48 - K:\GINT\PROJECTS\18-G0382 TINLEY PARK CONVENTION CENTER ILLINOIS-REL.GPJ



CLIENT Robinson Engineering, Ltd PROJECT NAME Tinley Park Convention Center
 PROJECT NUMBER 18-G0382 PROJECT LOCATION 18451 Convention Center Dr, Tinley Park, IL
 DATE COMPLETED 4/7/18 LOGGED BY NJ DRILLING METHOD 3.25 in. I.D. HSA

DEPTH (ft)	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	IBV VALUE	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	ATTERBERG LIMITS			
													LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0			0-4" ASPHALT PAVEMENT													
	691.7															
			4-14" AGGREGATE BASE													
1	690.8															
			mottled brown and gray LEAN CLAY trace sand, trace gravel very stiff, moist	SS 1	89	12-10-8 (18)	9.9	3.5		16.9						
2																
	689.3															

Bottom of borehole at 2.7 feet.

COMPLETION DEPTH 2.66 ft GROUND ELEVATION 692 ft
 CAVE DEPTH ft BACKFILL Soil Cuttings
 GROUND WATER LEVELS:
 AT TIME OF DRILLING — None
 AT END OF DRILLING — Dry upon completion
 AFTER DRILLING —

NOTES

HMA Asphalt: 3.5 inch core, 0.5 inch degraded

Lines of Demarcation represent an **approximate** boundary between soil types. Variations may occur between sampling intervals and between boring locations, and the transition may be gradual. Dashed lines are indicative of potentially erratic or unknown changes.

GPS PAVEMENT LOG - GPS STD DATA TEMPLATE.GDT - 4/16/18 09:48 - K:\GINT\PROJECTS\18-G0382 TINLEY PARK CONVENTION CENTER ILLINOIS-REL.GPJ

CLIENT Robinson Engineering, Ltd

PROJECT NAME Tinley Park Convention Center

PROJECT NUMBER 18-G0382

PROJECT LOCATION 18451 Convention Center Dr, Tinley Park, IL 60477

SAMPLE IDENTIFICATION

Visual soil classifications are made in general accordance with the United Soil Classification System (USCS) on the basis of textural and particle size categorization, and various soil behavior characteristics. Visual classifications should be substantiated by appropriate laboratory testing when a more exact soil identification is required to satisfy specific project applications criteria.

UNIFIED SOIL CLASSIFICATION SYSTEM (ASTM D-2487-98)

MATERIAL TYPES	CRITERIA FOR ASSIGNING SOIL GROUP NAMES		GROUP SYMBOL	SOIL GROUP NAMES & LEGEND	
COARSE-GRAINED SOILS >50% RETAINED ON NO. 200 SIEVE	GRAVELS >50% OF COARSE FRACTION RETAINED ON NO 4. SIEVE	CLEAN GRAVELS <5% FINES	$C_u \geq 4$ AND $1 \leq C_c \leq 3$	GW	WELL-GRADED GRAVEL
			$C_u \geq 4$ AND/OR $1 \leq C_c \leq 3$	GP	POORLY-GRADED GRAVEL
		GRAVELS WITH FINES >12% FINES	FINES CLASSIFY AS ML OR CL	GM	SILTY GRAVEL
			FINES CLASSIFY AS CL OR CH	GC	CLAYEY GRAVEL
	SANDS >50% OF COARSE FRACTION PASSES ON NO 4. SIEVE	CLEAN SANDS <5% FINES	$C_u \geq 6$ AND $1 \leq C_c \leq 3$	SW	WELL-GRADED SAND
			$C_u \geq 6$ AND/OR $1 \leq C_c \leq 3$	SP	POORLY-GRADED SAND
		SANDS AND FINES >12% FINES	FINES CLASSIFY AS ML OR MH	SM	SILTY SAND
			FINES CLASSIFY AS CL OR CH	SC	CLAYEY SAND
FINE-GRAINED SOILS >50% PASSES NO. 200 SIEVE	SILTS AND CLAYS LIQUID LIMIT <50	INORGANIC	$PI > 7$ AND PLOTS > "A" LINE	CL	LEAN CLAY
			$PI > 4$ AND PLOTS < "A" LINE	ML	SILT
		ORGANIC	LL (oven dried)/ LL (not dried) < 0.75	OL	ORGANIC CLAY OR SILT
	SILTS AND CLAYS LIQUID LIMIT >50	INORGANIC	PI PLOTS > "A" LINE	CH	FAT CLAY
			PI PLOTS < "A" LINE	MH	ELASTIC SILT
		ORGANIC	LL (oven dried)/ LL (not dried) < 0.75	OH	ORGANIC CLAY OR SILT
HIGHLY ORGANIC SOILS	PRIMARILY ORGANIC MATTER, DARK IN COLOR, AND ORGANIC ODOR		PT	PEAT	


PROJECT LITHOLOGIC SYMBOLS (USCS)

 ASPHALT: Asphalt	 FILL: Fill (made ground)	 GRAVEL FILL: Gravel Fill
--	--	--

PROJECT SAMPLE TYPES

Split Spoon (SS)

PLASTICITY CHART



SOIL RELATIVE DENSITY AND CONSISTENCY CLASSIFICATION

NON-COHESIVE SOILS		COHESIVE SOILS		
RELATIVE DENSITY	N-VALUE*	CONSISTENCY	N-VALUE*	COMPRESSIVE STRENGTH (TSF)
VERY LOOSE	0-3	VERY SOFT	0-2	0-0.25
LOOSE	3-7	SOFT	2-5	0.25-0.50
MEDIUM DENSE	7-15	MEDIUM STIFF	5-10	0.50-1.0
DENSE	15-38	STIFF	10-14	1.0-2.0
VERY DENSE	OVER 38	VERY STIFF	14-32	2.0-4.0
		HARD	OVER 32	OVER 4.0

* N-VALUE: NUMBER OF BLOWS OF 140 LB HAMMER FALLING 30 INCHES TO DRIVE A 2 INCH O.D. (1-3/8 INCH I.D.) SPLIT-BARREL SAMPLER THE LAST 12 INCHES OF AN 18-INCH DRIVE (ASTM-1586 STANDARD PENETRATION TEST).

ABBREVIATIONS

SS - SPLIT-SPOON SAMPLE	LL - LIQUID LIMIT (%)
ST - SHELBY TUBE SAMPLE	PL - PLASTIC LIMIT (%)
AU - AUGER SAMPLE	PI - PLASTIC INDEX (%)
MC - MOISTURE CONTENT (%)	NP - NON PLASTIC
-200 - PERCENT PASSING NO. 200 SIEVE	DD - DRY DENSITY (PCF)
Qp - POCKET PENETROMETER (TSF)	DCP - DYNAMIC CONE PENETROMETER
Qu - UNCONFINED STRENGTH (TSF)	IBV - IMMEDIATE BEARING VALUE



GRAIN SIZE DISTRIBUTION


PRINT DATE 4/13/2018

CLIENT Robinson Engineering, Ltd

PROJECT NAME Tinley Park Convention Center

PROJECT NUMBER 18-G0382

PROJECT LOCATION 18451 Convention Center Dr, Tinley Park, IL 60477



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

BOREHOLE	DEPTH	Classification					LL	PL	PI	Cc	Cu
● Composite	1.0	AGGREGATE BASE								2.56	48.96

BOREHOLE	DEPTH	D100	D60	D50	D10	%Gravel	%Sand	%Silt	%Clay
● Composite	1.0	25	3.929	2.647	0.08	35.2	55.2	9.6	

GRAIN SIZE - GPS STD DATA TEMPLATE.GDT - 4/13/18 09:38 - K:\GINT\PROJECTS\18-G0382 TINLEY PARK CONVENTION CENTER ILLINOIS-REL.GPJ

Boring B-01 Pavement Core

**3.5" Asphalt Pavement
8.5" Aggregate base
IBV Value: 4.2**



9370 Laraway Road, Suite D
Frankfort, IL 60423
P. 815.806.9986 F. 815.464.8691

Pavement Core Photograph Log
Tinley Park Convention Center
18451 Convention Center Drive
Tinley Park, IL 60477

PROJECT NUMBER:
18-G0382

DATE: April 2018

Boring B-02 Pavement Core

**3.5" Asphalt Pavement
10.0" Aggregate base
IBV Value: 4.8**



 **GEOCON**
PROFESSIONAL SERVICES
9370 Laraway Road, Suite D
Frankfort, IL 60423
P. 815.806.9986 F. 815.464.8691

Pavement Core Photograph Log
Tinley Park Convention Center
18451 Convention Center Drive
Tinley Park, IL 60477

PROJECT NUMBER:
18-G0382

DATE: April 2018

Boring B-03 Pavement Core

3.5" Asphalt Pavement
10.0" Aggregate base
IBV Value: 11.5



9370 Laraway Road, Suite D
Frankfort, IL 60423
P. 815.806.9986 F. 815.464.8691

Pavement Core Photograph Log
Tinley Park Convention Center
18451 Convention Center Drive
Tinley Park, IL 60477

PROJECT NUMBER:
18-G0382

DATE: April 2018

Boring B-04 Pavement Core

4.0" Asphalt Pavement
10.0" Aggregate base
IBV Value: 5.5



*** 3 inch core, 1 inch degraded



9370 Laraway Road, Suite D
Frankfort, IL 60423
P. 815.806.9986 F. 815.464.8691

Pavement Core Photograph Log
Tinley Park Convention Center
18451 Convention Center Drive
Tinley Park, IL 60477

PROJECT NUMBER:
18-G0382

DATE: April 2018

Boring B-05 Pavement Core

4.0" Asphalt Pavement
10.0" Aggregate base
IBV Value: 9.9



****3.5 inch core, 0.5 inch degraded*



9370 Laraway Road, Suite D
Frankfort, IL 60423
P. 815.806.9986 F. 815.464.8691



Pavement Core Photograph Log
Tinley Park Convention Center
18451 Convention Center Drive
Tinley Park, IL 60477

PROJECT NUMBER:
18-G0382




DATE: April 2018

Appendix B

STANDARD DRAWINGS



Note:
Longitudinal joints shall be as detailed on Standard 420001, except
tie bars are not required for patches 20'-0" (6.0 m) or less in length.



GENERAL NOTES
Existing tie bars shall be either cut or removed.
Marginal bars shall be cut.

All dimensions are in inches (millimeters)
unless otherwise shown.


DATE	REVISIONS
1-1-08	Switched units to English (metric).
1-1-07	Revised Note for Class C patches.

CLASS C and D PATCHES


STANDARD 442201-03

Illinois Department of Transportation
PASSED January 1, 2008
ENGINEER OF POLICY AND PROCEDURES
APPROVED January 1, 2008
ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97 44-1




PLAN
ADJACENT TO PCC PAVEMENT OR PCC BASE COURSE



DETAIL A
EXPANSION JOINT

Full depth & width 1 (25) - thick (min.) preformed expansion joint filler.



DEPRESSED CURB ADJACENT TO CURB RAMP ACCESSIBLE TO THE DISABLED

GENERAL NOTES

The bottom slope of combination curb and gutter constructed adjacent to pcc pavement shall be the same slope as the subbase or 6% when subbase is omitted.

t = Thickness of pavement.


Longitudinal joint tie bars shall be No. 6 (No. 19) at 36 (900) centers in accordance with details for longitudinal construction joint shown on Standard 420001.

A minimum clearance of 2 (50) between the end of the tie bar and the back of the curb shall be maintained.


The dowel bars shown in contraction joints will only be required for monolithic construction.

See Standard 606301 for details of corner islands.


All dimensions are in inches (millimeters) unless otherwise shown.




DEPRESSED CURB (TYPICAL)




ADJACENT TO PCC BASE COURSE WITH HMA SURFACING



M-2.06 (M-5.15) and M-2.12 (M-5.30)



BARRIER CURB



MOUNTABLE CURB

TABLE OF DIMENSIONS BARRIER CURB					
TYPE	A	B	C	D	R1
B-6.06 *	6	1	6	6	1
(B-15.15)	(150)	(25)	(150)	(150)	(25)
B-6.12	12	1	6	6	1
(B-15.3)	(300)	(25)	(150)	(150)	(25)
B-6.18	18	1	6	6	1
(B-15.45)	(450)	(25)	(150)	(150)	(25)
B-6.24	24	1	6	6	1
(B-15.60)	(600)	(25)	(150)	(150)	(25)
B-9.12	12	2	5	9	1
(B-22.30)	(300)	(50)	(125)	(225)	(25)
B-9.18	18	2	5	9	1
(B-22.45)	(450)	(50)	(125)	(225)	(25)
B-9.24	24	2	5	9	1
(B-22.60)	(600)	(50)	(125)	(225)	(25)

* For corner islands only.

TABLE OF DIMENSIONS MOUNTABLE CURB							
TYPE	A	B	C	D	R1	R2	
M-2.06	6	2	4	2	3	2	
(M-5.15)	(150)	(50)	(100)	(50)	(75)	(50)	
M-2.12	12	2	4	2	3	2	
(M-5.30)	(300)	(50)	(100)	(50)	(75)	(50)	
M-4.06	6	4	3	4	3	NA	
(M-10.15)	(150)	(100)	(75)	(100)	(75)	NA	
M-4.12	12	4	3	4	3	NA	
(M-10.30)	(300)	(100)	(75)	(100)	(75)	NA	
M-4.18	18	4	3	4	3	NA	
(M-10.45)	(450)	(100)	(75)	(100)	(75)	NA	
M-4.24	24	4	3	4	3	NA	
(M-10.60)	(600)	(100)	(75)	(100)	(75)	NA	
M-6.06	6	6	2	6	2	NA	
(M-15.15)	(150)	(150)	(50)	(150)	(50)	NA	
M-6.12	12	6	2	6	2	NA	
(M-15.30)	(300)	(150)	(50)	(150)	(50)	NA	
M-6.18	18	6	2	6	2	NA	
(M-15.45)	(450)	(150)	(50)	(150)	(50)	NA	
M-6.24	24	6	2	6	2	NA	
(M-15.60)	(600)	(150)	(50)	(150)	(50)	NA	

Illinois Department of Transportation

PASSED January 1, 2018

ENGINEER OF PROJECT AND PROCEDURES

APPROVED January 1, 2018


ENGINEER OF DESIGN AND ENVIRONMENT

DATE	REVISIONS
1-1-18	Revised General Note for tie bar spacing to 36 (900) cts.
1-1-15	Added B-6.06 (B-15.15) barrier curb and gutter to table (corner islands only).

CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER


(Sheet 1 of 2)

STANDARD 606001-07




Undoweled contraction joint (typ.) construction options:


1. Form with $\frac{1}{8}$ (3) thick steel template 2 (50) deep, and seal.
2. Saw 2 (50) deep at 4 to 24 hours, and seal.
3. Insert $\frac{1}{8}$ (20) thick preformed joint filler full depth and width.



PLAN




ON DISTURBED SUBGRADE




ON UNDISTURBED SUBGRADE

ADJACENT TO FLEXIBLE PAVEMENT




DEPRESSED CURB




BARRIER CURB

ADJACENT TO FLEXIBLE PAVEMENT



DEPRESSED CURB



BARRIER CURB


ADJACENT TO PCC PAVEMENT OR PCC BASE COURSE

CONCRETE CURB TYPE B


**CONCRETE CURB TYPE B
AND COMBINATION
CONCRETE CURB AND GUTTER**
(Sheet 2 of 2)

STANDARD 606001-07

Illinois Department of Transportation	
PASSED	January 1, 2018
<i>Michael Beaud</i>	
ENGINEER OF PROJECT AND PROCEDURES	
APPROVED	January 1, 2018
<i>Thomas W. Baker</i>	
ENGINEER OF DESIGN AND ENVIRONMENT	
DESIGN QUANTITY	



For contract construction projects




W20-1103(0)-48



W21-1(0)-48

For maintenance and utility projects



W20-1(0)-48

TYPICAL APPLICATIONS

- Utility operations
- Culvert extensions
- Side slope changes
- Guardrail installation and maintenance
- Delineator installation
- Landscaping operations
- Shoulder repair
- Sign installation and maintenance

SYMBOLS

-  Work area
-  Sign
-  Conc. drum or barricade

① When the work operation exceeds one hour, cones, drums or barricades shall be placed at 25' (8 m) centers for L/3 distance, and at 50' (15 m) centers through the remainder of the work area.

GENERAL NOTES

This Standard is used where any vehicles, equipment, workers or their activities will encroach in the area 15' (4.5 m) to 24' (600) from the edge of pavement.

Calculate L as follows:

SPEED LIMIT

FORMULAS
English (Metric)

40 mph (70 km/h)
or less:

$$L = \frac{WS^2}{60} \quad L = \frac{WS^2}{150}$$

45 mph (80 km/h)
or greater:

$$L = (W)(S) \quad L = 0.65(W)(S)$$

W = Width of offset
in feet (meters).

S = Normal posted speed
mph (km/h).


All dimensions are in inches (millimeters)
unless otherwise shown.


**OFF-RD OPERATIONS, 2L, 2W,
15' (4.5 m) TO 24" (600 mm)
FROM PAVEMENT EDGE**

STANDARD 701006-05




DATE	REVISIONS
1-1-14	Revised workers sign number to agree with current MUTCD.
1-1-13	Omitted text 'WORKERS' sign

Illinois Department of Transportation

PASSED January 1, 2014

 ENGINEER OF STATE ENGINEERING

APPROVED January 1, 2014

 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-14



TYPICAL APPLICATIONS

- Marking patches
- Field survey
- String line
- Utility operations
- Cleaning up debris on pavement

SYMBOLS

- Work area
- Sign on portable or permanent support
- Flagger with traffic control sign

All dimensions are in inches (millimeters) unless otherwise shown.


Illinois Department of Transportation

PASSED: JANUARY 1, 2011
 ENGINEER OF CIVIL ENGINEERING
 APPROVED: JANUARY 1, 2011
 ENGINEER OF DESIGN AND ENVIRONMENT

DATE	REVISIONS
1-1-11	Revised flagger sign.
1-1-09	Switched units to English (metric)

LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS

STANDARD 701301-04







* Distance varies depending on terrain and susceptibility of pavement marking or crack sealant to wheel tracking.

TYPICAL APPLICATIONS

- Landscaping work
- Utility work
- Pavement marking
- Weed spraying
- Roadmeter measurements
- Debris cleanup
- Crack pouring

SYMBOLS

-  Arrow board (Hazard Mode only)
-  Truck with headlights, emergency flashers and flashing amber light (visible from all directions)
-  18x18 (450x450) min. orange flag (use when guide wheel is used)
-  Truck mounted attenuator

GENERAL NOTES

This Standard is used where any vehicle, equipment, workers or their activities will require a continuous moving operation where the average speed is greater than 3 mph (5 km/h).

For shoulder operations not encroaching on the pavement, use DETAIL A, Standard 701426.

All dimensions are in inches (millimeters) unless otherwise shown.

DATE	REVISIONS
1-1-09	Switched units to English (metric). Omitted Pass With Care sign.
1-1-00	Elim. speed restrictions in Standard title.

**LANE CLOSURE 2L, 2W
MOVING OPERATIONS-
DAY ONLY**

STANDARD 701311-03

Illinois Department of Transportation


PASSED January 1, 2009

ENGINEER OF OPERATIONS *[Signature]*

APPROVED January 1, 2009

ENGINEER OF DESIGN AND ENVIRONMENT *[Signature]*

DATE CHANGED



SIGN SPACING	
Posted Speed	Sign Spacing
55	500' (150 m)
50-45	350' (100 m)
<45	200' (60 m)

SYMBOLS

- Work area
- Cone, drum or barricade (not required for moving operations)
- Sign on portable or permanent support
- Flagger with traffic control sign
- Barricade or drum with flashing light
- Type III barricade with flashing lights

- ① Refer to SIGN SPACING TABLE for distances.
- ② For approved slideroad closures.
- ③ Cones at 25' (8 m) centers for 250' (75 m). Additional cones may be placed at 50' (15 m) centers. When drums or Type I or Type II barricades are used, the interval between devices may be doubled.
- ④ Cones, drums or barricades at 20' (6 m) centers.

GENERAL NOTES

This Standard is used where at any time, day or night, any vehicle, equipment, workers or their activities encroach on the pavement requiring the closure of one traffic lane in an urban area.

All dimensions are in inches (millimeters) unless otherwise shown.

Illinois Department of Transportation


PASSED JANUARY 1 2011
 ENGINEER OF STATE HIGHWAYS
 APPROVED JANUARY 1 2011
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-11
 DATE 1-1-11

DATE	REVISIONS
1-1-11	Revised flagger sign.
1-1-09	Switched units to English (metric). Corrected sign No.'s.

**URBAN LANE CLOSURE,
2L, 2W, UNDIVIDED**

STANDARD 701501-06




W20-1103(0)-48 for contract construction projects



Or
W20-1(0)-48 for maintenance and utility projects

SIDEWALK DIVERSION



W20-1103(0)-48 for contract construction projects



Or
W20-1(0)-48 for maintenance and utility projects



R11-1102-2430



R11-1101-2418



R11-1102-2430

SIDEWALK CLOSURE

① Omit whenever duplicated by road work traffic control.

GENERAL NOTES

This Standard is used where, at any time, pedestrian traffic must be rerouted due to work being performed.

This Standard must be used in conjunction with other Traffic Control & Protection Standards when roadway traffic is affected.

Temporary facilities shall be detectable and accessible.

The temporary pedestrian facilities shall be provided on the same side of the closed facilities whenever possible.

The SIDEWALK CLOSED / USE OTHER SIDE sign shall be placed at the nearest crosswalk or intersection to each end of the closure. Where the closure occurs at a corner, the signs shall be erected on the corners across the street from the closure. The SIDEWALK CLOSED signs shall be used at the ends of the actual closures.

Type III barricades and R11-2-4830 signs shall be positioned as shown in "ROAD CLOSED TO ALL TRAFFIC" detail on Standard 701901.

All dimensions are in inches (millimeters) unless otherwise shown.

SYMBOLS

- Work area
- Sign on portable or permanent support
- Barricade or drum
- Cone, drum or barricade
- Type III barricade
- Detectable pedestrian channelizing barricade

Illinois Department of Transportation

PASSED: *[Signature]* APR 11 2016
ENGINEER OF SAFETY ENGINEERING

APPROVED: *[Signature]* APR 11 2016
ENGINEER OF DESIGN AND ENVIRONMENT


661111 02/2015

DATE	REVISIONS
4-1-16	Omitted orange safety fence from standard as this is covered in the std. spec.
1-1-12	Added SIDEWALK DIVERSION. Modified appearance of plan views. Renamed Std.


SIDEWALK, CORNER OR CROSSWALK CLOSURE

(Sheet 1 of 2)

STANDARD 701801-06



CORNER CLOSURE




CROSSWALK CLOSURE

SIDEWALK, CORNER OR CROSSWALK CLOSURE


[Sheet 2 of 2]

STANDARD 701801-06


Illinois Department of Transportation	
PASSED	APR 11 2016
ENGINEER OF SURVEYING	APR 11 2016
APPROVED	APR 11 2016
ENGINEER OF DESIGN AND ENVIRONMENT	




CONE FOR DAYTIME




REFLECTORIZED CONE FOR NIGHTTIME




TUBULAR MARKER




VERTICAL PANEL POST MOUNTED




DRUM




TYPE I BARRICADE




TYPE II BARRICADE




TYPE III BARRICADE



DIRECTION INDICATOR BARRICADE



VERTICAL BARRICADE



DETECTABLE PEDESTRIAN CHANNELIZING BARRICADE

* Warning lights (if required)

GENERAL NOTES

All heights shown shall be measured above the pavement surface.

All dimensions are in inches (millimeters) unless otherwise shown.

Illinois Department of Transportation

DESIGNED BY: *John Allen* JANUARY 1, 2018

APPROVED BY: *Thomas W. Baker* JANUARY 1, 2018

ENGINEER OF DESIGN AND ENVIRONMENT

68-111 02/ISS: 2018

DATE	REVISIONS
1-1-18	Revised END WORK ZONE SPEED LIMIT sign from orange to white background.
1-1-17	Changed FLEXIBLE DELINEATOR to TUBULAR MARKER.

TRAFFIC CONTROL DEVICES


(Sheet 1 of 3)

STANDARD 701901-07




POST MOUNTED SIGNS

** When curb or paved shoulder are present this dimension shall be 24 (600) to the face of curb or 6' (1.8 m) to the outside edge of the paved shoulder.



SIGNS ON TEMPORARY SUPPORTS

*** When work operations exceed four days, this dimension shall be 5' (1.5 m) min. If located behind other devices, the height shall be sufficient to be seen completely above the devices.



HIGH LEVEL WARNING DEVICE

ROAD CONSTRUCTION NEXT X MILES	END CONSTRUCTION
G20-1104(0)-6036	G20-1105(0)-6024

This signing is required for all projects 2 miles (3200 m) or more in length.
 ROAD CONSTRUCTION NEXT X MILES sign shall be placed 500' (150 m) in advance of project limits.
 END CONSTRUCTION sign shall be erected at the end of the job unless another job is within 2 miles (3200 m).
 Dual sign displays shall be utilized on multi-lane highways.

WORK LIMIT SIGNING

WORK ZONE	W21-1115(0)-3618
SPEED LIMIT	R2-1-3648
XX	
PHOTO ENFORCED	R10-1108p-3618
XXXX FINE MINIMUM	R2-1106p-3618

Sign assembly as shown on Standards or as allowed by District Operations.

END WORK ZONE SPEED LIMIT	G20-1103-6036
----------------------------------	---------------

This sign shall be used when the above sign assembly is used.

HIGHWAY CONSTRUCTION SPEED ZONE SIGNS


*** R10-1108p shall only be used along roadways under the jurisdiction of the State.



W12-1103-4848

WIDTH RESTRICTION SIGN

XX'-XX" width and X miles are variable.



FLAGGER TRAFFIC CONTROL SIGN

Illinois Department of Transportation


PASSED	JANUARY 1	2018
APPROVED	JANUARY 1	2018

ENGINEER OF OPERATIONS
 ENGINEER OF DESIGN AND ENVIRONMENT



TRAFFIC CONTROL DEVICES

(Sheet 2 of 3)



STANDARD 701901-07



ARROW BOARDS




SECTION A-A




TYPICAL INSTALLATION

TEMPORARY RUMBLE STRIPS



ReflectORIZED striping may be omitted on the back side of the barricades. If a Type III barricade with an attached sign panel which meets NCHRP 350 is not available, the sign may be mounted on an NCHRP 350 temporary sign support directly in front of the barricade.

**TYPICAL APPLICATIONS OF
TYPE III BARRICADES CLOSING A ROAD**



ReflectORIZED striping shall appear on both sides of the barricades. If a Type III barricade with an attached sign panel which meets NCHRP 350 is not available, the signs may be mounted on NCHRP 350 temporary sign supports directly in front of the barricade.

**TRAFFIC CONTROL
DEVICES**

(Sheet 3 of 3)

STANDARD 701901-07



Illinois Department of Transportation

DESIGNED: January 1, 2018

APPROVED: January 1, 2018

ENGINEER OF OPERATIONS

ENGINEER OF DESIGN AND ENVIRONMENT




Legend Height	Arrow Size	a
6' (1.8 m)	Small	2.9 (74)
8' (2.4 m)	Large	3.8 (96)

The space between adjacent letters or numerals should be approximately 3/15 for 6' (1.8 m) legend and 4/100 for 8' (2.4 m) legend.

LETTER AND ARROW GRID SCALE

Illinois Department of Transportation
 PASSED *[Signature]* 2015
 ENGINEERING OPERATIONS
 APPROVED *[Signature]* 2015
 DIVISION OF TRAFFIC AND ENVIRONMENTAL

TYPICAL PAVEMENT MARKINGS
 STANDARD 780001-05
 (Sheet 2 of 3)



LANE-REDUCTION ARROW

Right lane-reduction arrow shown.
Use mirror image for left lane.




20' (6 m): urban
50' (15 m): rural
(Between arrow
and word or
between words)

ONLY

6' (1.8 m): urban
8' (2.4 m): rural

WORD AND ARROW LAYOUT



WRONG WAY ARROW



**INTERNATIONAL
SYMBOL OF
ACCESSIBILITY**



**SHARED LANE
SYMBOL**



BIKE SYMBOL
(Arrow is optional.)

Illinois Department of Transportation

PASSED January 1, 2015

ENGINEER OF OPERATIONS

APPROVED January 1, 2015


REGISTERED PROFESSIONAL ENGINEER

REGISTERED PROFESSIONAL ENGINEER

**TYPICAL PAVEMENT
MARKINGS**

(Sheet 3 of 3)

STANDARD 780001-05



NOTES:

1. SIDE ROAD WITH A SPEED LIMIT OF 40 MPH (60 km/h) OR LESS AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
 - a) ONE "ROAD CONSTRUCTION AHEAD" SIGN 36 x 36 (900x900) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 200' (60 m) IN ADVANCE OF THE MAIN ROUTE.
 - b) THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE I, TYPE II OR TYPE III BARRICADES, 1/3 OF THE CROSS SECTION OF THE CLOSED PORTION.
2. SIDE ROAD WITH A SPEED LIMIT GREATER THAN 40 MPH (60 km/h) AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
 - a) ONE "ROAD CONSTRUCTION AHEAD" SIGN 48 x 48 (1.2 m x 1.2 m) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 500' (150 m) IN ADVANCE OF THE MAIN ROUTE.
 - b) THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE III BARRICADES, 1/2 OF THE CROSS SECTION OF THE CLOSED PORTION.
3. CONES MAY BE SUBSTITUTED FOR BARRICADES OR DRUMS AT HALF THE SPACING DURING DAY OPERATIONS. CONES SHALL BE A MINIMUM OF 28 (710) IN HEIGHT.
4. WHEN THE SIDE ROAD LIES BETWEEN THE BEGINNING OF THE MAINLINE SIGNING AND THE WORK ZONE, A SINGLE HEADED ARROW (M6-1) SHALL BE USED IN LIEU OF THE DOUBLE HEADED ARROW (M6-4).
5. WHEN WORK IS BEING PERFORMED ON A SIDE ROAD OR DRIVEWAY, FOLLOW THE APPLICABLE STANDARDS. THE DIRECTIONAL ARROW (M6-1 OR M6-4) SHALL BE COVERED OR REMOVED WHEN NO LONGER CONSISTENT WITH THE TRAFFIC CONTROL SET-UP.
6. ADVANCE WARNING SIGNS ARE TO BE OMITTED ON DRIVEWAYS UNLESS OTHERWISE SPECIFIED IN THE PLANS OR BY THE ENGINEER.
7. THE TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.

All dimensions are in inches (millimeters) unless otherwise shown.

FILE NAME *	USER NAME * (optional)	DESIGNED - L.H.A.	REVISED - A. HOUSEH 10-15-96
path\11888\REDINT\Gallimages\p\1007\Documents\1007 Offices\District 1\Project\Dist 1\GMM\CAD\DATA\CAD\Drawings\1018.dgn			REVISED - T. RAMMACHER 01-06-00
Default	PLOT SCALE = 50.000 / in.	CHECKED -	REVISED - A. SCHUETZE 07-01-13
	PLOT DATE = 9/15/2018	DATE - 06-89	REVISED - A. SCHUETZE 09-15-16



**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TRAFFIC CONTROL AND PROTECTION FOR
SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS**

SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	TC-10			
ILLINOIS FED. AID PROJECT			CONTRACT NO.	

PARKING BLOCKS



* OR AS DIRECTED BY THE ENGINEER.

GENERAL NOTES

CLASS SI CONCRETE SHALL BE USED THROUGHOUT.

ANCHOR PINS SHALL BE 3/4 DIAMETER, 36 LONG.

THE COST OF THE MATERIAL, LABOR AND EQUIPMENT NECESSARY TO INSTALL THE PARKING BLOCKS WITH ANCHOR PINS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER EACH FOR PARKING BLOCKS.

ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.

PLOT DATE - 4/19/2016

REVISED - 10-03-11
REVISED -
REVISED -
REVISED -

REGION 2 / DISTRICT 2 STANDARD				
SCALE: 1.5485' / in.	SHEET NO.	OF	SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PLAN
SHEETS

VILLAGE of TINLEY PARK, ILLINOIS

CONVENTION CENTER PARKING LOT IMPROVEMENTS




HIGHWAY STANDARDS

442201-03	CLASS C AND D PATCHES
606001-07	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
701006-05	OFF RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701311-03	LANE CLOSURE, 2L, 2W MOVING OPERATIONS - DAY ONLY
701501-06	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701801-06	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901-07	TRAFFIC CONTROL DEVICES
780001-05	TYPICAL PAVEMENT MARKINGS

DISTRICT 1 STANDARDS

TC-10	TRAFFIC CONTROL AND PROTECTION FOR SIDEROADS, INTERSECTIONS & DRIVEWAYS
TC-13	TYPICAL PAVEMENT MARKINGS



LOCATION MAP

— INDICATES PROPOSED IMPROVEMENT

INDEX OF SHEETS

1. COVER SHEET
2. SUMMARY OF QUANTITIES AND GENERAL NOTES
3. PAVEMENT PLAN - OPTION 1
4. PAVEMENT PLAN - OPTION 2
5. PAVEMENT MARKING PLAN

PREPARED BY OR UNDER THE
DIRECT SUPERVISION OF:

Jeffrey P. Pring

06-21-18



LICENSE EXPIRES: 11/30/19

PREPARED BY:



© COPYRIGHT 2018
ILLINOIS DESIGN FIRM REGISTRATION NO. 184001128

PROJECT NO. 18-R0455

SHEET NO. 01 OF 05

18R0455-COVR-03 - COVR01

Call Before You Dig

JULIE
ILLINOIS ONE-CALL SYSTEM

JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS

48 hours before you dig
(EXCLUDING SAT., SUN. & HOL.)

811

Call: 811 OR 1-800-892-0123

OPTION #1


NO.	ITEM DESCRIPTION	UNIT	TOTAL
1	TOPSOIL FURNISH AND PLACE, 4" (SPECIAL)	SQ YD	75
2	PREPARATION OF BASE	SQ YD	2,500
3	AGGREGATE BASE REPAIR	TON	840
4	BITUMINOUS MATERIALS (PRIME COAT)	POUND	5,630
5	BITUMINOUS MATERIALS (TACK COAT)	POUND	11,100
6	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2,900
7	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	25,850
8	COMBINATION CURB AND GUTTER REMOVAL	FOOT	200
9	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	2,500
10	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	200
11	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,100
12	PAINT PAVEMENT MARKING - LINE 4"	FOOT	28,000
13	PAINT PAVEMENT MARKING - LINE 6"	FOOT	800
14	PAINT PAVEMENT MARKING - LINE 24"	FOOT	100
15	REMOVE EXISTING PARKING BLOCKS	EACH	20
16	CONCRETE PARKING BLOCKS	EACH	20
17	SODDING, SPECIAL	SQ YD	75
18	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	25
19	DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED	EACH	5
20	RUBBER ADJUSTING RINGS	EACH	50
21	STEEL ADJUSTING RINGS	EACH	10

OPTION #2

NO.	ITEM DESCRIPTION	UNIT	TOTAL
1	TOPSOIL FURNISH AND PLACE, 4" (SPECIAL)	SQ YD	75
2	PREPARATION OF BASE	SQ YD	2,500
3	AGGREGATE BASE REPAIR	TON	840
4	BITUMINOUS MATERIALS (PRIME COAT)	POUND	20,430
5	BITUMINOUS MATERIALS (TACK COAT)	POUND	9,590
6	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,150
7	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2,770
8	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	16,770
9	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	9,080
10	COMBINATION CURB AND GUTTER REMOVAL	FOOT	200
11	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	200
12	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,100
13	PAINT PAVEMENT MARKING - LINE 4"	FOOT	28,000
14	PAINT PAVEMENT MARKING - LINE 6"	FOOT	800
15	PAINT PAVEMENT MARKING - LINE 24"	FOOT	100
16	REMOVE EXISTING PARKING BLOCKS	EACH	20
17	CONCRETE PARKING BLOCKS	EACH	20
18	SODDING, SPECIAL	SQ YD	75
19	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	25
20	DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED	EACH	5
21	RUBBER ADJUSTING RINGS	EACH	50
22	STEEL ADJUSTING RINGS	EACH	10

GENERAL NOTES

- ALL CONSTRUCTION SHALL CONFORM TO THE LATEST EDITION OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION".
- ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST HIGHWAY STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
- BOTH THE ROBINSON ENGINEERING, LTD. FIELD OFFICE (708-331-6700) AND THE VILLAGE OF TINLEY PARK VILLAGE ENGINEER (708-444-5500) SHALL BE NOTIFIED TWO (2) WORKING DAYS BEFORE CONSTRUCTION BEGINS.
- AREAS DISTURBED BY CONSTRUCTION SHALL BE KEPT TO A MINIMUM. ALL AREAS DISTURBED UNNECESSARILY SHALL BE RESTORED AS REQUIRED, AT THE CONTRACTORS EXPENSE.
- CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, CONDITIONS, AND EXTENT OF THE WORK TO BE ACCOMPLISHED UNDER THIS CONTRACT, AT THE CONTRACTORS EXPENSE.
- CONTRACTOR SHALL EXAMINE ALL DRAWINGS AND SPECIFICATIONS FOR ANY WORK MARKED FOR EACH RESPECTIVE SUBCONTRACTOR AND INCLUDE SUCH WORK IN THEIR BID.
- ALL DIMENSIONS INDICATED ON THE DRAWINGS SHALL BE ADHERED TO IN PREFERENCE TO SCALING DRAWINGS.
- WHEN IN THE CONSTRUCTION OPERATION, ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF DITCHES, GUTTERS OR OTHER DRAINAGE STRUCTURES SO THAT THE NATURAL FLOW OF WATER IS OBSTRUCTED, IT SHALL BE REMOVED AT THE CLOSE OF EACH DAY BY THE CONTRACTOR AT HIS EXPENSE. AT THE CONCLUSION OF THE CONSTRUCTION OPERATION, ALL DRAINAGE STRUCTURES SHALL BE FREE FROM ALL DIRT AND DEBRIS. THIS WORK SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- THE REMOVAL AND/OR REPLACEMENT OF ANY DRIVEWAYS, PAVEMENT, CURB, SIDEWALK, ETC., SHALL BE ACCOMPLISHED BY MEANS OF A SAW CUT JOINT, AT THE DIRECTION OF THE ENGINEER. THE SAW CUTTING SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THE VARIOUS RELEVANT ITEMS.
- WHEN EXISTING DRAINAGE FACILITIES ARE DISTURBED, THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TEMPORARY OUTLETS AND CONNECTIONS FOR ALL PRIVATE OR PUBLIC DRAINS, SEWERS OR CATCH BASINS. HE SHALL PROVIDE FACILITIES TO TAKE ALL STORM WATER WHICH WILL BE RECEIVED BY THESE DRAINS AND SEWERS AND DISCHARGE SAME. HE SHALL PROVIDE AND MAINTAIN AN EFFICIENT PUMPING PLAN, IF NECESSARY, AND A TEMPORARY OUTLET, AND BE PREPARED AT ALL TIMES TO DISPOSE OF THE WATER CONNECTIONS WITH SEWERS ARE BUILT AND IN SERVICE. THIS WORK WILL NOT BE PAID FOR DIRECTLY, BUT WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- THE CONTRACTOR SHALL FURNISH, ERECT AND MAINTAIN SUCH BARRICADES, SIGNS AND LIGHTS AS ARE NECESSARY TO SAFEGUARD TRAFFIC AND PROTECT THE WORK IN ACCORDANCE WITH ARTICLE 107.14 OF THE STANDARD SPECIFICATIONS, AS SPECIFIED HEREIN, AND AS REQUIRED BY THE MUNICIPALITY. SUCH BARRICADES, SIGNS AND LIGHTS SHALL BE PROVIDED WHEREVER REQUIRED TO PREVENT ANY ACCIDENT OR HARM TO LIFE, LIMB, PROPERTY OR THE WORK IN CONSEQUENCE OF THE EXCAVATION, USE OR OCCUPANCY OF STREETS, ALLEYS, HIGHWAYS OR RIGHT-OF-WAY. OPERATION OF FLASHER LIGHTS SHALL BE MAINTAINED BY THE CONTRACTOR AS LONG AS THEY ARE NEEDED TO SAFEGUARD TRAFFIC AND PROTECT THE WORK AS DETERMINED BY THE MUNICIPALITY. COMPLIANCE WITH THE ABOVE REQUIREMENTS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY J.U.L.I.E. AT LEAST 48 HOURS PRIOR TO EXCAVATION TO VERIFY LOCATIONS OF ALL UTILITIES. IF DETERMINED NECESSARY UTILITY RELOCATIONS SHALL BE PERFORMED BY PRIVATE UTILITY OWNERS. NO ADDITIONAL COMPENSATION SHALL BE ALLOWED DUE TO DELAYS OR INCONVENIENCES CAUSED BY SUCH ADJUSTMENTS.
- CONTRACTOR SHALL PROVIDE THE ENGINEER WITH VIDEO DETAILING ALL SURFACE CONDITIONS WITHIN THE PROJECT AREA PRIOR TO EXCAVATION. ALL RESTORATION SHALL BE COMPLETED TO THE SATISFACTION OF THE OWNER AND ENGINEER.
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON VILLAGE PROPERTY WITHOUT PERMISSION FROM THE VILLAGE.
- THE TOP OF ALL STRUCTURES SHALL BE FLUSH WITH THE ADJACENT SURFACE OR THE INDICATED ELEVATION SHOWN ON THE PLANS.
- THE THICKNESS OF HMA MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA SURFACE IS PLACED.
- CLASS D PATCHING QUANTITIES FOR THIS CONTRACT SHALL BE PERFORMED AT THE DIRECTION OF THE ENGINEER AFTER PAVEMENT MILLING.



STAGING NOTES:

- MUST MAINTAIN ACCESS FOR ACCESS ROAD AT ALL TIMES - LIMITED CLOSURE ONLY. FULL CLOSURE NOT ALLOWED
- MAIN PARKING LOT AND SOUTHEAST LOT CANNOT BE CLOSED AT THE SAME TIME

DATE	= 06-21-18	DESIGNED	-- JP	REVISED	--
SCALE	= NONE	CHECKED	-- JP	REVISED	--
PROJECT NO	= 18-R0455	DRAWN	-- CAD	REVISED	--
FILE NAME	= 18R0455-QUAN-03	CHECKED	-- AG	REVISED	--










CONVENTION CENTER
PARKING LOT IMPROVEMENTS
SUMMARY OF QUANTITIES AND GENERAL NOTES

VILLAGE
of
TINLEY PARK

SHEET NO.
02 of 05

HARLEM AVENUE


LEGEND

-  HOT-MIX ASPHALT SURFACE REMOVAL, 2"
-  HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50, 2"
-  CLASS "D" PATCHES TYPE IV, 4"
-  AGGREGATE BASE REPAIR
-  PREPARATION OF BASE
-  B-8.12 COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT
-  DRAINAGE & UTILITY STRUCTURE TO BE ADJUSTED



NOTES:

1. ALL PAVEMENT MARKINGS TO BE COMPLETED AS DIRECTED BY THE ENGINEER.
2. FINAL PATCHING LOCATIONS TO BE DETERMINED IN THE FIELD BY THE ENGINEER.
3. FINAL CURB & GUTTER REMOVAL AND REPLACEMENT LOCATIONS TO BE DETERMINED IN THE FIELD BY THE ENGINEER.
4. CONTRACTOR SHALL CLOSE HALF OF MAIN PARKING LOT AT A TIME FOR REMOVAL AND RESURFACING ACTIVITIES. THE OTHER HALF OF THE LOT SHALL REMAIN OPEN FOR CUSTOMERS. FULL CLOSURE WILL NOT BE ALLOWED.
5. THE SOUTHEAST LOT MAY NOT BE CLOSED AT THE SAME TIME AS WORK IS OCCURRING IN THE MAIN LOT.
6. ADVANCED NOTICE SIGNAGE AND TRAFFIC MOVEMENT SIGNAGE SHALL BE PROVIDED BY THE CONTRACTOR AND COORDINATED WITH THE VILLAGE. THIS SHALL BE INCIDENTAL TO THE CONTRACT.
7. THERE ARE SEVERAL DATES THAT THE LOT MUST BE 100% AVAILABLE FOR USE (SEE SPECIAL PROVISIONS FOR DETAILS). SCHEDULING AND PARKING LOGISTICS TO BE COORDINATED WITH JEFF DOANE, FACILITIES MANAGER FOR MID-CON HOSPITALITY LLC.
8. THE ACCESS ROAD MUST REMAIN OPEN TO TRAFFIC AT ALL TIMES.
9. BUTT JOINTS ARE INCIDENTAL TO SURFACE REMOVAL.



HOT-MIX ASPHALT MIXTURE REQUIREMENTS - OPTION 1

MIXTURE TYPE	AIR VOIDS @ Ndes
RESURFACING	
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (L-9.5 mm), 2"	4% @ 50 GYR
PATCHING	
CLASS D PATCHES (HMA BINDER IL-19mm), 4"	4% @ 70 GYR

NOTE:

THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIXTURE QUANTITIES IS 112 LBS/SY/IN.

THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG 76-22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64-22" UNLESS MODIFIED BY DISTRICT ONE SPECIAL PROVISIONS. FOR HMA FULL-DEPTH "AC-TYPE" SEE SPECIAL PROVISIONS. FOR USE OF RECYCLED MATERIALS SEE SPECIAL PROVISIONS.

ALL PATCHING OPERATIONS SHALL TAKE PLACE AFTER SURFACE MILLING HAS BEEN COMPLETED.

DATE = 08-21-18	DESIGNED -- JP	REVISED --
SCALE = 1"=60'	CHECKED -- JP	REVISED --
PROJECT NO = 18-RD455	DRAWN -- KWM	REVISED --
FILE NAME = 18RD455-PLAN-03	CHECKED -- AG	REVISED --



CONVENTION CENTER
PARKING LOT IMPROVEMENTS
PAVEMENT PLAN - OPTION 1





VILLAGE
of
TINLEY PARK

SHEET NO.
03 of 05

183RD STREET 20+00

HARLEM AVENUE


LEGEND

-  HOT-MIX ASPHALT SURFACE REMOVAL, 2"
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50, 2"
-  HOT-MIX ASPHALT SURFACE REMOVAL, 4"
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50, 1.75"
HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50, 2.25"
-  B-6.12 COMBINATION CONCRETE CURB AND GUTTER
REMOVAL AND REPLACEMENT
-  A DRAINAGE & UTILITY STRUCTURE
TO BE ADJUSTED



NOTES:

1. ALL PAVEMENT MARKINGS TO BE COMPLETED AS DIRECTED BY THE ENGINEER.
2. FINAL PATCHING LOCATIONS TO BE DETERMINED IN THE FIELD BY THE ENGINEER.
3. FINAL CURB & GUTTER REMOVAL AND REPLACEMENT LOCATIONS TO BE DETERMINED IN THE FIELD BY THE ENGINEER.
4. CONTRACTOR SHALL CLOSE HALF OF MAIN PARKING LOT AT A TIME FOR REMOVAL AND RESURFACING ACTIVITIES. THE OTHER HALF OF THE LOT SHALL REMAIN OPEN FOR CUSTOMERS. FULL CLOSURE WILL NOT BE ALLOWED.
5. THE SOUTHEAST LOT MAY NOT BE CLOSED AT THE SAME TIME AS WORK IS OCCURRING IN THE MAIN LOT.
6. ADVANCED NOTICE SIGNAGE AND TRAFFIC MOVEMENT SIGNAGE SHALL BE PROVIDED BY THE CONTRACTOR AND COORDINATED WITH THE VILLAGE. THIS SHALL BE INCIDENTAL TO THE CONTRACT.
7. THERE ARE SEVERAL DATES THAT THE LOT MUST BE 100% AVAILABLE FOR USE (SEE SPECIAL PROVISIONS FOR DETAILS). SCHEDULING AND PARKING LOGISTICS TO BE COORDINATED WITH JEFF DOANE, FACILITIES MANAGER FOR MID-CON HOSPITALITY LLC.
8. THE ACCESS ROAD MUST REMAIN OPEN TO TRAFFIC AT ALL TIMES.
9. BUTT JOINTS ARE INCIDENTAL TO SURFACE REMOVAL.



HOT-MIX ASPHALT MIXTURE REQUIREMENTS - OPTION 2

MIXTURE TYPE	AIR VOIDS ● Ndes
RESURFACING - MAIN LOT	
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (IL-9.5 mm), 1-1/2"	4% ● 50 GYR
RESURFACING - SOUTHEAST LOT	
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (IL-9.5mm), 1-3/4"	4% ● 50 GYR
HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50, 2-1/4"	4% ● 50 GYR

NOTE:
THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIXTURE QUANTITIES IS 112 LBS/SY/IN.
THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG 78-22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64-22" UNLESS MODIFIED BY DISTRICT ONE SPECIAL PROVISIONS. FOR HMA FULL-DEPTH "AC-TYPE" SEE SPECIAL PROVISIONS. FOR USE OF RECYCLED MATERIALS SEE SPECIAL PROVISIONS.
ALL PATCHING OPERATIONS SHALL TAKE PLACE AFTER SURFACE MILLING HAS BEEN COMPLETED.

DATE = 06-21-18	DESIGNED -- JP	REVISED --
SCALE = 1"=60'	CHECKED -- JP	REVISED --
PROJECT NO = 18-RD455	DRAWN -- KWM	REVISED --
FILE NAME = 18RD455-PLAN-03	CHECKED -- AG	REVISED --



CONVENTION CENTER
PARKING LOT IMPROVEMENTS
PAVEMENT PLAN - OPTION 2

VILLAGE
of
TINLEY PARK

SHEET NO.
04 of 05

163RD STREET

HARLEM

AVENUE


LEGEND

- ① PAVEMENT MARKING LINE, 4" (YELLOW)
- ② 6" WHITE LANE LINE
- ③ 4" YELLOW LANE LINE
- ④ 6" WHITE SKIP DASH LINE (2' LINE, 6' SPACE)
- ⑤ 24" WHITE STOP BAR
- ⑥ PAVEMENT MARKING LETTERS & SYMBOLS
- ⑦ PARKING BLOCKS CONCRETE



NOTE:

- 1. ALL PAVEMENT MARKINGS SHALL CONFORM TO DISTRICT 1 STANDARDS.
- 2. ALL PAVEMENT MARKINGS SHALL BE PAINT AND APPLIED IN TWO PASSES, WHICH IS REFLECTED IN THE OVERALL QUANTITY, FOR EACH PAY ITEM.
- 3. CONTRACTOR TO ADD PARKING BLOCKS AS DIRECTED IN THE FIELD.



DATE	= 06-21-18	DESIGNED	= JP	REVISED	=
SCALE	= 1"=60'	CHECKED	= JP	REVISED	=
PROJECT NO	= 18-PD455	DRAWN	= KWM	REVISED	=
FILE NAME	= 18PD455-PLAN-03	CHECKED	= AG	REVISED	=



CONVENTION CENTER
PARKING LOT IMPROVEMENTS
PAVEMENT MARKING & SIGNING

VILLAGE
of
TINLEY PARK

SHEET NO.
05 of 05