



CALTRAIN ELECTRIFICATION UPDATE

Burlingame Community Meeting February 3, 2021






AGENDA

- Caltrain System Overview
- Project Overview
- Burlingame Construction Activities
- Questions





CALTRAIN SYSTEM



- 31 Stations Gilroy to San Francisco
- 68 Weekday Trains
- At-Grade Crossings, Viaducts, and Bridges
- Intermodal Connections
- Bike Commuters






PROJECT DESCRIPTION

Project Area



- 51 miles
- San Francisco to San Jose (Tamien Station)

Project Elements



Electrification

- Overhead Contact System (OCS)
- Traction Power Facilities

Electric Trains*

- 19 7-car train sets
- 133 electric cars

*Includes 2018 State TIRCP Funding





PROJECT DESCRIPTION

Service Elements



Speed

Up to 79 mph



Service Increase

- 6 trains / hour / direction
- More station stops / reduced travel time
- Restore Broadway service



Mixed-fleet Service (interim period)

Continue Tenant Service

 ACE, Capitol Corridor, Amtrak, Freight





PROJECT BENEFITS



Improved Train
Performance,
Increased Service
and Greater Capacity



Improved Regional Air Quality and Reduced Greenhouse Gas Emissions



Positive Economic Benefits for the Region



Reduced Engine
Noise Emanating
from Trains




Increased Revenue and Reduced Fuel Cost





SCHEDULE




* Note: Schedule subject to change





CONSTRUCTION PHASING




- 51 Miles Corridor
- 4 Work Segments
- 2,600 Poles
- 10 Traction Power Facilities







BURLINGAME







FIELD WORK PROGRESSION

| Work Completed | Utility Survey Geotechnical Investigations Disposal of Soil from Geotechnical Investigations Soil Resistivity Testing Site Surveys Signal Cable Inspections |
|------------------|--|
| Work In Progress | Tree Pruning/Removal Potholing Foundation Installation Pole and Wire Installation |
| Future Work | Paralleling Station Construction |





FUTURE CONSTRUCTION

Burlingame

| Date | Work Activity | Expected Completion* |
|---------------|----------------------------------|----------------------|
| In Progress | Tree Pruning/Removal | Summer 2021 |
| In Progress | Potholing | Summer 2021 |
| In Progress | Foundation Installation | Fall 2021 |
| In Progress | Pole Installation | Fall 2021 |
| In Progress | Wire Installation | Fall 2021 |
| February 2020 | Paralleling Station Construction | Fall 2021 |






FOUNDATION CONSTRUCTION


- Excavation
- Rebar and Anchor Installation
- Electrical Grounding
- Concrete Fill





FOUNDATION INSTALLATION









POLE INFORMATION

- 2,600 Installed throughout Corridor
 - Approx. 139 poles in Burlingame
- Pole Height: 30-50'
- Pole Spacing: ~180' apart





POLE TYPES BURLINGAME



Single Track Cantilever



Two Track Cantilever



Portal





POLE INSTALLATION







STRINGING WIRE








TRACTION POWER FACILITIES

- 10 Traction Power Facilities Installed throughout Corridor
 - 1 Paralleling Station installed in Burlingame
 - Gantry structures up to 63'
 - Accommodates future elevated track as part of Broadway Grade Separation
 Project
- Provides electrical power to trains through the Overhead Contact System
- Unmanned station
- Day and weekend construction work
- Limited night work during construction





PARALLELING STATION LOCATION







PARALLELING STATION LAYOUT







PARALLELING STATION EXAMPLE



Paralleling Station - Amtrak Northeast Corridor





GANTRIES EXAMPLE



Main Gantry - San Mateo



Strain Gantry - Palo Alto






CONSTRUCTION INFORMATION

- Work will occur during day and night
- Some 24-hour weekend work
- Crews will utilize acoustical barrier blankets and position lights away from homes
- Dedicated hotline for construction complaints





PUBLIC OUTREACH



Cal Mod

CALTRAIN MODERNIZATION PROGRAM

Test Pile Construction Activities

DAY TIME WORK

08/28/17 - 09/1/17

ANTICIPATED WORK HOURS 7:00 a.m. - 5:00 p.m.

CREWS CONDUCTING WORK IN YOUR AREA TO INSTALL AND TEST FOUNDATION PILES

During the week of August 28, Caltrain electrification crews will be working in your area to construct one test pile foundation for integrity testing. The piles will be installed within the Caltrain right-of-way.

Crews will be conducting the work over a two day period between Monday, August 28 and Friday, September 1, between the hours of 7 a.m. and 5 p.m. Crews will return at a later date to test the integrity of the installed piles.

Main construction activities include:


- Survey and layout of proposed pile test location
- Trucks and equipment working near Caltrain right of way
- Drill holes for placement of test piles
- · Pour concrete and install rebar
- · Backfill holes to cover work areas


We spologize for any inconvenience this may cause. The field team will work as quietly as possible. Thank you for your patience and understanding as we deliver these critical benefits to our communities.

Please visit our website at www.caltrain.com/PCEPconstruction to sign-up for weekly construction updates.

We appreciate your patience during construction.







Factsheet



Postcard



Public Meeting





PUBLIC OUTREACH

- Subscribe to Weekly Updates
 - Visit www.calmod.org/get-involved
- Social Media
- Construction Outreach Office





CALMOD CONTACT INFORMATION

WEEKLY UPDATES (a) CalMod.org/get-involved

EMAIL ② CalMod@caltrain.com

PHONE (650-399-9659 800-660-4287 (Toll Free)

WEBSITE @ CalMod.org

FACEBOOK () www.facebook.com/caltrain

TWITTER ② @caltrain

