

Place the following notes on the soil erosion control plan:

- ALL SOIL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL COMPLY WITH ARTICLE 2 OF CITY OF KENTWOOD ORDINANCE 78 AND PART 91 OF PUBLIC ACT 451.
- ALL SOIL EROSION AND SEDIMENT CONTROLS SHALL BE INSPECTED AND MAINTAINED ON A DAILY BASIS AND IMMEDIATELY FOLLOWING EVERY SIGNIFICANT RAINFALL EVENT.
- ALL EXCESS SPOILS ARE TO BE REMOVED FROM THE SITE. OTHERWISE, STOCKPILES MUST BE PROVIDED WITH TEMPORARY AND PERMANENT STABILIZATION MEASURES.
- EXCESS DIRT IS NOT TO BE PLACED ON ANY AREAS ON OR ADJACENT TO THE SITE WHERE THE PLAN DOES NOT SHOW THE AREA BEING DISTURBED.
- SILT FENCING IS REQUIRED ALONG ALL DOWNSTREAM EDGES OF THE GRADING LIMITS AND MUST REMAIN IN PLACE UNTIL VEGETATION IS UNIFORMLY RE-ESTABLISHED. THE SILT FENCE MUST BE TOED IN A MINIMUM OF 6 INCHES ALONG ITS BASE.
- ALL DISTURBED BANKS EQUAL TO OR GREATER THAN 4:1 AND THE DETENTION BASIN BANKS AND BOTTOM MUST BE COVERED WITH TOPSOIL, SEED AND NORTH AMERICAN GREEN S-150 (OR APPROVED EQUAL) EROSION CONTROL BLANKET. THIS BLANKET, ALONG WITH THE NECESSARY STAPLES OR WOOD PEGS, SHALL BE PLACED PER MANUFACTURER'S RECOMMENDATIONS. SEAMS SHALL BE PLACED PARALLEL TO THE DIRECTION OF SURFACE RUNOFF.
- ALL SOIL EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY EARTH MOVING OPERATIONS, AND SHALL BE MAINTAINED UNTIL VEGETATION IS UNIFORMLY RE-ESTABLISHED AND THE SITE IS PERMANENTLY STABILIZED.
- NO SEDIMENT SHALL BE TRACKED ONTO THE ADJACENT PUBLIC STREET AND IF IT DOES OCCUR, IT SHALL BE CLEANED DAILY.