




Public Works Division



Our Mission


The Mission of Waste Management Services Department (WMSD) is "to properly operate and maintain the collection system infrastructure, transporting and treating wastewater without disruption or overflows, while meeting the needs of Waterloo's citizens, protecting surface and groundwater resources and complying with all Federal and State regulations."



Major Accomplishments

- ✓ Completion of Wing Dike Project. Through Legal Appeal the IDNR agreed to reinstate previous Waste Load Allocation of Permit Limits.
- Satellite Wet Well Project continues. Crossover Structure on Lafayette near completion.
- ✓ Dry Run Creek Interceptor and Lift Station work continues. Completion scheduled March 2021.
- ✓ Biosolids Contract #994 construction at full steam. Currently at 40% completion.
- ✓ Discussions continuing with City of Evansdale on acceptance of wastewater flow.
- ✓ Digester #3 Cover Modifications Contract #1021 at 90% Complete. Full completion expected 5/1/2021
- ✓ Cleaned and replaced all Aeration Membranes in Easton Aeration Basin 3. This meets our schedule of cleaning and replacing membranes of one basin per year/next 4 years. Easton Aeration Basin 4 will be rebuilt 2021
- ✓ CIPP Phase IVA work complete in November 2020.
- ✓ Titus Lift Station and Force Main design work underway and expected to be bid in summer 2021.
- ✓ In-house Smoke Testing in September and October 2020 to identify deficiencies in the W. 4th St and Russell Rd and Cedar River areas, including discovery and repair of a hole in a 48" line along the river.
- ✓ Removal of 16 Storm Sewer Cross-Connects from the sanitary system in 2020.
- ✓ Phase II West Side Interceptor Manhole Inspections complete in May 2020.
- ✓ Large diameter sanitary sewer cleaning: 3200' in SA 14 and 1400' in SA 19


WMS Enterprise Funded



Sanitary	\$9,402,917
Storm	\$691,310
Total	\$10,094,227



Sanitary Sewer Budget





Budget for Chemicals

		PRICE PER			
CHEMICALS	VENDOR	LOAD	ANNUAL LOADS	UNITS	ANNUAL COST \$
Magnesium Hydroxide	Brentag	\$9,302	10	\$0.19/lb	\$83,718
Polly Aluminum Chloride	Rhino	\$9,570	3	\$0.21/lb	\$38,280
Polymer For Thickeners and Filter Bld	Rhino	\$28,880	8	8,800 lb	\$173,280
Struvite Removal	Guard	\$18,675	2	1,375 Gallons	\$37,350
Incidental Chemicals De-Foamers Etc	Rhino	2,000	2	50 Gallons	\$4,000
					\$336,628

History				
FY	Cost			
FY14	\$334,627			
FY15	\$290,375			
FY16	\$252,669			
FY17	\$396,341			
FY18	\$358,517			
FY19	\$330,000			
FY20 (projected)	\$340,000			

2020 Sanitary Sewer Cleaning

- Sewer Maintenance cleaned 45 miles
 - Additional 1 mile cleaned in CIPP Phase IVA
- Reached 60% of CMOM Program Annual Goal to clean entire system every 5 years.



- * large dia. cleaning projects
- *June/July rain events
- *restrictions due to COVID-19



2020 Sanitary Sewer Televising


- Sewer Maintenance televised 27 miles
 - Additional 1 mile televised in CIPP Phase IVA
- 80% of CMOM Program Annual Goal to inspect entire system every 10 years.





2020 Smoke Testing

- Sewer Mtce and CMOM Staff performed smoke testing to identify sources of I/I in targeted areas:
 - West 4th Street and Russell Road
 - Cedar River
- Inspected 5.4 miles of sanitary sewer
- Discovered and repaired hole in 48" line
- Identified 30 potential sources of inflow



Smoke Test Setup

West 4th Street and Russell Road



Storm Sewer Budget





Storm Water Work 4/1/2019 - 3/31/2020

- 8,759 ft Storm Pipe Televised
- 9,094 ft Storm Pipe Cleaned
- 1,100 Catch Basins Cleaned
- 23 Catch Basins Repaired/Replaced
- 8 Culverts Cleaned
- 11 Waterways Cleaned
- 6 Trash Racks cleaned
- 97 Flood Gates Maintained




DNR Events

SSO, Basement Backups, Bypassing


Year	Total DNR Events(SSO, Basement Backup, Bypass)	Root Related	Root %	Rains Related	Rains %	FOG Related	FOG %	Other (Deposits, Debris, Power Fail, Structural, etc.)	Other %
2014	52	11	21%	34	65%	1	2%	6	12%
2015	19	9	47%	6	32%	2	10.5%	2	10.5%
2016	25	10	40%	14	56%	0	0%	1	4%
2017	16	7	44%	0	0%	1	6%	8	50%
2018	137	14	10%	122	89%	0	0%	1	1%
2019	42	4	90%	25	60%	2	5%	11	26%
2020	158	6	4%	145	92%	2	1%	5	3%
Total	449	61	14%	346	77%	8	1%	34	8%



Total WMS Budget Breakdown



Percentages by Fund



Categories	Sanitary		Storm		Total		
Salaries	\$3,398,318		\$648,839		\$4,047,157	40.0%	
Contracted Services	\$2,400,505		\$1,421		\$2,401,926	23.8%	
Commodities	\$1,186,250		\$41,050		\$1,227,300	12.2%	
Capital Outlay	\$2,417,844		\$0		\$2,417,844	24.0%	
	\$9,402,917	93.0%	\$691,310	7.0%	\$10,094,227		